

CP

UTAH OIL AND GAS CONSERVATION COMMISSION

m

REMARKS WELL LOG ELECTRIC LOGS ☒ X WATER SANDS LOCATION INSPECTED SUB. REPORT/abd.

940101 Commenced In Section eff. 4-19-94

DATE FILED 10-24-83
LAND: FEE & PATENTED STATE LEASE NO. PUBLIC LEASE NO. U-16535 INDIAN

DRILLING APPROVED 10-28-83 - OIL

SPUDDED IN: 2-28-84

COMPLETED: 4-19-84 POW PUT TO PRODUCING: 4-19-84

INITIAL PRODUCTION: 35 BOPD, 139 MCF

GRAVITY API 34°

GOR: 3963/1

PRODUCING ZONES: 5024'-5043' Green River (GRAN)

TOTAL DEPTH: 6400'

WELL ELEVATION: 5600' GR

DATE ABANDONED:

FIELD: ~~UNDESIGNATED~~ monument Butte

UNIT:

COUNTY: DUCHESNE

WELL NO. MONUMENT FEDERAL 8-34

API #43-013-30843

LOCATION 2059' FNL FT. FROM (N) (S) LINE, 701' FEL

FT. FROM (E) (W) LINE

SENE

1/4 - 1/4 SEC. 34

TWP.	RGE.	SEC.	OPERATOR	TWP.	RGE.	SEC.	OPERATOR
				8S	16E	34	LOMAX EXPLORATION CO.

QUATERNARY	Star Point	Chinle	Molas
Alluvium	Wahweap	Shinarump	Manning Canyon
Lake beds	Masuk	Moenkopi	Mississippian
Pleistocene	Colorado	Sinbad	Humburg
Lake beds	Sego	PERMIAN	Brazer
TERTIARY	Buck Tongue	Kaibab	Pilot Shale
Pliocene	Castlegate	Coconino	Madison
Salt Lake	Mancos	Cutler	Leadville
Oligocene	Upper	Hoskinnini	Redwall
Norwood	Middle	DeChelly	DEVONIAN
Eocene	Lower	White Rim	Upper
Duchesne River	Emery	Organ Rock	Middle
Uinta	Blue Gate	Cedar Mesa	Lower
Bridger	Ferron	Halgaite Tongue	Ouray
Green River	Frontier	Phosphoria	Elbert
Garden Gulch 4600'	Dakota	Park City	McCracken
Douglas Creek 5021'	Burro Canyon	Rico (Goodridge)	Aneth
Black S F 5944'	Cedar Mountain	Supai	Simonson Dolomite
	Buckhorn	Wolfcamp	Sevy Dolomite
	JURASSIC	CARBON I FEROUS	North Point
Wasatch	Morrison	Pennsylvanian	SILURIAN
Stone Cabin	Salt Wash	Oquirrh	Laketown Dolomite
Colton	San Rafael Gr.	Weber	ORDOVICIAN
Flagstaff	Summerville	Morgan	Eureka Quartzite
North Horn	Bluff Sandstone	Hermosa	Pogonip Limestone
Almy	Curtis		CAMBRIAN
Paleocene	Entrada	Pardox	Lynch
Current Creek	Moab Tongue	Ismay	Bowman
North Horn	Carmel	Desert Creek	Tapeats
CRETACEOUS	Glen Canyon Gr.	Akah	Ophir
Montana	Navajo	Barker Creek	Tintic
Mesaverde	Kayenta		PRE - CAMBRIAN
Price River	Wingate	Cane Creek	
Blackhawk	TRIASSIC		

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

DIVISION OF

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. TYPE OF WORK

DRILL ☒

DEEPEN ☐

PLUG BACK ☐

b. TYPE OF WELL

OIL WELL ☒

GAS WELL ☐

OTHER

SINGLE ZONE ☐

MULTIPLE ZONE ☐

2. NAME OF OPERATOR

Lomax Exploration Company

3. ADDRESS OF OPERATOR

P.O. Box 4503, Houston, Texas 77210

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)*

At surface

701' FEL & 2059' FNL SE/NE

At proposed prod. zone

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*

11 miles South of Myton, Utah

15. DISTANCE FROM PROPOSED*

LOCATION TO NEAREST
PROPERTY OR LEASE LINE, FT.
(Also to nearest drig. unit line, if any)

2024

16. NO. OF ACRES IN LEASE

1280 ✓

17. NO. OF ACRES ASSIGNED
TO THIS WELL

40 ✓

18. DISTANCE FROM PROPOSED LOCATION*

TO NEAREST WELL, DRILLING, COMPLETED,
OR APPLIED FOR, ON THIS LEASE, FT.

1321

19. PROPOSED DEPTH

5700 ✓

20. ROTARY OR CABLE TOOLS

Rotary

21. ELEVATIONS (Show whether DF, RT, GR, etc.)

5600' GR

22. APPROX. DATE WORK WILL START*

January, 1984

23.

PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12 1/4	8 5/8	24	300	To Surface
7 7/8	5 1/2	17	TD	As Required

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24.

SIGNED

G. L. Pruitt

TITLE V.P. Drilling & Production

DATE 10/21/83

(This space for Federal or State office use)

PERMIT NO.

APPROVAL DATE

APPROVED BY

TITLE

DATE


CONDITIONS OF APPROVAL, IF ANY:

10-23-83
M

T 8 S, R 16 E, S.L.B.&M.

PROJECT
LOMAX EXPLORATION

Well location, **MONUMENT**
FED. #8-34, located as shown
in the SE1/4 NE1/4 Section 34,
T8S, R16E, S.L.B.&M. Duchesne
County, Utah.



CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM
FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY
SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE
BEST OF MY KNOWLEDGE AND BELIEF.

Robert L. Kay
REGISTERED LAND SURVEYOR
REGISTRATION NO 5709
STATE OF UTAH

UINTAH ENGINEERING & LAND SURVEYING
P.O. BOX Q - 85 SOUTH - 200 EAST
VERNAL, UTAH - 84078

SCALE 1" = 1000'	DATE 10/17/83
PARTY R.K. J.F. S.B.	REFERENCES GLO Plat
WEATHER Cool	FILE LOMAX

X = Section Corners Located

TEN POINT WELL PROGRAM

LOMAX EXPLORATION COMPANY
Monument Federal #8-34
SE/NE Section 34, T8S, R16E
Duchesne County, Utah

1. GEOLOGIC SURFACE FORMATION:

Uinta formation of Upper Eocene Age

2. ESTIMATED TOPS OF IMPORTANT GEOLOGIC MARKERS:

Uinta	0 - 3050
Green River	3050
Wasatch	6090 ✓

3. ESTIMATED DEPTHS OF ANTICIPATED WATER, OIL, GAS OR MINERALS:

Green River	5000	-	Oil
-------------	------	---	-----

4. PROPOSED CASING PROGRAM:

8 5/8", J-55, 24#; set at 300'
5 1/2", J-55, 17#; set at TD
All casing will be new

5. MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL:

The operators minimum specifications for pressure control equipment are as follows:

A 10" Series 900 Hydril Bag type BOP and a 10" Double Ram Hydraulic unit with a closing unit will be utilized. Pressure tests of BOP's to 1000# will be made prior to drilling surface plug and operation will be checked daily. (See exhibit A)

6. TYPE AND CHARACTERISTICS OF THE PROPOSED CIRCULATION MUDS:

It is proposed that the hole be drilled with fresh water to the "J" zone and with mud thereafter. The mud system will be a water based gel-chemical, weighted to 10.0 ppg as necessary for gas control.

LOMAX EXPLORATION COMPANY
Monument Federal #8-84
SE/NE Section 34, T8S, R16E
Duchesne County, Utah

7. AUXILIARY SAFETY EQUIPMENT TO BE USED:

Auxiliary safety equipment will be a Kelly Cock, bit float, and a TIW valve with drill pipe threads.

8. TESTING, LOGGING AND CORING PROGRAMS:

No coring or drill stem testing has been scheduled for this well. The logging will consist of a Dual Induction Laterolog and a Compensated Neutron-Formation Density.

9. ANTICIPATED ABNORMAL PRESSURE OR TEMPERATURE:

It is not anticipated that abnormal pressures or temperatures will be encountered; nor that any other abnormal hazards such as H₂S gas will be encountered in this area.

10. ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS:

It is anticipated that operations will commence approximately January, 1984.

LOMAX EXPLORATION
13 Point Surface Use Plan
For
Well Location
Monument Federal #8-34
Located In
Section 34, T8S, R16E, S.L.B. & M.
Duchesne County, Utah

1. EXISTING ROADS

See attached Topographic Map "A".

To reach LOMAX EXPLORATION well location site Monument Federal #8-34, located in the SE 1/4 NE 1/4 Section 34, T8S, R16E, S.L.B. & M., Duchesne County, Utah:

Proceed Westerly out of Myton, Utah along U.S. Highway 40 - 1.6 miles to the Junction of this Highway and Utah State Highway 53; proceed Southerly direction along Utah State Highway 53 - 1.6 miles to its junction with Utah State Highway 216; proceed Southerly along State Highway 216 - 4.7 miles to its junction with an existing dirt road to the Southwest; proceed Southwesterly along this road 2.9 miles to its junction with an existing dirt road to the Southeast; proceed Southeasterly along this road 0.5 miles to the beginning of the proposed access road to be discussed in item #2.

The highways mentioned in the foregoing paragraph are bituminous surfaced roads to a point 4.5 miles South on Highway 216; thereafter the roads are constructed with existing materials and gravels. The highways are maintained by Utah State road crews. All other roads are maintained by County crews.

The aforementioned dirt oil field service roads and other roads in the vicinity are constructed out of existing native materials that are prevalent to the existing areas they are located in, and range from clays to a sandy-clay shale material.

The roads that are required for access during the drilling phase, completion phase, and production phase of this well will be maintained at the standards required by the B.L.M. or other controlling agencies. This maintenance will consist of some minor grader work for smoothing of road surfaces and for snow removal.

2. PLANNED ACCESS ROAD

See Topographic Map "B".

The planned access road leaves the existing location described in Item #1 in the SE 1/4 NE 1/4 Section 34, T8S, R16E, S.L.B. & M., and proceeds in a Easterly direction approximately 100' \pm to the proposed location site.

The proposed access road will be an 18' crown road (9' either side of the centerline) with drain ditches along either side of the proposed road where it is determined necessary in order to handle any run-off from normal meterological conditions that are prevalent to this area.

Back slopes along the cut areas of the road will be 1 1/2 to 1 slopes and terraced.

There will be no culverts required along this access road.

There are no fences encountered along this proposed road. There will be no new gates or cattleguards required.

There will be no turnouts required along this road.

3. LOCATION OF EXISTING WELLS

There are seven known existing producing wells within a one mile radius of this location site. (See Topographic Map "B").

There are no known water wells, abandoned wells, injection wells, monitoring or observation wells for other resources within a one-mile radius of this location site.

4. LOCATION OF EXISTING AND PROPOSED FACILITIES

There are eight existing LOMAX EXPLORATION wells within a one mile radius of this location site.

A tank battery site will be set at the proposed location site. This battery will be used to contain production from this well. If in the event this battery can not be improvised, a flowline will be built which will extend to an existing well in the area.

The area will be built if possible, with native materials and if these materials are not available then the necessary arrangements will be made to get them from private sources. These facilities will be constructed using bulldozers, graders and workman crews to construct and place the proposed facilities. If there is any deviation from the above, all appropriate agencies will be notified. Rehabilitation of disturbed areas no longer needed for operation after construction is completed will meet the requirements of Item #10.

5. LOCATION AND TYPE OF WATER SUPPLY

See Topographic Map "B".

At the present time, it is anticipated that the water for this well will be hauled by truck from a private water source that is indicated on Topo. Map "A".

In the event that this source is not used, an alternate source will be used and all necessary arrangements will be made with the proper authorities.

There will be no water well drilled at this location site.

6. SOURCE OF CONSTRUCTION MATERIALS

All construction material for this location site and access road shall be borrow material accumulated during construction of the location site and access road. No pit lining materials from other sources are anticipated at this time, but if they are required, the appropriate actions will be taken to acquire them from private sources.

7. METHOD OF HANDLING WASTE DISPOSAL

See Location Layout Sheet.

A reserve pit will be constructed.

The reserve pit will vary in size and depth according to the water table at the time drilling.

One half of the reserve pit will be used as a fresh water storage area during the drilling of this well and the other one half will be used to store non-flammable materials such as cuttings, salts, drilling fluids, chemicals and produced fluids, etc.

If deemed necessary by the agencies concerned to prevent contamination to surrounding areas, the reserve pits will be lined with a gel.

The pits will have wire and overhead flagging installed if deemed necessary to protect the water fowl, wildlife, and domestic animals.

At the onset of drilling, the reserve pit will be fenced on three sides and at the time drilling activities are completed, it will be fenced on the fourth side and allowed to dry completely prior to the time that backfilling and other reclamation activities are attempted.

When the reserve pit dries and reclamation activities commence, the pits will be covered with a minimum of four feet of soil and all requirements in Item #10 will be followed.

A portable chemical toilet will be provided for human waste.

8. ANCILLARY FACILITIES

There are no ancillary facilities planned for at the present time and none foreseen in the near future.

9. WELL SITE LAYOUT

See attached Location Layout Sheet.

The B.L.M. District Manager shall be notified before any construction begins on the proposed location site.

As mentioned in Item #7, the pits will be unlined unless it is determined by the representatives of the agencies involved that the materials are too porous and would cause contamination to the surrounding area; then the pits will be lined with a gel and any other type of material necessary to make them safe and tight.

When drilling activities commence, all work shall proceed in a neat and orderly sequence.

10. PLANS FOR RESTORATION OF SURFACE

As there is some topsoil on the location site, it shall be stripped and stockpiled. (See Location Layout Sheet). When all drilling and production activities have been completed, the location site and access road will be reshaped to the original contour and stockpiled topsoil spread over the disturbed area.

Any drainages re-routed during construction activities shall be restored to their original line of flow as near as possible. Fences around pits are to be removed upon completion of drilling activities and all waste being contained in the trash basket shall be hauled to the nearest Sanitary Landfill.

Restoration activities shall begin within 90 days after completion of the well. Once restoration activities have begun, they shall be completed within 30 days.

When restoration activities have been completed, the location site shall be reseeded with a seed mixture recommended by the surface owner when the moisture content of the soil is adequate for germination. The Lessee further covenants and agrees that all of said clean-up and restoration activities shall be done and performed in a diligent and most workmanlike manner and in strict conformity with the above mentioned Items #7 and #10.

11. OTHER INFORMATION

The Topography of the General Area - (See Topographic Map "A").

The area is a large basin formed by the Uinta Mountains to the North and the Book Cliff Mountains to the South. The Green River is located approximately 23 miles to the South of the location site.

The basin floor is interlaced with numerous canyons and ridges formed by the non-perennial streams of the area. The sides of these canyons are steep and ledges formed in sandstone ledges, conglomerate deposits, and shale are common in this area.

The geologic structures of the area that are visible are of the Uinta formation (Eocene Epoch) Tertiary Period in the upper elevations and the cobblestone and younger alluvial deposits from the Quaternary Period.

Outcrops of sandstone ledges, conglomerate deposits and shale are common in this area.

The topsoils in the area range from a light brownish-gray sandy clay (SK-KL) type soil with poorly graded gravels to a clayey (OL) soil.

The majority of the numerous washes and draws in the area are of non-perennial nature flowing during the early spring run-off and heavy rain storms of long duration which are rare as the normal annual rainfall in the area is only 8".

Due to the low precipitation average, climatic conditions and the marginal types of soils, the vegetation that is found in the area is common of the semi-arid regions and consists of areas of sagebrush, rabbitbrush some grasses and cacti, on the upper benches with cottonwoods, beach, willows, Russian Olives, and grasses along the lower levels close to the wet areas and streams.

The fauna of the area consists predominantly of the mule deer, pronghorn antelope, coyotes, rabbits and varieties of small ground squirrels and other types of rodents. The area is used by man for the primary purpose of grazing domestic livestock.

The birds of the area are raptors, finches, ground sparrows, magpies, crows, and jays.

The Topography of the Immediate Area - (See Topographic Map "B")

Monument Federal #8-34 is located approximately 3.0 miles North of Castle Peak Draw, and 1.0 miles Southeast of Wells Draw, non-perennial drainages which runs to the North East, and drain into the Green River.

The terrain in the vicinity of the location slopes from the South through the location site to the North at approximately 5% grade.

The vegetation in the immediate area surrounding the location site consists of sparse amounts of sagebrush and grassed, with large areas devoid of vegetation.

There are no occupied dwellings or other facilities of this nature in the general area.

There are no visible archeological, historical or cultural sites within any reasonable proximity of the proposed location site. (See Topographic Map "B".)

There are no historical, or cultural sites within any reasonable proximity of the proposed location site.

12. LESSEE'S OR OPERATOR'S REPRESENTATIVE

Jack Pruitt
LOMAX EXPLORATION
P.O. Box 4503
Houston, TX 77210-4503
1-713-931-9276



13. CERTIFICATION

I hereby certify that I, or persons under my direct supervision have inspected the proposed drill site and access route; that I am familiar with the conditions which presently exist; that the statements made in this plan are to the best of my knowledge true and correct; and that the work associated with the operation proposed herein will be performed by LOMAX EXPLORATION and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved.


Date

10/21/83

Jack Pruitt




Shaffer Spherical
10" 900



Cameron Space Saver

10" 900

Collinghead




LOMAX EXPLORATION CO.

MONUMENT FED. #8-34


LOCATION LAYOUT & CUT SHEET

SCALE 1" = 50'






SOILS LITHOLOGY

- No Scale -



C
R
O
S
S
S
E
C
T
I
O
N



Scales

1" = 50'

APPROXIMATE YARDAGES

Cubic Yards Cut - 4,880

Cubic Yards Fill - 493

MONUMENT FED. #8-34
PROPOSED LOCATION


TOPO.

MAP "A"

SCALE 1" = 4 MI.

Water Source

PROPOSED LOCATION



PROPOSED	LOCATION
1	1
2	2
3	3
4	4
5	5
6	6
7	7
8	8
9	9
10	10
11	11
12	12
13	13
14	14
15	15
16	16
17	17
18	18
19	19
20	20
21	21
22	22
23	23
24	24
25	25
26	26
27	27
28	28
29	29
30	30
31	31
32	32
33	33
34	34
35	35
36	36
37	37
38	38
39	39
40	40
41	41
42	42
43	43
44	44
45	45
46	46
47	47
48	48
49	49
50	50
51	51
52	52
53	53
54	54
55	55
56	56
57	57
58	58
59	59
60	60
61	61
62	62
63	63
64	64
65	65
66	66
67	67
68	68
69	69
70	70
71	71
72	72
73	73
74	74
75	75
76	76
77	77
78	78
79	79
80	80
81	81
82	82
83	83
84	84
85	85
86	86
87	87
88	88
89	89
90	90
91	91
92	92
93	93
94	94
95	95
96	96
97	97
98	98
99	99
100	100

MAP "B"

SCALE 1" = 2000'

ROAD CLASSIFICATION

Light duty road, all weather, improved surface	Unimproved road fair or dry weather
---	--


UTAH

QUADRANGLE LOCATION

PROPOSED ACCESS ROAD 100' ±

T85
T95

PROPOSED LOCATION




PROPOSED ACCESS ROAD 100' ±

PROPOSED LOCATION
MONUMENT FED. # 8-34

T8S
T9S

October 21, 1983



Chief, Branch of Fluid Minerals,
Utah State Office, B.L.M.
136 East South Temple
Salt Lake City, Utah 84111

DIVISION OF
OIL, GAS & MINING

Lomax Exploration Company
APD/NTL-6 Transmittal

Gentlemen:

Enclosed are APD/NTL-6's for the following wells:

Monument Federal #8-34, SE/NE S34, T8S, R16E, Duchesne County

Pariette Ute Tribal #9-34, NE/SE S34, T4S, R2E, Uintah County

It is requested that a copy of the approval be mailed to Lomax's
Roosevelt office at P.O. Box 1446, Roosevelt, Utah 84066.

Please advise if you need additional information.

Very truly yours,

A handwritten signature in cursive script that reads "Michele Tisdell".

Michele Tisdell
Sec., V.P. Drilling & Production

MT
Enclosures (8)

cc: State of Utah
Division of Oil and Gas
4241 State Office Building
Salt Lake City, Utah 84114

Bureau of Land Management
170 South 500 East
Vernal, Utah 84078

333 North Belt East • Suite 880 • Houston, Texas 77060 • 713/931-9276
Mailing Address: P.O. Box 4503 • Houston, Texas 77210-4503

District Office: 248 North Union • Roosevelt, Utah 84066
Mailing Address: P.O. Box 1446 • Roosevelt, Utah 84066

OPERATOR

Lomax Exploration

DATE

10-26-83

WELL NAME

Monument Fed 8-34

SEC

SE NE 34

T

85

R

16E

COUNTY

Duchesne

43-013-30843

API NUMBER

Fed.

TYPE OF LEASE

POSTING CHECK OFF:

☐

INDEX

☐

MAP

☐

HL

☐

NID

☐☐

PI

PROCESSING COMMENTS:

NO OIL WELLS WITHIN 1000'WATER PERMIT # 57707 (47-1675)APPROVED BY THE STATE
OF UTAH DIVISION OF
OIL, GAS, AND MININGDATE: 10-28-83BY: [Signature]

CHIEF PETROLEUM ENGINEER REVIEW:

APPROVAL LETTER:

SPACING:

☐

A-3

UNIT

☐

c-3-a

CAUSE NO. & DATE

☒

c-3-b

☐

c-3-c

SPECIAL LANGUAGE:

☒ RECONCILE WELL NAME AND LOCATION ON APD AGAINST SAME DATA ON PLAT MAP.

☒ AUTHENTICATE LEASE AND OPERATOR INFORMATION

☒ VERIFY ADEQUATE AND PROPER BONDING *FED*

☒ AUTHENTICATE IF SITE IS IN A NAMED FIELD, ETC.

☐ APPLY SPACING CONSIDERATION

☐ ORDER *NO*

☐ UNIT *NO*

☒ c-3-b

☐ c-3-c

☒ CHECK DISTANCE TO NEAREST WELL.

☒ CHECK OUTSTANDING OR OVERDUE REPORTS FOR OPERATOR'S OTHER WELLS.

☒ IF POTASH DESIGNATED AREA, SPECIAL LANGUAGE ON APPROVAL LETTER

☒ IF IN OIL SHALE DESIGNATED AREA, SPECIAL APPROVAL LANGUAGE.

October 28, 1983

Lomax Exploration Company
P. O. Box 4503
Houston, Texas 77210

RE: Well No. Monument Fed. 8-34
SENE Sec. 34, T. 8S, R. 18E
2059' FHL, 701' FEL
Duchesne County, Utah

Gentlemen:

Insofar as this office is concerned, approval to drill the above referred to oil well is hereby granted in accordance with Rule C-3(b), General Rules and Regulations and Rules of Practice and Procedure. Prior to spudding, a copy of the Utah Division of Water Rights (Phone No. 801-533-6071) approval for use or purchase of drilling water must be submitted to this office, otherwise this approval is void.

Should you determine that it will be necessary to plug and abandon this well, you are hereby requested to immediately notify the following:

RONALD J. FIRTH - Chief Petroleum Engineer
Office: 533-5771
Home: 571-6068

Enclosed please find Form OGC-8-X, which is to be completed whether or not water sands (aquifers) are encountered during drilling. Your cooperation in completing this form will be appreciated.

Further, it is requested that this Division be notified within 24 hours after drilling operations commence, and that the drilling contractor and rig number be identified.

The API number assigned to this well is 43-013-30843.

Sincerely,

Norman C. Stout
Administrative Assistant

NCS/as
cc: Branch of Fluid Minerals
Encl.

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. TYPE OF WORK

DRILL ☒DEEPEN ☐PLUG BACK ☐

b. TYPE OF WELL

OIL
WELL ☒GAS
WELL ☐

OTHER

SINGLE
ZONE ☐MULTIPLE
ZONE ☐

2. NAME OF OPERATOR

Lomax Exploration Company

3. ADDRESS OF OPERATOR

P.O. Box 4503, Houston, Texas 77210

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.*)

At surface

701' FEL & 2059' FNL SE/NE

At proposed prod. zone

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*

11 miles South of Myton, Utah

15. DISTANCE FROM PROPOSED*

LOCATION TO NEAREST

PROPERTY OR LEASE LINE, FT.

(Also to nearest drig. unit line, if any)

2024

16. NO. OF ACRES IN LEASE

1280

17. NO. OF ACRES ASSIGNED
TO THIS WELL

40

18. DISTANCE FROM PROPOSED LOCATION*

TO NEAREST WELL, DRILLING, COMPLETED,
OR APPLIED FOR, ON THIS LEASE, FT.

1321

19. PROPOSED DEPTH

5700

20. ROTARY OR CABLE TOOLS

Rotary

21. ELEVATIONS (Show whether DF, RT, GR, etc.)

5600' GR

22. APPROX. DATE WORK WILL START*

January, 1984

23.

PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12 1/4	8 5/8	24	300	To Surface
7 7/8	5 1/2	17	TD	As Required

RECEIVED
NOV 18 1983DIVISION OF
OIL, GAS & MINING

OCT 25 AM 8:50

RECEIVED
DIVISION OF OIL, GAS & MINING

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout prevention program, if any.

24.

SIGNED

G. L. Pruitt

TITLE V.P. Drilling & Production

DATE 10/21/83

(For Federal or State office use)

BY

APPROVAL DATE

APPROVED BY

TITLE

DISTRICT MANAGER

DATE

11/17/83

CONDITIONS OF APPROVAL, IF ANY:

NOTICE OF APPROVAL CONDITIONS OF APPROVAL ATTACHED
TO OPERATOR'S COPY

State Oil & Gas

REPLY TO DIVISION OF
OIL, GAS & MINING
DATED 11/83

NOS _____
APD 10/31/83
Company Lomax Exploration
Well Mon. Butte 8-34
Section 34 T 8S R 16E
Lease U-16535
Onsite Date 11/3/83

ADDITIONS TO THE MULTIPOINT
SURFACE USE PLAN
RECLAMATION PROCEDURES

CONSTRUCTION

1. Construction and maintenance of roads, rehabilitation of disturbed areas, and construction of pipeline routes shall be in accordance with the surface use standards as set forth in the booklet, "Surface Operating Standards for Oil and Gas Exploration and Development".
 2. The maximum width of access roads will be 30 feet total disturbed area.
 3. Topsoil will be stockpiled. The top 6-10 inches of topsoil material will be removed from the location and stockpiled on the south end of the location.
 4. Burning will not be allowed. All trash must be contained and hauled to the nearest sanitary land fill.
 5. The reserve pit will not be lined with native clay, commercial bentonite, or plastic sufficient to prevent seepage.
 6. Reserve pits will be fenced with a wire mesh fence and topped with at least one strand of barbed wire.
 7. The operator or his contractor will contact the Vernal District BLM, Diamond Mountain Resource Area, 48 hours prior to beginning any work on public land.
 8. The dirt contractor will be furnished with an approved copy of the surface use plan and any additional BLM stipulations prior to any work.
- A cultural resource clearance is required before any construction begins. The clearance has been granted by Grand River Consultants.

REHABILITATION

1. Immediately upon completion of drilling, the location and surrounding area will be cleared of all debris resulting from the operation. All trash will be hauled to a local sanitary land fill.
2. The operator or his contractor will contact the Vernal BLM, Diamond Mountain Resource Area, 48 hours prior to starting rehabilitation work that involves earth moving equipment and upon completion of restoration measures.
3. Before any dirt work to restore the location takes place, the reserve pit must be completely dry and all trash (cans, barrels, pipe, etc.) must be removed.
4. Prior to reseeding, all disturbed areas, including the access road, will be scarified and left with a rough surface.
5. Seed will be broadcast or drilled at a time specified by the BLM. If broadcast, a harrow or some such implement will be dragged over the seeded area to assure seed coverage.
6. The access will be blocked to prevent any vehicle use.
7. If any cultural resources are found during construction, all work will stop and the BLM will be notified.

PRODUCTION

1. The reserve pit and that portion of the location and access road not needed for production or production facilities will be reclaimed with the methods described in the rehabilitation section. Stockpiled topsoil will be used in reclaiming the unused areas.
2. All permanent [on site for six (6) months duration or longer] structures constructed or installed, including the pumpjack, shall be painted a flat, non-reflective, earthtone color to match the standard environmental colors, Pocky Mountain 5 State Interagency Committee. All facilities shall be painted within 6 months of when the production facilities are put in place. Facilities that are required to comply with O.S.H.A. (Occupational Safety and Health Act) are excluded.

SPECIAL STIPULATIONS

1. Adequate and sufficient electric/radioactive logs will be run to locate and identify the prime oil shale horizons in the Mahogany zone of the Green River formation. Casing and cementing programs will be adjusted to eliminate any potential influence of the well bore or productive hydrocarbon zones on the oil shale resource. Surface casing program may require adjustment for protection of fresh water aquifers. (See attached tentative casing and cementing program for the Uintah Basin.)



United States Department of the Interior

GEOLOGICAL SURVEY
Conservation Division
2000 Administration Building
1745 West 1700 South
Salt Lake City, Utah 84104

March 31, 1980

General Outline for the Protection and Isolation of Ground Water and Oil Shale in the Uinta Basin.

The oil shale occurs with varying thicknesses in most parts of the Uinta Basin and at varying depths. Ground water also occurs at varied depths above and below the Oil Shale. These ground waters have varying degrees of salinity. Nonetheless, drilling for hydrocarbon in the Uinta Basin should provide for the protection of the oil shale and the ground water if either is present.

The protection of the oil shale and the ground water can effectively be carried on through the design of an adequate casing and cementing program for each well drilled in the area.

In the Uinta basin, water occurs mainly in the Uinta and the Green River formations. As drilling for hydrocarbon gets deeper into the crust of the earth, more ground water might be encountered and will be protected as it is encountered.

This notice's purpose is to attempt to lay the groundwork for a casing program and cementing program that will protect the oil shale and the ground water if present.

These programs are to be considered as guidelines. The specificity of casing depth, amount of cement and the depth of staging collars will be considered on an individual basis after a careful study of the logs of each individual well.

The casing and cementing program presented here as an example, will assume that fresh water was encountered in the upper parts of the Green River, that the oil shale occurs in the middle of the Green River (1000 foot section) and that some ground water is encountered in the lower parts of the Green River.

In this case, three areas will have to be cemented to assure the integrity of the ground water and oil shale. These areas are above the upper fresh water, across the oil shale and below the lower water aquifer. Deep aquifers that do not contain useful water are cemented to prevent water zone influence on production.

The following casing and cementing program will be appropriate for this example:

- A. Surface casing is set at approximately 300 feet and cemented to the surface.

- B. The next casing string will be set at approximately 300 feet below the lowest aquifer. Cementing will be done in three stages, using two stage collars and cement metal baskets or equivalent as described below and on attached sketches:
1. Cement first stage through the casing shoe using 150 percent of the calculated volume of cement to fill annulus back to base of lower aquifer.
 2. Place 1st stage collar (with metal basket immediately below) at a selected point in the lower one third of the oil shale zone using 120% of calculated volume of cement to be at least 600 feet above the stage collar or 100 feet below the top of the oil shale.
 3. Place 2nd stage collar (with metal petal basket immediately below) 50 feet above the top of the top aquifer and cement using 150% volume of cement to at least 300 feet above the stage collar.
- C. The above is an example. Reasonable equivalents that accomplish these same protective measures, depending on the individual cases will be considered for approval.
- D. When the above mentioned well is to be abandoned, inner-casing plugs will have to be placed at the same depth as the above mentioned annulus cement jobs.

The use of cement bond logs will verify the authenticity of the cement job performed.


- E. The Operator of such well should notify that U.S.G.S. 48 hours prior to commencement of casing and cementing activity, so a technician could be dispatched to witness the operations to verify compliance with casing and cementing program.

Attached Sketches:

1. Schematic of the required casing and cementing program.
2. Cross section of the Uinta Basin.

PARTIAL CASING AND CEMENTING PROGRAM FOR WELLS IN THE UINTA BASIN

CEMENT TO BE PLACED ALONG LOW PERMEABILITY SECTIONS






Figure 5a- Cross-section of the Uinta Basin generalizing the stratigraphic and structural framework of the rock section of interest in the application area.

DIVISION OF OIL, GAS AND MINING

SPUDDING INFORMATION

NAME OF COMPANY: LOMAX EXPLORATION

WELL NAME: MONUMENT FED. 8-34

SECTION SENE 34 TOWNSHIP 8S RANGE 16E COUNTY DUCHESNE

DRILLING CONTRACTOR TWT

RIG # 56

SPUDDED: DATE 2-28-84

TIME 11:00 PM

How Rotary

DRILLING WILL COMMENCE

REPORTED BY Michelle

TELEPHONE # 713-931-9276

DATE 3-1-84 SIGNED AS

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil ☒ well gas ☐ well other ☐

2. NAME OF OPERATOR
Lomax Exploration Company

3. ADDRESS OF OPERATOR
P.O. Box 4503, Houston, TX 77210

4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE: 701' FEL & 2059' FNL SE/NE
AT TOP PROD. INTERVAL:
AT TOTAL DEPTH:

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:		SUBSEQUENT REPORT OF:	
TEST WATER SHUT-OFF	<input type="checkbox"/>		<input type="checkbox"/>
FRACTURE TREAT	<input type="checkbox"/>		<input type="checkbox"/>
SHOOT OR ACIDIZE	<input type="checkbox"/>		<input type="checkbox"/>
REPAIR WELL	<input type="checkbox"/>		<input type="checkbox"/>
PULL OR ALTER CASING	<input type="checkbox"/>		<input type="checkbox"/>
MULTIPLE COMPLETE	<input type="checkbox"/>		<input type="checkbox"/>
CHANGE ZONES	<input type="checkbox"/>		<input type="checkbox"/>
ABANDON*	<input type="checkbox"/>		<input type="checkbox"/>
(other) SPUD NOTIFICATION			

5. LEASE
U-16535

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME

8. FARM OR LEASE NAME
Monument Federal

9. WELL NO.
8-34

10. FIELD OR WILDCAT NAME
Monument Butte

11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA
Section 34, T8S, R16E

12. COUNTY OR PARISH
Duchesne

13. STATE
Utah

14. API NO.
43-013-30843

15. ELEVATIONS (SHOW DF, KDB, AND WD)
5600' GR

(NOTE: Report results of multiple completion or zone change on Form 9-330.)

DIVISION OF
OIL, GAS & MINING

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

2/23/84 Drilled 13" surface hole with dryhole digger. Set 8 5/8" 24# j-55 casing @ 279' GL. Cemented with 210 sx cl "G" + 2% CaCl + 1/4#/sx flocele. Returns to surface.

2/28/84 Spud with TWT Rig #56 @ 11:00 P.M.

Subsurface Safety Valve: Manu. and Type _____ Set @ _____ Ft.

18. I hereby certify that the foregoing is true and correct

SIGNED Michael L. Pruitt G.L. Pruitt TITLE V.P. Dir. & Prod. DATE 3/6/84

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY:

RECEIVED

MAY 21 1984

May 17, 1984

DIVISION OF OIL
GAS & MINING

Bureau of Land Management
170 South 500 East
Vernal, Utah 84078

Monument Federal #8-34
SE/NE Sec 34, T8S, R16E
Duchesne County, Utah
Lease U-16535
Well Completion Report & Log

Gentlemen:


Please find enclosed the original and a copy of the Well Completion Report on the subject well.

Please also find enclosed the logs required:

- (1) Cement Bond Log
- (2) Compensated Density/Compensated Neutron Log
- (3) Dual Laterlog

If further information is required, please advise.

Yours very truly,


Janice A. Hertfelder
Secretary/V.P., Drilling & Production

JAH/
Enclosures - 5

cc: State of Utah
Division of Oil & Gas
4241 State Office Building
Salt Lake City, Utah 84114

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUBMIT IN DUPLICATE

(See other instructions on reverse side)

Form approved.
Budget Bureau No. 1004-0137
Expires August 31, 1985

WELL COMPLETION OR RECOMPLETION REPORT AND LOG *

1a. TYPE OF WELL:		OIL WELL <input checked="" type="checkbox"/>	GAS WELL <input type="checkbox"/>	DRY <input type="checkbox"/>	Other _____						
b. TYPE OF COMPLETION:		NEW WELL <input checked="" type="checkbox"/>	WORK OVER <input type="checkbox"/>	DEEP-EN <input type="checkbox"/>	PLUG BACK <input type="checkbox"/>	DIFF. RESVR. <input type="checkbox"/>	Other _____				
2. NAME OF OPERATOR Lomax Exploration Company											
3. ADDRESS OF OPERATOR P.O. Box 4503, Houston, Texas 77210											
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements) At surface 701' FEL & 2059' FNL SE/NE At top prod. interval reported below At total depth											
14. PERMIT NO. 43-013-30843				DATE ISSUED 10/28/83							
15. DATE SPUDDED 2-28-84		16. DATE T.D. REACHED 3-8-84		17. DATE COMPL. (Ready to prod.) 4-19-84		18. ELEVATIONS (DF, RKE, RT, GR, ETC.)* 5600' GR		19. ELEV. CASINGHEAD 5600'			
20. TOTAL DEPTH, MD & TVD 6400'		21. PLUG, BACK T.D., MD & TVD 5610'		22. IF MULTIPLE COMPL., HOW MANY* ---		23. INTERVALS DRILLED BY →		ROTARY TOOLS X		CABLE TOOLS	
24. PRODUCING INTERVAL(S), OF THIS COMPLETION—TOP, BOTTOM, NAME (MD AND TVD)* Green River 5024-43'								25. WAS DIRECTIONAL SURVEY MADE NO			
26. TYPE ELECTRIC AND OTHER LOGS RUN DLL-MSPL, CDI-CND, CBI-GR								27. WAS WELL CORED NO			
28. CASING RECORD (Report all strings set in well)											
CASING SIZE		WEIGHT, LB./FT.		DEPTH SET (MD)		HOLE SIZE		CEMENTING RECORD		AMOUNT PULLED	
8 5/8"		24#		279' GL		13"		210 sx. Class "G" & 2% Gacel & 1/4#/sk flocele			
5 1/2"		17#		6388' KB		7 7/8"		150 sx HiFill & 3.25 sx Gypseal			
29. LINER RECORD											
SIZE		TOP (MD)		BOTTOM (MD)		SACKS CEMENT*		SCREEN (MD)			
30. TUBING RECORD											
SIZE		DEPTH SET (MD)		PACKER SET (MD)							
2 7/8"		5134'									
31. PERFORATION RECORD (Interval, size and number)						32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.					
6219-36' (1 SPF)						DEPTH INTERVAL (MD)					
5024-38'						6219'-36'					
5040-43 (1 SPF)						5024'-43'					
						AMOUNT AND KIND OF MATERIAL USED					
						3000 gals KCl water & Clay stab-ilizer.					
						27,500 gal. Gelled KCl water & 89,500# 20/40 sand.					
33.* PRODUCTION											
DATE FIRST PRODUCTION 4/19/84		PRODUCTION METHOD (Flowing, gas lift, pumping—size and type of pump) Pumping						WELL STATUS (Producing or shut-in) Producing			
DATE OF TEST 5-3-84		HOURS TESTED 24		CHOKE SIZE Open		PROD'N. FOR TEST PERIOD →		OIL—BBL. 35		GAS—MCF. 139	
FLOW. TUBING PRESS. 0		CASING PRESSURE 0		CALCULATED 24-HOUR RATE →		OIL—BBL. 35		GAS—MCF. 139		WATER—BBL. 0	
										GAS-OIL RATIO 3963	
										OIL GRAVITY-API (CORR.) 34	
34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.) Sold and used for fuel.										TEST WITNESSED BY	
35. LIST OF ATTACHMENTS											
36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records											
SIGNED <u>G.L. Pruitt</u> TITLE <u>V.P., Drilling & Production</u> DATE <u>May 16, 1984</u>											

*(See Instructions and Spaces for Additional Data on Reverse Side)

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

37. SUMMARY OF POROUS ZONES: (Show all important zones of porosity and contents thereof; cored intervals; and all drill-stem, tests, including depth interval tested, cushion used, flowing and shut-in pressures, and recoveries):

FORMATION	TOP	BOTTOM	DESCRIPTION, CONTENTS, ETC.	NAME	TOP	
					MEAS. DEPTH	TRUE VERT. DEPTH
Garden Gulch	4600'	4632'		Green River Fm	1790'	
Douglas Creek	5021'	5046'		Garden Gulch	3994'	
Black Shale Facies	5944'	5962'		Douglas Creek	4997'	
				Black Shale Facies	5756'	
				Basal Green River	6308'	

38. GEOLOGIC MARKERS

1. (Name of well)
(Number of wells)
(Location of well)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUBMIT IN THE DATE*
(Other instructions on reverse side)

Form approved.
Budget Item No. 1004-0135
Expires August 31, 1985

5. LEASE DESIGNATION AND SERIAL NO.

U-16535

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

N/A

7. UNIT AGREEMENT NAME

N/A

8. FARM OR LEASE NAME

N/A

9. WELL NO.

See attached sheet.

10. FIELD AND POOL, OR WILDCAT

Monument Butte

11. SEC., T., R., M., OR BLE. AND SURVEY OR AREA

34 & 35, 8S-16E

12. COUNTY OR PARISH

Duchesne

13. STATE

Utah

1. OIL WELL ☒ GAS WELL ☐ OTHER ☐
2. NAME OF OPERATOR Lomax Exploration Company
3. ADDRESS OF OPERATOR 50 W. Broadway, Suite 1000, Salt Lake City, UT 84101
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements. See also space 17 below.)
At surface
See attached sheet.

14. PERMIT NO. See attached sheet. 15. ELEVATIONS (Show whether DT, AT, OR, etc.) See attached sheet.

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF

FRACTURE TREAT

SHOOT OR ACIDIZE

REPAIR WELL

(Other)

PULL OR ALTER CASING

MULTIPLE COMPLETE

ABANDON*

CHANGE PLANS

Construct gas gathering system

X

SUBSEQUENT REPORT OF:

WATER SHUT-OFF

FRACTURE TREATMENT

SHOOTING OR ACIDIZING

(Other)

REPAIRING WELL

ALTERING CASING

ABANDONMENT*

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS: (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Construct a gas gathering system for the subject wells. The system will consist of an 8" main line and 3" feeder lines from each of the subject wells to the main line. The 8" main line will transport the associated casinghead gas from the subject wells off lease to a compressor/processing plant and sales point in Section 36, T8S-R16E. The entire system will be buried. A 3" fuel gas line will also be buried in the same ditch. Initial volumes of gas to be transported will be approximately 610 MCFD. A 4" surface line will also be built on the subject lease. Such 4" surface line will transport gas from other Lomax wells located off lease across the lease to the sales point in Section 36, T8S-R16E. Construction will begin upon receipt of approval. See attached plat.

RECEIVED

MAY 29 1984

DIVISION OF OIL
GAS & MINING

18. I hereby certify that the foregoing is true and correct

SIGNED

David D. Perkins

(This space for Federal or State office use)

TITLE District Landman

DATE May 16, 1984

APPROVED BY

CONDITIONS OF APPROVAL, IF ANY:

TITLE

DATE

*See Instructions on Reverse Side

19. I hereby certify that no person knowingly and willfully has made to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Attached to that certain Sundry Notice dated May 16, 1984 for the Monument Butte Federal #1-34, #8-34, #1-35, #2-35, #3-35, #4-35, #5-35, #6-35, # 10-35, #12-35, #13-35, & #14-35 Wells on Lease U-16535.

Item 4. - Location of wells:

#1-34 - 739' FNL, 758' FEL, Section 34, T8S, R16E
#8-34 - 2059' FNL, 701' FEL, Section 34, T8S-R16E
#1-35 - 506' FSL, 528' FEL, Section 35, T8S-R16E
#2-35 - 2090' FSL, 660' FEL, Section 35, T8S-R16E
#3-35 - 660' FNL, 1980' FWL, Section 35, T8S-R16E
#4-35 - 1836' FSL, 1883' FWL, Section 35, T8S-R16E
#5-35 - 2042' FNL, 661' FWL, Section 35, T8S-R16E
#6-35 - 1831' FNL, 1968' FWL, Section 35, T8S-R16E
#10-35 - 1825' FSL, 2137' FEL, Section 35, T8S-R16E
#12-35 - 1839' FSL, 779' FWL, Section 35, T8S-R16E
#13-35 - 640' FSL, 592' FWL, Section 35, T8S-R16E
#14-35 - 511' FSL, 2134' FWL, Section 35, T8S-R16E

Item 9. - Well No.:

Federal #1-34	Federal #5-35
Federal #8-34	Federal #6-35
Federal #1-35	Federal #10-35
Federal #2-35	Federal #12-35
Federal #3-35	Federal #13-35
Federal #4-35	Federal #14-35

Item 14. - Permit No.:

#1-34 - 43013-30808
#8-34 - 43013-30843
#1-35 - 43013-30561
#2-35 - 43013-30606
#3-35 - 43013-31381
#4-35 - 43013-30605
#5-35 - 43013-30686
#6-35 - 43013-30751
#10-35 - 43013-30801
#12-35 - 43013-30744
#13-35 - 43013-30745
#14-35 - 43013-30812


Item 15. - Elevations:

#1-34 - 5585 GR
#8-34 - 5600 GR
#1-35 - 5482 GR
#2-35 - 5515 GR
#3-35 - 4830 GR
#4-35 - 5565 GR
#5-35 - 5584 GR
#6-35 - 5562 GR
#10-35 - 5534 GR
#12-35 - 5580 GR
#13-35 - 5586 GR
#14-35 - 5524 GR

LOMAX EXPLORATION

T8S
T9S

Scale: 1" = 2000'



May 29, 1984

Mr. Ron Firth
State of Utah
Division of Oil, Gas & Mining
4241 State Office Building
Salt Lake City, Utah 84114

✓ Monument Federal #8-34
SE NE Sec 34, T8S, R16E
Duchesne County, Utah

Gentlemen:


Pursuant to Rule C-27 as stated in the Oil & Gas Conservation General Rules and Regulations, we conducted a seventy-two (72) hour test on the subject well May 18-20, 1984.

The results were as follows:

26 BOPD
91 MCFD
3500 GDR

This well is within the area of our Monument Butte pipeline however the pipeline is handling maximum capacity. We are currently in the process of upgrading the pipeline and expect to have this well tied in by August 1, 1984. We plan to continue to produce the well and flare the associated gas until that time.

Yours very truly,


G.L. Pruitt
V.P., Drilling & Production


RECEIVED

GLP/jwh

JUN 4 1984

DIVISION OF OIL
GAS & MINING

333 North Belt East • Suite 880 • Houston, Texas 77060 • 713/931-9276
Mailing Address: P.O. Box 4503 • Houston, Texas 77210-4503

 District Office: West Pole Line Road • Roosevelt, Utah 84066
Mailing Address: P.O. Box 1446 • Roosevelt, Utah 84066

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

FEB 19 1991

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. TYPE OF WELL: OIL WELL ☒ GAS WELL ☐ DRY ☐ Other ☐b. TYPE OF COMPLETION: NEW WELL ☐ WORK OVER ☒ DEEP-EN ☐ PLUG BACK ☐ DIFF. RESV. ☐ Other ☒ Perforate

2. NAME OF OPERATOR

Lomax Exploration

3. ADDRESS OF OPERATOR

P.O. Box 1446 Roosevelt, Utah 84066

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements)

At surface 701' FEL & 2059' FNL SE/NE

At top prod. interval reported below

At total depth

14. API NO.

43-013-30843

DATE ISSUED

10/28/83

12. COUNTY

Duchesne

13. STATE

Utah

15. DATE SPUNDED

2/28/84

16. DATE T.D. REACHED

3/8/84

17. DATE COMPL. (Ready to prod.)

10/14/90 (Plug & Abd.)

18. ELEVATIONS (DP, RES. RT, GR, ETC.)

5600' GR

19. ELEV. CASINGHEAD

5600'

20. TOTAL DEPTH, MD & TVD

6350'

21. PLUG BACK T.D., MD & TVD

5610'

22. IF MULTIPLE COMPL. HOW MANY

23. INTERVALS DRILLED BY

ROTARY TOOLS

X

CABLE TOOLS

24. PRODUCING INTERVAL(S), OF THIS COMPLETION—TOP, BOTTOM, NAME (MD AND TVD)

Green River 5024'-43'

25. WAS DIRECTIONAL SURVEY MADE

No

26. TYPE ELECTRIC AND OTHER LOGS RUN

None

27. WAS WELL CORED YES ☐ NO ☒ (Submit analysis)
DRILL STEM TEST YES ☐ NO ☒ (See reverse side)

28. CASING RECORD (Report all strings set in well)

CASING SIZE	WEIGHT, LB./FT.	DEPTH SET (MD)	HOLE SIZE	CEMENTING RECORD	AMOUNT POLLED
8 5/8"	24#	279'	13"	210sx cl "G" + 2% CaCl + 1/2sx flocele	
5 1/2"	17#	6388'	7 7/8"	150sx HiFill + 3/4sx Gypseal	

29. LINER RECORD

SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT	SCREEN (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
					2 7/8"	5134'	

31. PERFORATION RECORD (Interval, size and number)

5024'-38' 3 add. spf

5040'-43' 3 add. spf

6219'-36' 1 spf

32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL (MD)	AMOUNT AND KIND OF MATERIAL USED
5024'-43'	1500 gals. 15% HCl acid w/ nitrogen

33. PRODUCTION

23.

DATE FIRST PRODUCTION 10/14/90		PRODUCTION METHOD (Flowing, gas lift, pumping—size and type of pump) Pumping				WELL STATUS (Producing or shut-in) Producing	
DATE OF TEST 10/18/90	HOURS TESTED 70	CHOKE SIZE	PROD'N. FOR TEST PERIOD →	OIL—BBL. 230	GAS—MCF. 73	WATER—BBL. 70	GAS-OIL RATIO 317
FLOW, TUBING PRESS.	CASING PRESSURE	CALCULATED 24-HOUR RATE →	OIL—BBL. 79	GAS—MCF. 25	WATER—BBL. 24	OIL GRAVITY-API (CORR.) 34.8	

34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.)

Sold & used for fuel

TEST WITNESSED BY

35. LIST OF ATTACHMENTS

None

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records

SIGNED

TITLE

Production Secretary

DATE

2/15/91

See Spaces for Additional Data on Reverse Side

INSTRUCTIONS

This form should be completed in compliance with the Utah Oil and Gas Conservation General Rules. If not filed prior to this time, all logs, tests, and directional surveys as required by Utah Rules should be attached and submitted with this report.

ITEM 18: Indicate which elevation is used as reference for depth measurements given in other spaces on this form and on any attachments.

ITEMS 22 and 24: If this well is completed for separate production from more than one interval zone (multiple completion), so state in item 22, and in item 24 show the producing interval, or intervals, top(s), bottom(s) and name(s) for only the interval reported in item 33. Submit a separate report (page) on this form, adequately identified, for each additional interval to be separately produced, showing the additional data pertinent to such interval.

ITEM 29: "Sacks Cement": Attached supplemental records for this well should show the details of any multiple stage cementing and the location of the cementing tool.

ITEM 33: Submit a separate completion report on this form for each interval to be separately produced (see instruction for items 22 and 24 above)

37. SUMMARY OF POROUS ZONES: Show all important zones of porosity and contents thereof; cored intervals; and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			38. GEOLOGIC MARKERS		
Formation	Top	Bottom	Description, contents, etc.	Name	<div style="display: flex; justify-content: space-between; font-size: small;"> Meas. Depth True Vert. Depth </div>
Garden Gulch	4600'	4632'		Green River	1790'
Douglas Creek	5021'	5046'		Garden Gulch	3994'
Blk Shale Fac.	5944'	5962'		Douglas Creek	4997'
				Blk Shale Fac.	5756'
				Basal Green River	6308'

Lomax Exploration Company

P.O. Box 1446
Roosevelt, Utah 84066
(801) 722-5103
FAX (801) 722-9149



State of Utah
Division of Oil, Gas & Mining
355 West North Temple
Three Triad Center - Suite 350
Salt Lake City, Utah 84180-1203

February 13, 1991



DIVISION OF
OIL, GAS & MINING

RE: Monument Butte Federal #8-34
Sec. 34, T8S, R16E SE/NE
Duchesne Co. Utah
Monument Butte Green River "D"
Unit #83688U6800

Dear Sir:

Please find enclosed the [✓]Well Recompletion Report for the
above mentioned well.

If you have any questions or need further information, please
don't hesitate to call me.

Sincerely,

Kebbie Jones
Production Secretary

Enclosures

/kj

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APR 15 1993

DIVISION OF

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

5. Lease Designation and Serial No.

U-16535 Unit #83688U680C

6. If Indian, Allottee or Tribe Name

SUNDRY NOTICES AND REPORTS ON WELLS GAS & MINING

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

LOMAX EXPLORATION COMPANY

801-722-5103

3. Address and Telephone No.

P.O. Box 1446, Roosevelt, UT 84066

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

701' FEL 2059' FNL SE/NE Section 34, T8S, R16E

7. If Unit or CA, Agreement Designation

Monument Butte (Green River "D") Unit

8. Well Name and No.

Monument Federal #8-34

9. API Well No.

43-013-30843

10. Field and Pool, or Exploratory Area

Monument Butte

11. County or Parish, State

Duchesne County, Utah

12. CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☒ Notice of Intent

☐ Subsequent Report

☐ Final Abandonment Notice

TYPE OF ACTION

☐ Abandonment

☐ Recompletion

☐ Plugging Back

☐ Casing Repair

☐ Altering Casing

☐ Other

☐ Change of Plans

☐ New Construction

☐ Non-Routine Fracturing

☐ Water Shut-Off

☐ Conversion to Injection

☒ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Lomax Exploration Company reports that produced water from the above referenced location is being produced into a water tank and hauled to our water injection station at the #5-35 located in Section 35, T8S, R16E, Duchesne County or to the approved disposal facilities of Hansen Disposal or RNI.

However, Lomax requests approval for a pit 15' x 15' to drain water into that inadvertently goes to the oil tank and needs to be drained off. The amount of water drained will not exceed 5 bbls /day.

RECEIVED

APR 26 1993

DIVISION OF
OIL GAS & MINING


Accepted by the State
of Utah Division of
Oil, Gas and Mining

Date: 4-30-93

By: 

14. I hereby certify that the foregoing is true and correct

Signed



Title Regional Production Manager

Date 4/8/93

(This space for Federal or State office use)

Approved by

Federal Approval of this

Title

Date

Conditions of approval, if any: Action is Necessary

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instruction on Reverse Side

Lomax Exploration Company

P.O. Box 1446
Roosevelt, Utah 84066
(801) 722-5103
FAX (801) 722-9149



Bureau of Land Management
170 South 500 East
Vernal, Utah 84078
Attention: Ed Forsman

State of Utah
Division of Oil, Gas & Mining
355 West North Temple
3 Triad Center, Suite 350
Salt Lake City, Utah 84180-1203

April 8, 1993

RECEIVED

APR 13 1993

DIVISION OF
OIL, GAS & MINING

RE: Monument Federal #8-34
Monument Federal #10-34
Monument Federal #8-35
Sec. 34 & 35, T8S, R16E
Monument Butte (Green River "D")
Unit, Duchesne County, Utah

Gentlemen:

Please find enclosed the "Sundry Notices and Reports on Wells" reports to dispose of produced water for the above referenced locations.

If you should have any questions, please don't hesitate to call me in the Roosevelt office at 801-722-5103.

Sincerely,

Lucy Nemec
Engineering Secretary

VLAN
GOVTWTRFDSN.LTR

Enclosures

LOMAX EXPLORATION COMPANY

APPLICATION FOR APPROVAL OF CLASS II INJECTION WELL

MONUMENT FEDERAL #8-34

MONUMENT BUTTE (GREEN RIVER "D") UNIT

FEBRUARY 17, 1994

APPLICATION FOR INJECTION WELL - UIC FORM 1

OPERATOR LOMAX EXPLORATION
ADDRESS P.O. Box 1446
Roosevelt, Utah 84066

Well name and number: MONUMENT FEDERAL #8-34 Unit #83688U6800
Field or Unit name: MONUMENT BUTTE GR "D" Unit Lease no. U-16535
Well location: QQ SE/NE section 34 township 8S range 16E county Duchesne

Is this application for expansion of an existing project? . . Yes ☒ No ☐

Will the proposed well be used for: Enhanced Recovery? . . Yes ☒ No ☐
Disposal? Yes ☐ No ☒
Storage? Yes ☐ No ☒

Is this application for a new well to be drilled? Yes ☐ No ☒

If this application is for an existing well,
has a casing test been performed on the well? Yes ☒ No ☐
Date of test: 10/13/90
API number: 43-013-30843

Proposed injection interval: from 5024 to 5043

Proposed maximum injection: rate 1000 BWIPD pressure 2000# psig

Proposed injection zone contains ☒ oil, ☒ gas, and/or ☐ fresh water within 1/2 mile of the well.

IMPORTANT: Additional information as required by R615-5-2 should accompany this form.

List of Attachments: A, A-1, A-2, B-1 - B-8, C-1, C-2, C-3, D

I certify that this report is true and complete to the best of my knowledge.

Name Brad Mecham Signature *Brad Mecham*
Title Regional Production Manager Date 2-17-94
Phone No. (801) 722-5103

(State use only)
Application approved by _____ Title _____
Approval Date _____

Comments:

REQUIREMENTS FOR INJECTION OF FLUIDS INTO RESERVOIRS
RULE R615-5-1

- 1) Operations to increase ultimate recovery, such as cycling of gas, the maintenance of pressure, the introduction of gas, water or other substances into a reservoir for the purpose of secondary or other enhanced recovery or for storage and the injection of water into any formation for the purpose of water disposal shall be permitted only by order of the Board after notice and hearing.
- 2) A request for agency action for authority for the injection of gas, liquefied petroleum gas, air, water or any other medium into any formation for any reason, including but not necessarily limited to the establishment of or the expansion of waterflood projects, enhanced recovery projects, and pressure maintenance projects shall contain:

2.1. *The name and address of the operator of the project;*

Answer: Lomax Exploration Company
P.O. Box 1446
W. Poleline Road
Roosevelt, Utah 84066

2.2. *A plat showing the area involved and identifying all wells, including all proposed injection wells, in the project area and within one-half mile radius of the project area;*

Answer: Reference Exhibit A.

2.3. *A full description of the particular operation for which approval is requested;*

Answer: To approve the conversion of a Unit producing well to a Unit injection well in the Monument Butte (Green River "D" Unit).

2.4. *A description of the pools from which the identified wells are producing or have produced;*

Answer: The proposed injection well is currently producing oil and gas from the Green River Formation, specifically the "D" Sand which has been previously been unitized for production.

2.5. *The names, description and depth of the pool or pools to be affected;*

Answer: The Green River Formation pool targeted for injection is "D" sand with a gamma ray derived top as follows:

#8-34 - "D" sand @ 4992'

The injection zones are a porous and permeable lenticular calcareous sandstone. The porosity of the sandstone is inter granular. The confining impermeable stratum directly above and below the injection zones are composed of tight, moderately calcareous lacustrine shales.

2.6. *A copy of a log of a representative well completed in the pool;*

Answer: Referenced log Federal #1-34 is currently on file with the Utah Division of Oil, Gas & Mining and Bureau of Land Management.

- 2.7. *A statement as to the type of fluid to be used for injection, its source and the estimated amounts to be injected daily;*

Answer: Culinary water from Johnson Water District supply line.
Estimated Injection Rate: 200 - 300 BWIPD
Maximum Injection Rate: 1000 BWIPD

- 2.8. *A list of all operators or owners and surface owners within a one-half mile radius of the proposed project;*

Answer: Reference Exhibit A-1 & A-2.

- 2.9. *An affidavit certifying that said operators or owners and surface owners within a one-half mile radius have been provided a copy of the petition for injection;*

Answer: Reference Exhibit D.

- 2.10. *Any additional information the Board may determine is necessary to adequately review the petition.*

Answer: Lomax will supply any additional information requested by the Bureau.

- 4.0. *Establish recovery projects may be expanded and additional wells placed on injection only upon authority from the board after notice and hearing or by administrative approval.*

Answer: This proposed injection well is within the Monument Butte (Green River "D") Unit and the request is for administrative approval.

**REQUIREMENTS FOR CLASS II INJECTION WELLS INCLUDING WATER DISPOSAL, STORAGE
AND ENHANCED RECOVERY WELLS
SECTION V - RULE 615-5-2**

- 1) Injection well shall be completed, equipped, operated, and maintained in a manner that will prevent pollution and damage to any USDW, or other resources and will confine injected fluids to the interval approved.
- 2) The application for an injection well shall include a properly completed Form DOGM-UIC-1 and the following:

- 2.1. *A plat showing the location of the injection well, all abandoned or active wells within a one-half mile radius of the proposed wells, and the surface owner and the operator of any lands or producing leases, respectively, within a one-half mile radius of the proposed injection well;*

Answer: Reference Exhibit A, A-1 & A-2.

- 2.2. *Copies of electrical or radioactive logs, including gamma ray logs, for the proposed well run prior to the installation of casing and indicating resistivity, spontaneous potential, caliper and porosity;*

Answer: Reference log currently on file with the Utah Division of Oil, Gas & Mining and the Bureau of Land Management.

- 2.3. *A copy of a cement bond or comparable log run for the proposed injection well after casing was set and cemented;*

Answer: Reference log currently on file with the Utah Division of Oil, Gas & Mining and the Bureau of Land Management.

- 2.4 *Copies of log already on file with the Division should be referenced, but need not to be refiled.*

Answer: Radioactive and cement bond logs currently on file with the Utah Division of Oil, Gas & Mining and the Bureau of Land Management.

- 2.5 *A description of the casing or proposed casing program of the injection well and of the proposed method for testing the casing before use of the well;*

Answer: Reference Exhibit B - 1 and B - 2
A casing integrity test will be conducted upon conversion.

- 2.6. *A statement as to the type of fluid to be used for injection, its source and estimated amounts to be injected daily.*

Answer: Culinary water from Johnson Water district supply line.
Estimated Injection Rate: 200 - 300 BWIPD
Maximum Injection Rate: 1000 BWIPD

- 2.7. *Standard laboratory analysis of (1) the fluid to be injected, (2) the fluid in the formation into which the fluid is being injected, and (3) the compatibility of the fluids.*

Answer: Items (1) & (2) reference Exhibits C - 1 , C - 2 , C - 3. Item (3) - as Exhibit C - 2 shows, fresh water from our injection wells has reached the #8-34 resulting in compatible water.

2.8. *The proposed average and maximum injection pressures;*

Answer: Average Injection Pressure will be determined upon conversion by a Step Rate Test
Maximum Injection Pressure: 2000 psig - surface

2.9. *Evidence and data to support a finding that the proposed injection well will not initiate fractures through the overlying strata or a confining interval that could enable the injected fluid or formation fluid to enter the fresh water strata;*

Answer: The frac gradients for the field averages to be 0.84 psig/ft. The maximum injection pressures will be kept below this gradient. A step rate test will be performed periodically to insure we are below parting pressure.

2.10. *Appropriate geological data on the injection interval and confining beds, including the geologic name, lithologic description, thickness, depth, and lateral extent;*

Answer: The injection zone is "D" sandstone reservoir found within the Douglas Creek Member of the Green River Formation. The Douglas Creek is composed of porous and permeable lenticular calcareous sandstones and low porosity carbonates and calcareous shales.

	INJECTION ZONE	
	TOP	THICKNESS
#8-34 "D" SAND	5024'	19'

The porous and permeable lenticular sandstones vary in thickness from 0' to 34' and are confined to the Monument Butte field by low porosity calcareous shales and carbonates.

The confining stratum directly above and below the injection zone is the Douglas Creek member of the Green River Formation. The strata confining the injection zone is composed of tight, moderately calcareous sandy lacustrine shales. All of the confining strata is impermeable and it will effectively seal off the oil, gas, and water of the injection zone from any strata directly above or below it. Maps and cross sections to the Monument Butte (Green River "D") Unit are on file with the Division of Oil, Gas & Mining and also with the U. S. Bureau of Land Management.

2.11. *A review of the mechanical condition of each well within a one-half mile radius of the proposed injection well to assure that no conduit exists that could enable fluids to migrate up or down the wellbore and enter improper intervals;*

Answer: Exhibits B-1 through B-8.

The injection system will be equipped with high and low pressure shut-down devices which will automatically shut-in injection waters if a system blockage or leakage occurs. One way check valves will also insure proper flow management. Relief valves will also be utilized for high pressure relief.

2.12. *An affidavit certifying that a copy of the application has been provided to all operators or owners, and surface owners within a one-half mile radius of the proposed injection well;*

Answer: Exhibit D.

2.13 *Any other additional information that the Board or Division may determine is necessary to adequately review the application.*

Answer: Lomax exploration will await review of this application and additional information will be submitted if required.


3) Applications for injection wells which are within a recovery project area will be considered for approval.

3.1. Pursuant to Rule 615-5-1-3


3.2. Subsequent to Board approval of a recovery project pursuant to Rule 615-5-1-3.

4) Approval of an injection well is subject to the requirements of Rule 615-5-4, if the proposed injection interval can be classified as an USDW.

5) In addition to the requirements of this section, the provisions of Rule 615-3-1, R615-3-4, R615-3-24, R615-3-32, R615-8-1 and R615-10 apply to all Class II injection wells.



R 16 E



- PRODUCING WELL
- ★ PROPOSED INJECTION WELL
- ◇ DRY HOLE

EXHIBIT A-1

MONUMENT BUTTE
DUCHESNE CO., UTAH
MINERAL RIGHTS

EXHIBIT A-2

SURFACE OWNERS, OWNERS AND OPERATORS WITHIN A ONE-HALF MILE RADIUS OF THE
MONUMENT FEDERAL #8-34

SURFACE OWNERS

Bureau of Land Management
Attention: Ed Forsman
170 South 500 East
Vernal, UT 84078

State of Utah - Division of State Lands & Forestry
Attention: Ed Bonner
355 West North Temple
3 Triad Center, Suite 400
Salt Lake City, UT 84180-1204

GRAZING RIGHTS ONLY

Elmer Moon
HC1 Box 115
Duchesne, Utah 84021

OPERATORS

Enserch Exploration, Inc.
1817 Wood St.
Dallas, Texas 75201

PG&E Resources Company
6688 N. Central Expressway, Suite 1000
Dallas, Texas 75206

MONUMENT FEDERAL #8-34

SE/NE SECTION 34, T8S, R16E
DUCHESNE COUNTY, UTAH




EXHIBIT B-1

BM 2/8/94

WATER ANALYSIS REPORT

COMPANY Lomax Exploration ADDRESS Roosevelt, UT. DATE 8-02-91
SOURCE Johnson water pump station DATE SAMPLED 8-02-91 ANALYSIS NO. _____

Analysis	Mg/l (ppm)	Meq/l
1. PH	<u>6.5</u>	
2. H ₂ S (Qualitative)	<u>.5</u>	
3. Specific Gravity	<u>1.002</u>	
4. Dissolved Solids	<u>370</u>	
5. Suspended Solids		
6. Anaerobic Bacterial Count		C/MI
7. Methyl Orange Alkalinity (CaCO ₃)		
8. Bicarbonate (HCO ₃)	<u>140</u>	<u>+61</u> <u>2</u> HCO ₃
9. Chlorides (Cl)	<u>30</u>	<u>+35.5</u> <u>1</u> Cl
10. Sulfates (SO ₄)	<u>100</u>	<u>+48</u> <u>2</u> SO ₄
11. Calcium (Ca)	<u>48</u>	<u>+20</u> <u>2</u> Ca
12. Magnesium (Mg)	<u>29</u>	<u>+12.2</u> <u>2</u> Mg
13. Total Hardness (CaCO ₃)	<u>240</u>	
14. Total Iron (Fe)	<u>.8</u>	
15. Barium (Qualitative)		
16. Phosphate Residuals		

*Milli equivalents per liter

PROBABLE MINERAL COMPOSITION

2	Ca	←	HCO ₃	2
2	Mg	←	SO ₄	2
1	Na	←	Cl	1

Saturation Values

Distilled Water 20°C

CaCO₃

13 Mg/l

CaSO₄ · 2H₂O

2,090 Mg/l

MgCO₃

103 Mg/l

Compound	Equiv. Wt.	X	Meq/l	=	Mg/l
Ca (HCO ₃) ₂	81.04		<u>2</u>		<u>162</u>
Ca SO ₄	68.07				
Ca Cl ₂	55.50				
Mg (HCO ₃) ₂	73.17				
Mg SO ₄	60.19		<u>2</u>		<u>120</u>
Mg Cl ₂	47.52				
Na HCO ₃	84.00				
Na ₂ SO ₄	71.03				
Na Cl	58.46		<u>1</u>		<u>59</u>

REMARKS _____



A Procter & Gamble Co.

EXHIBIT C-2

P.O. BOX 1898
CORSICANA, TX. 75151

OFFICE:
TEL: 214/872-3011
FAX: 214/872-4216

PLANT:
TEL: 214/874-9500
FAX: 214/874-9596

WATER ANALYSIS REPORT

COMPANY Lomax Exploration ADDRESS Roosevelt, UT. DATE: 12-05-90
SOURCE 8-34 DATE SAMPLED _____ ANALYSIS NO. _____

Analysis	Mg/l (ppm)	*Meq/l
1. PH <u>8.1</u>		
2. H ₂ S (Qualitative) <u>5.5</u>		
3. Specific Gravity <u>1.017</u>		
4. Dissolved Solids <u>7,542</u>		
5. Suspended Solids _____		
6. Anaerobic Bacterial Count _____ C/MI		
7. Methyl Orange Alkalinity (CaCO ₃) _____		
8. Bicarbonate (HCO ₃) <u>366</u> ÷ 61 <u>6</u> HCO ₃		
9. Chlorides (Cl) <u>4,272</u> ÷ 35.5 <u>120</u> Cl		
10. Sulfates (SO ₄) <u>0</u> ÷ 48 <u>0</u> SO ₄		
11. Calcium (Ca) <u>24</u> ÷ 20 <u>1</u> Ca		
12. Magnesium (Mg) <u>5</u> ÷ 12.2 <u>0</u> Mg		
13. Total Hardness (CaCO ₃) <u>80</u>		
14. Total Iron (Fe) <u>1.1</u>		
15. Barium (Qualitative) _____		
16. Phosphate Residuals _____		

*Milli equivalents per liter

PROBABLE MINERAL COMPOSITION

1	Ca	←	HCO ₃	6
0	Mg	→	SO ₄	0
125	Na	→	Cl	120

Saturation Values

Ca CO ₃	13 Mg/l
Ca SO ₄ · 2H ₂ O	2,090 Mg/l
Mg CO ₃	103 Mg/l

Distilled Water 20°C

Compound	Equiv. Wt.	X	Meq/l	=	Mg/l
Ca (HCO ₃) ₂	81.04		1		81
Ca SO ₄	68.07				
Ca Cl ₂	55.50				
Mg (HCO ₃) ₂	73.17				
Mg SO ₄	60.19				
Mg Cl ₂	47.62				
Na HCO ₃	84.00		5		420
Na ₂ SO ₄	71.03				
Na Cl	58.46		120		7,015

REMARKS _____



A Procter & Gamble Co.

EXHIBIT C-3

P.O. BOX 1898
CORSICANA, TX. 75151

OFFICE:
TEL: 214/872-3011
FAX: 214/872-4216

PLANT:
TEL: 214/874-9500
FAX: 214/874-9596

WATER ANALYSIS REPORT

COMPANY Lomax Exploration ADDRESS Roosevelt, UT. DATE: 12-06-90
SOURCE 1 part 8-34 to 10 parts source water DATE SAMPLED _____ ANALYSIS NO. _____

Analysis

Mg/l (ppm)

*Meq/l

1. PH	7.8		
2. H ₂ S (Qualitative)	1.0		
3. Specific Gravity	1.001		
4. Dissolved Solids	1,423		
5. Suspended Solids			
6. Anaerobic Bacterial Count		C/MI	
7. Methyl Orange Alkalinity (CaCO ₃)			
8. Bicarbonate (HCO ₃)	122	÷61	2 HCO ₃
9. Chlorides (Cl)	754	÷35.5	21 Cl
10. Sulfates (SO ₄)	20	÷48	0 SO ₄
11. Calcium (Ca)	48	÷20	2 Ca
12. Magnesium (Mg)	19	÷12.2	1 Mg
13. Total Hardness (CaCO ₃)	200		
14. Total Iron (Fe)	1.3		
15. Barium (Qualitative)			
16. Phosphate Residuals			

*Milli equivalents per liter

PROBABLE MINERAL COMPOSITION

Compound	Equiv. Wt.	X	Meq/l	=	Mg/l
Ca (HCO ₃) ₂	81.04		2		162
Ca SO ₄	68.07				
Ca Cl ₂	55.50				
Mg (HCO ₃) ₂	73.17				
Mg SO ₄	60.19				
Mg Cl ₂	47.62		1		48
Na HCO ₃	84.00				
Na ₂ SO ₄	71.03				
Na Cl	58.46		20		1,169

Saturation Values	Distilled Water 20°C
Ca CO ₃	13 Mg/l
Ca SO ₄ · 2H ₂ O	2,090 Mg/l
Mg CO ₃	103 Mg/l

MARKS _____


EXHIBIT D

RE: Application for Approval of Class II Injection Well
Monument Federal #8-34


I certify that a copy of the application has been provided to all surface owners within a one-half mile radius of the proposed injection well.


LOMAX EXPLORATION COMPANY
By Brad Mecham, Regional Production Manager

Sworn to and subscribed before me the 17th day of February 1994.


Notary Public in and for the State of Utah

Printed Name: Kebbie Jones
My Commission Expires: 5/4/94



MONUMENT FEDERAL #8-34

SE/NE SECTION 34, T8S, R16E

DUCHESNE COUNTY, UTAH

(AFTER CONVERSION)




EXHIBIT B-2

BM 2/8/94

MONUMENT FEDERAL #1-34

NE/NE SECTION 34, T8S, R16E
 DUCHESNE COUNTY, UTAH




EXHIBIT B-3

BM 1/18/94

MONUMENT FEDERAL #9-34
NE/SE SECTION 34, T8S, R16E
DUCHESNE COUNTY, UTAH




EXHIBIT B-4

BM 1/18/94

MONUMENT FEDERAL #10-34
NW/SE SECTION 34, T8S, R16E
DUCHESNE COUNTY, UTAH




EXHIBIT B-5

LN 9/7/93

MONUMENT FEDERAL #5-35
SW/NW SECTION 35, T8S, R16E
DUCHESNE COUNTY, UTAH




EXHIBIT B-6

MONUMENT FEDERAL #6-35

SE/NW SECTION 35, T8S, R16E
 DUCHESNE COUNTY, UTAH




EXHIBIT B-7

BM 2/9/94

MONUMENT FEDERAL #12-35

NW/SW SECTION 35, T8S, R16E
 DUCHESNE COUNTY, UTAH




EXHIBIT B-8

Lomax Exploration Company

P.O. Box 1446
Roosevelt, Utah 84066
(801) 722-5103
FAX (801) 722-9149

FEB 17 1994

February 17, 1994



State of Utah
Division of Oil, Gas & Mining
355 West North Temple
3 Triad Center, Suite 350
Salt Lake City, Utah 84180-1203
Attention: Dan Jarvis

RE: Conversion to Water Injection
MONUMENT FEDERAL #8-34
SE/NE Sec. 34, T8S, R16E
Monument Butte Green River "D" Unit
Duchesne County, Utah

Dear Dan:

Please find enclosed the original and one copy of UIC Form 1 and attachments for the conversion to water injection for the above referenced location.

If you should have any questions or require additional information, please don't hesitate to call me in the Roosevelt office at 801-722-5103.

Sincerely,

A handwritten signature in dark ink, appearing to read "Brad Mecham", is written over a horizontal line.

Brad Mecham
Regional Production Manager

/kj

Enclosures

LOMAX EXPLORATION COMPANY

APPLICATION FOR APPROVAL OF CLASS II INJECTION WELL

MONUMENT FEDERAL #8-34

MONUMENT BUTTE (GREEN RIVER "D") UNIT

FEBRUARY 17, 1994

REQUIREMENTS FOR INJECTION OF FLUIDS INTO RESERVOIRS
RULE R615-5-1

- 1) Operations to increase ultimate recovery, such as cycling of gas, the maintenance of pressure, the introduction of gas, water or other substances into a reservoir for the purpose of secondary or other enhanced recovery or for storage and the injection of water into any formation for the purpose of water disposal shall be permitted only by order of the Board after notice and hearing.
- 2) A request for agency action for authority for the injection of gas, liquefied petroleum gas, air, water or any other medium into any formation for any reason, including but not necessarily limited to the establishment of or the expansion of waterflood projects, enhanced recovery projects, and pressure maintenance projects shall contain:

2.1. *The name and address of the operator of the project;*

Answer: Lomax Exploration Company
P.O. Box 1446
W. Poleline Road
Roosevelt, Utah 84066

2.2. *A plat showing the area involved and identifying all wells, including all proposed injection wells, in the project area and within one-half mile radius of the project area;*

Answer: Reference Exhibit A.

2.3. *A full description of the particular operation for which approval is requested;*

Answer: To approve the conversion of a Unit producing well to a Unit injection well in the Monument Butte (Green River "D" Unit).

2.4. *A description of the pools from which the identified wells are producing or have produced;*

Answer: The proposed injection well is currently producing oil and gas from the Green River Formation, specifically the "D" Sand which has been previously been unitized for production.

2.5. *The names, description and depth of the pool or pools to be affected;*

Answer: The Green River Formation pool targeted for injection is "D" sand with a gamma ray derived top as follows:

#8-34 - "D" sand @ 4992'

The injection zones are a porous and permeable lenticular calcareous sandstone. The porosity of the sandstone is inter granular. The confining impermeable stratum directly above and below the injection zones are composed of tight, moderately calcareous lacustrine shales.

2.6. *A copy of a log of a representative well completed in the pool;*

Answer: Referenced log Federal #1-34 is currently on file with the Utah Division of Oil, Gas & Mining and Bureau of Land Management.

- 2.7. *A statement as to the type of fluid to be used for injection, its source and the estimated amounts to be injected daily;*

Answer: Culinary water from Johnson Water District supply line.
Estimated Injection Rate: 200 - 300 BWIPD
Maximum Injection Rate: 1000 BWIPD

- 2.8. *A list of all operators or owners and surface owners within a one-half mile radius of the proposed project;*

Answer: Reference Exhibit A-1 & A-2.

- 2.9. *An affidavit certifying that said operators or owners and surface owners within a one-half mile radius have been provided a copy of the petition for injection;*

Answer: Reference Exhibit D.

- 2.10. *Any additional information the Board may determine is necessary to adequately review the petition.*

Answer: Lomax will supply any additional information requested by the Bureau.

- 4.0. *Establish recovery projects may be expanded and additional wells placed on injection only upon authority from the board after notice and hearing or by administrative approval.*

Answer: This proposed injection well is within the Monument Butte (Green River "D") Unit and the request is for administrative approval.

**REQUIREMENTS FOR CLASS II INJECTION WELLS INCLUDING WATER DISPOSAL, STORAGE
AND ENHANCED RECOVERY WELLS
SECTION V - RULE 615-5-2**

- 1) Injection well shall be completed, equipped, operated, and maintained in a manner that will prevent pollution and damage to any USDW, or other resources and will confine injected fluids to the interval approved.
- 2) The application for an injection well shall include a properly completed Form DOGM-UIC-1 and the following:

- 2.1. *A plat showing the location of the injection well, all abandoned or active wells within a one-half mile radius of the proposed wells, and the surface owner and the operator of any lands or producing leases, respectively, within a one-half mile radius of the proposed injection well;*

Answer: Reference Exhibit A, A-1 & A-2.

- 2.2. *Copies of electrical or radioactive logs, including gamma ray logs, for the proposed well run prior to the installation of casing and indicating resistivity, spontaneous potential, caliper and porosity;*

Answer: Reference log currently on file with the Utah Division of Oil, Gas & Mining and the Bureau of Land Management.

- 2.3. *A copy of a cement bond or comparable log run for the proposed injection well after casing was set and cemented;*

Answer: Reference log currently on file with the Utah Division of Oil, Gas & Mining and the Bureau of Land Management.

- 2.4. *Copies of log already on file with the Division should be referenced, but need not to be refiled.*

Answer: Radioactive and cement bond logs currently on file with the Utah Division of Oil, Gas & Mining and the Bureau of Land Management.

- 2.5. *A description of the casing or proposed casing program of the injection well and of the proposed method for testing the casing before use of the well;*

Answer: Reference Exhibit B - 1 and B - 2
A casing integrity test will be conducted upon conversion.

- 2.6. *A statement as to the type of fluid to be used for injection, its source and estimated amounts to be injected daily.*

Answer: Culinary water from Johnson Water district supply line.
Estimated Injection Rate: 200 - 300 BWIPD
Maximum Injection Rate: 1000 BWIPD

- 2.7. *Standard laboratory analysis of (1) the fluid to be injected, (2) the fluid in the formation into which the fluid is being injected, and (3) the compatibility of the fluids.*

Answer: Items (1) & (2) reference Exhibits C - 1 , C - 2 , C - 3. Item (3) - as Exhibit C - 2 shows, fresh water from our injection wells has reached the #8-34 resulting in compatible water.

- 2.8. *The proposed average and maximum injection pressures;*

Answer: Average Injection Pressure will be determined upon conversion by a Step Rate Test
Maximum Injection Pressure: 2000 psig - surface

- 2.9. *Evidence and data to support a finding that the proposed injection well will not initiate fractures through the overlying strata or a confining interval that could enable the injected fluid or formation fluid to enter the fresh water strata;*

Answer: The frac gradients for the field averages to be 0.84 psig/ft. The maximum injection pressures will be kept below this gradient. A step rate test will be performed periodically to insure we are below parting pressure.

- 2.10. *Appropriate geological data on the injection interval and confining beds, including the geologic name, lithologic description, thickness, depth, and lateral extent;*

Answer: The injection zone is "D" sandstone reservoir found within the Douglas Creek Member of the Green River Formation. The Douglas Creek is composed of porous and permeable lenticular calcareous sandstones and low porosity carbonates and calcareous shales.

	INJECTION ZONE	
	TOP	THICKNESS
#8-34 "D" SAND	5024'	19'

The porous and permeable lenticular sandstones vary in thickness from 0' to 34' and are confined to the Monument Butte field by low porosity calcareous shales and carbonates.

The confining stratum directly above and below the injection zone is the Douglas Creek member of the Green River Formation. The strata confining the injection zone is composed of tight, moderately calcareous sandy lacustrine shales. All of the confining strata is impermeable and it will effectively seal off the oil, gas, and water of the injection zone from any strata directly above or below it. Maps and cross sections to the Monument Butte (Green River "D") Unit are on file with the Division of Oil, Gas & Mining and also with the U. S. Bureau of Land Management.

- 2.11. *A review of the mechanical condition of each well within a one-half mile radius of the proposed injection well to assure that no conduit exists that could enable fluids to migrate up or down the wellbore and enter improper intervals;*

Answer: Exhibits B-1 through B-8.

The injection system will be equipped with high and low pressure shut-down devices which will automatically shut-in injection waters if a system blockage or leakage occurs. One way check valves will also insure proper flow management. Relief valves will also be utilized for high pressure relief.

- 2.12. *An affidavit certifying that a copy of the application has been provided to all operators or owners, and surface owners within a one-half mile radius of the proposed injection well;*

Answer: Exhibit D.

2.13 *Any other additional information that the Board or Division may determine is necessary to adequately review the application.*

Answer: Lomax exploration will await review of this application and additional information will be submitted if required.

3) Applications for injection wells which are within a recovery project area will be considered for approval.


3.1. Pursuant to Rule 615-5-1-3

3.2. Subsequent to Board approval of a recovery project pursuant to Rule 615-5-1-3.

4) Approval of an injection well is subject to the requirements of Rule 615-5-4, if the proposed injection interval can be classified as an USDW.

5) In addition to the requirements of this section, the provisions of Rule 615-3-1, R615-3-4, R615-3-24, R615-3-32, R615-8-1 and R615-10 apply to all Class II injection wells.

R 16 E



- PRODUCING WELL
- ⊗ PROPOSED INJECTION WELL
- ⊙ DRY HOLE

EXHIBIT A-1

MONUMENT BUTTE
DUCHESNE CO., UTAH
MINERAL RIGHTS

EXHIBIT A-2

SURFACE OWNERS, OWNERS AND OPERATORS WITHIN A ONE-HALF MILE RADIUS OF THE
MONUMENT FEDERAL #8-34

SURFACE OWNERS

Bureau of Land Management
Attention: Ed Forsman
170 South 500 East
Vernal, UT 84078

State of Utah - Division of State Lands & Forestry
Attention: Ed Bonner
355 West North Temple
3 Triad Center, Suite 400
Salt Lake City, UT 84180-1204

GRAZING RIGHTS ONLY

Elmer Moon
HC1 Box 115
Duchesne, Utah 84021

OPERATORS

Enserch Exploration, Inc.
1817 Wood St.
Dallas, Texas 75201

PG&E Resources Company
6688 N. Central Expressway, Suite 1000
Dallas, Texas 75206

MONUMENT FEDERAL #8-34

SE/NE SECTION 34, T8S, R16E
DUCHESNE COUNTY, UTAH




EXHIBIT B-1

BM 2/8/94

MONUMENT FEDERAL #8-34

SE/NE SECTION 34, T8S, R16E

DUCHESNE COUNTY, UTAH

(AFTER CONVERSION)




EXHIBIT B-2

BM 2/8/94

MONUMENT FEDERAL #1-34

NE/NE SECTION 34, T8S, R16E
DUCHESNE COUNTY, UTAH




EXHIBIT B-3

BM 1/18/94

MONUMENT FEDERAL #9-34

NE/SE SECTION 34, T8S, R16E

DUCHESNE COUNTY, UTAH





EXHIBIT B-4

BM 1/18/94

MONUMENT FEDERAL #10-34

NW/SE SECTION 34, T8S, R16E

DUCHESNE COUNTY, UTAH

**EXHIBIT B-5**

LN 9/7/93

MONUMENT FEDERAL #5-35

SW/NW SECTION 35, T8S, R16E

DUCHESNE COUNTY, UTAH




EXHIBIT B-6

BM 2/8/94

MONUMENT FEDERAL #6-35

SE/NW SECTION 35, T8S, R16E
 DUCHESNE COUNTY, UTAH




EXHIBIT B-7

BM 2/9/94

MONUMENT FEDERAL #12-35
NW/SW SECTION 35, T8S, R16E
DUCHESNE COUNTY, UTAH




EXHIBIT B-8


WATER ANALYSIS REPORT

COMPANY Lomax Exploration ADDRESS Roosevelt, UT. DATE: 8-02-91
SOURCE Johnson water pump station DATE SAMPLED 8-02-91 ANALYSIS NO. _____

Analysis	Mg/l (ppm)	*Meq/l
1. PH <u>6.5</u>		
2. H ₂ S (Qualitative) <u>.5</u>		
3. Specific Gravity <u>1.002</u>		
4. Dissolved Solids <u>370</u>		
5. Suspended Solids _____		
6. Anaerobic Bacterial Count _____ C/MI		
7. Methyl Orange Alkalinity (CaCO ₃) _____		
8. Bicarbonate (HCO ₃) <u>140</u> ÷ 61 <u>2</u> HCO ₃		
9. Chlorides (Cl) <u>30</u> ÷ 35.5 <u>1</u> Cl		
10. Sulfates (SO ₄) <u>100</u> ÷ 48 <u>2</u> SO ₄		
11. Calcium (Ca) <u>48</u> ÷ 20 <u>2</u> Ca		
12. Magnesium (Mg) <u>29</u> ÷ 12.2 <u>2</u> Mg		
13. Total Hardness (CaCO ₃) <u>240</u>		
14. Total Iron (Fe) <u>.8</u>		
15. Barium (Qualitative) _____		
16. Phosphate Residuals _____		

*Milli equivalents per liter

PROBABLE MINERAL COMPOSITION



Saturation Values

Distilled Water 20°C

CaCO₃ 13 Mg/l
Ca SO₄ · 2H₂O 2,090 Mg/l
Mg CO₃ 103 Mg/l

Compound	Equiv. Wt.	X	Meq/l	=	Mg/l
Ca (HCO ₃) ₂	81.04		2		162
Ca SO ₄	68.07				
Ca Cl ₂	55.50				
Mg (HCO ₃) ₂	73.17				
Mg SO ₄	60.19		2		120
Mg Cl ₂	47.62				
Na HCO ₃	84.00				
Na ₂ SO ₄	71.03				
Na Cl	58.46		1		59

REMARKS _____



A Procter & Gamble Co.

EXHIBIT C-2

P.O. BOX 1898
CORSICANA, TX. 75151

OFFICE:
TEL: 214/872-3011
FAX: 214/872-4216

PLANT:
TEL: 214/874-9500
FAX: 214/874-9596

WATER ANALYSIS REPORT

COMPANY Lomax Exploration ADDRESS Roosevelt, UT. DATE: 12-05-90

SOURCE 8-34 DATE SAMPLED _____ ANALYSIS NO. _____

Analysis

Mg/l (ppm)

*Meq/l

1. PH	<u>8.1</u>		
2. H ₂ S (Qualitative)	<u>5.5</u>		
3. Specific Gravity	<u>1.017</u>		
4. Dissolved Solids		<u>7,542</u>	
5. Suspended Solids			
6. Anaerobic Bacterial Count			C/MI
7. Methyl Orange Alkalinity (CaCO ₃)			
8. Bicarbonate (HCO ₃)		HCO ₃ <u>366</u> ÷ 61 <u>6</u> HCO ₃	
9. Chlorides (Cl)		Cl <u>4,272</u> ÷ 35.5 <u>120</u> Cl	
10. Sulfates (SO ₄)		SO ₄ <u>0</u> ÷ 48 <u>0</u> SO ₄	
11. Calcium (Ca)		Ca <u>24</u> ÷ 20 <u>1</u> Ca	
12. Magnesium (Mg)		Mg <u>5</u> ÷ 12.2 <u>0</u> Mg	
13. Total Hardness (CaCO ₃)		<u>80</u>	
14. Total Iron (Fe)		<u>1.1</u>	
15. Barium (Qualitative)			
16. Phosphate Residuals			

*Milli equivalents per liter

PROBABLE MINERAL COMPOSITION

1	Ca	←	HCO ₃	6
0	Mg	→	SO ₄	0
125	Na	→	Cl	120

Saturation Values

Distilled Water 20°C

Ca CO ₃	13 Mg/l
Ca SO ₄ · 2H ₂ O	2,090 Mg/l
Mg CO ₃	103 Mg/l

Compound	Equiv. Wt.	X	Meq/l	=	Mg/l
Ca (HCO ₃) ₂	81.04		<u>1</u>		<u>81</u>
Ca SO ₄	68.07				
Ca Cl ₂	55.50				
Mg (HCO ₃) ₂	73.17				
Mg SO ₄	60.19				
Mg Cl ₂	47.62				
Na HCO ₃	84.00		<u>5</u>		<u>420</u>
Na ₂ SO ₄	71.03				
Na Cl	58.46		<u>120</u>		<u>7,015</u>

REMARKS _____



A Procter & Gamble Co.

EXHIBIT C-3

P.O. BOX 1898
CORSICANA, TX. 75151

OFFICE:
TEL: 214/872-3011
FAX: 214/872-4216

PLANT:
TEL: 214/874-9500
FAX: 214/874-9596

WATER ANALYSIS REPORT

COMPANY Lomax Exploration ADDRESS Roosevelt, UT. DATE: 12-06-90

SOURCE 1 part 8-34 to 10 parts source water DATE SAMPLED _____ ANALYSIS NO. _____

Analysis	Mg/l (ppm)	*Meq/l
1. PH	7.8	
2. H ₂ S (Qualitative)	1.0	
3. Specific Gravity	1.001	
4. Dissolved Solids	1,423	
5. Suspended Solids		
6. Anaerobic Bacterial Count	C/MI	
7. Methyl Orange Alkalinity (CaCO ₃)		
8. Bicarbonate (HCO ₃)	HCO ₃ 122	+61 2 HCO ₃
9. Chlorides (Cl)	Cl 754	+35.5 21 Cl
10. Sulfates (SO ₄)	SO ₄ 20	+48 0 SO ₄
11. Calcium (Ca)	Ca 48	+20 2 Ca
12. Magnesium (Mg)	Mg 19	+12.2 1 Mg
13. Total Hardness (CaCO ₃)	200	
14. Total Iron (Fe)	1.3	
15. Barium (Qualitative)		
16. Phosphate Residuals		

*Milli equivalents per liter

PROBABLE MINERAL COMPOSITION

2	Ca	HCO ₃	2
1	Mg	SO ₄	0
20	Na	Cl	21

Compound	Equiv. Wt.	X	Meq/l	=	Mg/l
Ca (HCO ₃) ₂	81.04		2		162
Ca SO ₄	68.07				
Ca Cl ₂	55.50				
Mg (HCO ₃) ₂	73.17				
Mg SO ₄	60.19				
Mg Cl ₂	47.62		1		48
Na HCO ₃	84.00				
Na ₂ SO ₄	71.03				
Na Cl	58.46		20		1,169

Saturation Values

Distilled Water 20°C

Ca CO ₃	13 Mg/l
Ca SO ₄ · 2H ₂ O	2,090 Mg/l
Mg CO ₃	103 Mg/l

MARKS _____





EXHIBIT D

RE: Application for Approval of Class II Injection Well
Monument Federal #8-34


I certify that a copy of the application has been provided to all surface owners within a one-half mile radius of the proposed injection well.


LOMAX EXPLORATION COMPANY
By Brad Mecham, Regional Production Manager

Sworn to and subscribed before me the 17th day of February 1994.



Notary Public in and for the State of Utah

Printed Name: Kebbie Jones
My Commission Expires: 5/4/94



Lomax Exploration Company

P.O. Box 1446
Roosevelt, Utah 84066
(801) 722-5103
FAX (801) 722-9149



March 2, 1994



State of Utah
Division of Oil, Gas & Mining
Attn: Dan Jarvis
355 West North Temple
Three Triad Center - Suite #350
Salt Lake City, Utah 84180-1203

RE: **MONUMENT BUTTE FEDERAL #8-34**
SE/NE Sec 34, T8S, R16E
Monument Butte Green River "D" Unit
Duchesne County, Utah

Dear Dan:

You have received the "Application for Injection" for the above referenced well. As per your request please find enclosed the original and one copy of the following:

- 1) Amended Exhibit "D"
- 2) Exhibit B-9

The Amended Exhibit "D" shows that we have mailed a copy of the application to all owners and operators within a one-half mile radius. Exhibit B-9 is a P&A'D well we referenced in Exhibit A-1, but failed to include information on. These two items should be all you will need to process this application.

If you should have any questions or require additional information, please don't hesitate to contact me.

Sincerely,

A handwritten signature in cursive script that reads "Brad Mechem".

Brad Mechem
Regional Production Manager

Enclosures

/kj


EXHIBIT D - AMENDED MARCH 2, 1994

RE: Application for Approval of Class II Injection Well
Monument Federal #8-34


I certify that a copy of the application has been provided to all surface owners, grazing right owners and operators within a one-half mile radius of the proposed injection well.


LOMAX EXPLORATION COMPANY
By Brad Mecham, Regional Production Manager

Sworn to and subscribed before me the 2nd day of March 1994.


Notary Public in and for the State of Utah

Printed Name: Kebbie Jones
My Commission Expires: 5/4/94



MONUMENT BUTTE FED 4A-35
NW/NW SEC 35, T8S, R16E
660' FWL 600' FNL
DUCHESNE CO., UTAH
API #43-013-31348-0000

WELL DATA

Elevation: 6400'GR, 6412'KB KB = 12
Spud Date: 4/20/92
TD: 6395'
Csg: 8-5/8" 23# & 24# J-55 @ 282
PBSD: P & A - Dry hole

COMPLETION HISTORY

DRY HOLE - P&A'd 5/7/92 as follows:

60 sks	Class "G" @ 5747'- 5547'
30 sks	Class "G" @ 5650'- 5550'
60 sks	Class "G" @ 2400'- 2200'
175 sks	Class "G" @ 450'- 150'
6 sks	Cement @ 50'- surface

EXHIBIT B-9

APPLICATION FOR INJECTION WELL - UIC FORM 1

OPERATOR LOMAX EXPLORATION
ADDRESS P.O. Box 1446
Roosevelt, Utah 84066

Well name and number: MONUMENT FEDERAL #8-34
Field or Unit name: MONUMENT BUTTE GR "D" Unit Unit #83688U6800
Lease no. U-16535
Well location: QQ SE/NE section 34 township 8S range 16E county Duchesne

Is this application for expansion of an existing project? . . Yes ☒ No ☐

Will the proposed well be used for: Enhanced Recovery? . . Yes ☒ No ☐
Disposal? Yes ☐ No ☒
Storage? Yes ☐ No ☒

Is this application for a new well to be drilled? Yes ☐ No ☒

If this application is for an existing well,
has a casing test been performed on the well? Yes ☒ No ☐
Date of test: 10/13/90
API number: 43-013-30843

Proposed injection interval: from 5024 to 5043

Proposed maximum injection: rate 1000 BWIPD pressure 2000# psig

Proposed injection zone contains ☒ oil, ☒ gas, and/or ☐ fresh water within 1/2 mile of the well.

IMPORTANT: Additional information as required by R615-5-2 should accompany this form.

List of Attachments: A, A-1, A-2, B-1 - B-8, C-1, C-2, C-3, D

I certify that this report is true and complete to the best of my knowledge.

Name Brad Mechem Signature Brad Mechem
Title Regional Production Manager Date 2-17-94
Phone No. (801) 722-5103

(State use only)
Application approved by _____ Title _____
Approval Date _____

Comments:

BEFORE THE DIVISION OF OIL, GAS AND MINING
DEPARTMENT OF NATURAL RESOURCES
STATE OF UTAH

---ooOoo---

IN THE MATTER OF THE APPLICATION	:	NOTICE OF AGENCY ACTION
OF LOMAX EXPLORATION COMPANY FOR	:	
ADMINISTRATIVE APPROVAL OF THE	:	CAUSE NO. UIC-148
MONUMENT FEDERAL #8-34 WELL	:	
LOCATED IN SECTION 34, TOWNSHIP	:	
8 SOUTH, RANGE 16 EAST, S.L.M.,	:	
DUCHESNE COUNTY, UTAH, AS A	:	
CLASS II INJECTION WELL	:	

---ooOoo---

THE STATE OF UTAH TO ALL PERSONS INTERESTED IN THE ABOVE ENTITLED MATTER.


Notice is hereby given that the Division is commencing an informal adjudicative proceeding to consider the application of Lomax Exploration Company for administrative approval of the Monument Federal #8-34 Well, located in Section 34, Township 8 South, Range 16 East, Duchesne County, Utah, for conversion to a Class II injection well. The proceeding will be conducted in accordance with Utah Admin. R.649-10, Administrative Procedures.

The well will be selectively perforated from 5024' to 5043' in the Green River formation (D sand interval). The applicant has requested a maximum injection pressure of 2000 psig which will be confirmed by conducting a step-rate pressure test following the completion of the well. The requested injection volume is approximately 1000 bwpd.

Any person desiring to object to the application or otherwise intervene in the proceeding, must file a written protest or notice of intervention with the Division within fifteen days of the date of publication of this notice. If such a protest or notice of intervention is received, a hearing will be scheduled before the Board of Oil, Gas and Mining. Protestants and/or intervenors should be prepared to demonstrate at the hearing how this matter affects their interests.

DATED this 22nd day of March 1994.

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING



R.J. Firth
Associate Director, Oil and Gas

WUI101

**Lomax Exploration Company
Monument Federal #9-34 Well
Cause No. UIC-148**

Publication Notices were sent to the following:

Newspaper Agency Corporation
Legal Advertising
157 Regent Street
Salt Lake City, Utah 84110

Uintah Basin Standard
268 South 200 East
Roosevelt, Utah 84066

Bureau of Land Management
Vernal District Office
170 South 500 East
Vernal, Utah 84078

Lomax Exploration Company
P.O. Box 1446
Roosevelt, Utah 84066

U.S. Environmental Protection Agency
Region VIII
Attn. Dan Jackson
999 18th Street
Denver, Colorado 80202-2466



Lisa D. Clement
Administrative Secretary
March 22, 1994



State of Utah
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

Michael O. Leavitt
Governor

Ted Stewart
Executive Director

James W. Carter
Division Director

355 West North Temple
3 Triad Center, Suite 350
Salt Lake City, Utah 84180-1203
801-538-5340
801-359-3940 (Fax)
801-538-5319 (TDD)

March 22, 1994

Newspaper Agency Corporation
Legal Advertising
157 Regent Street
Salt Lake City, Utah 84110

Gentlemen:

Re: Notice of Agency Action - Cause No. UIC-148

Enclosed is a copy of the referenced Notice of Agency Action. Please publish the Notice, once only, as soon as possible. Please send proof of publication and billing to the Division of Oil, Gas and Mining, 355 West North Temple, 3 Triad Center, Suite 350, Salt Lake City, Utah 84180-1203.

Sincerely,

Lisa D. Clement
Administrative Secretary

Enclosure
WOI168





State of Utah
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

Michael O. Leavitt
Governor

Ted Stewart
Executive Director

James W. Carter
Division Director

355 West North Temple
3 Triad Center, Suite 350
Salt Lake City, Utah 84180-1203
801-538-5340
801-359-3940 (Fax)
801-538-5319 (TDD)

March 22, 1994

Uintah Basin Standard
268 South 200 East
Roosevelt, Utah 84066

Gentlemen:

Re: Notice of Agency Action - Cause No. UIC-148

Enclosed is a copy of the referenced Notice of Agency Action. Please publish the Notice, once only, as soon as possible. Please send proof of publication and billing to the Division of Oil, Gas and Mining, 355 West North Temple, 3 Triad Center, Suite 350, Salt Lake City, Utah 84180-1203.

Sincerely,

Lisa D. Clement
Administrative Secretary

Enclosure
WOI168



REVIEW SUMMARY

Comments & Recommendation



State of Utah
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

Michael O. Leavitt
Governor

Ted Stewart
Executive Director

James W. Carter
Division Director

355 West North Temple
3 Triad Center, Suite 350
Salt Lake City, Utah 84180-1203
801-538-5340
801-359-3940 (Fax)
801-538-5319 (TDD)

March 22, 1994

Uintah Basin Standard
268 South 200 East
Roosevelt, Utah 84066

Gentlemen:

Re: Notice of Agency Action - Cause No. UIC-148

Enclosed is a copy of the referenced Notice of Agency Action. Please publish the Notice, once only, as soon as possible. Please send proof of publication and billing to the Division of Oil, Gas and Mining, 355 West North Temple, 3 Triad Center, Suite 350, Salt Lake City, Utah 84180-1203.

Sincerely,

Lisa D. Clement
Administrative Secretary

Enclosure
WOI168



BEFORE THE DIVISION OF OIL, GAS AND MINING
DEPARTMENT OF NATURAL RESOURCES
STATE OF UTAH

---ooOoo---

IN THE MATTER OF THE APPLICATION	:	NOTICE OF AGENCY ACTION
OF LOMAX EXPLORATION COMPANY FOR	:	
ADMINISTRATIVE APPROVAL OF THE	:	CAUSE NO. UIC-148
MONUMENT FEDERAL #8-34 WELL	:	
LOCATED IN SECTION 34, TOWNSHIP	:	
8 SOUTH, RANGE 16 EAST, S.L.M.,	:	
DUCHESNE COUNTY, UTAH, AS A	:	
CLASS II INJECTION WELL	:	

---ooOoo---

THE STATE OF UTAH TO ALL PERSONS INTERESTED IN THE ABOVE ENTITLED MATTER.


Notice is hereby given that the Division is commencing an informal adjudicative proceeding to consider the application of Lomax Exploration Company for administrative approval of the Monument Federal #8-34 Well, located in Section 34, Township 8 South, Range 16 East, Duchesne County, Utah, for conversion to a Class II injection well. The proceeding will be conducted in accordance with Utah Admin. R.649-10, Administrative Procedures.

The well will be selectively perforated from 5024' to 5043' in the Green River formation (D sand interval). The applicant has requested a maximum injection pressure of 2000 psig which will be confirmed by conducting a step-rate pressure test following the completion of the well. The requested injection volume is approximately 1000 bwpd.

Any person desiring to object to the application or otherwise intervene in the proceeding, must file a written protest or notice of intervention with the Division within fifteen days of the date of publication of this notice. If such a protest or notice of intervention is received, a hearing will be scheduled before the Board of Oil, Gas and Mining. Protestants and/or intervenors should be prepared to demonstrate at the hearing how this matter affects their interests.

DATED this 22nd day of March 1994.

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING



R.J. Firth
Associate Director, Oil and Gas

WUI101

**DIVISION OF OIL, GAS AND MINING
UNDERGROUND INJECTION CONTROL PROGRAM**

**PERMIT
DECISION DOCUMENT**

Applicant: Lomax Exploration Co. **Well:** Injection Well 8-34

Location: Monument Butte, Duchesne County

Ownership Issues: The proposed well is located in section 34, township 8 south, range 16 east, Duchesne, County, Utah. The surface and minerals within a 1/2 mile of the well is owned by the federal government, and the State of Utah. Lomax has provided an affidavit stating that all interested parties have been notified of their intent to convert the well to injection.

Well Integrity: The well proposed for injection is the Monument Butte Federal 8-34. The well has an 8 5/8" surface casing at 302 feet and cemented to surface. A 5 1/2" longstring is set at 6400 feet and is cemented to 3284 feet and was verified by a cement bond log. The injection interval is from 5024-5043 feet (Green River Formation). A 2 7/8" tubing will be set in a packer no higher than 50 feet above the perforations. This construction should adequately protect all USDW's. There are 5 producing wells and 1 injection well and a plugged well in the 1/2 mile area of review. All wells in the AOR have sufficient cement behind the longstring and have adequate surface casing to prevent any migration of fluid up the hole. A casing test should be performed at the time of conversion and a casing/tubing pressure test should be performed prior to injection.

Ground Water Protection: The base of moderately saline water is at a depth of approximately 2400 feet located in the Uinta Formation in the area of the project. Any shallow fresh water zones will be adequately protected by existing constructions of surrounding wells. A maximum injection pressure of 2000 psi (surface pressure) was requested and should be approved. A number of step rate tests have been conducted in the field and the average fracture gradient is .84 psi/ft. A maximum rate of 1000 bwpd was requested. No corrective action is needed on any of the wells in the area of review.

Oil/Gas & Other Mineral Resources Protection: The Monument Butte Field is an existing water flood project which has been in operation for a number of years. Injection into this well should have no adverse affects on any offsetting production outside the unit area.

Bonding: All the wells in the section are operated by Lomax and are covered by a state wide bond.

Actions Taken and Further Approvals Needed: A public notice for the 8-34 injection

has been published in both the Salt Lake Tribune and the Uinta Basin Standard. Administrative approval can be granted for the injection well after a 15 day comment period if no objections are received. An MIT needs to be conducted prior to injection.

DJJ
Reviewers

03-30-94
Date

Form 3160-5
(June 1990)UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENTFORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals

5. Lease Designation and Serial No.

U-16535
8368806800

6. If Indian, Allottee or Tribe Name

7. If Unit or CA, Agreement Designation

SUBMIT IN TRIPLICATE

1. Type of Well

☐ Oil Well ☐ Gas Well ☒ Other Water Injection

2. Name of Operator

LOMAX EXPLORATION

3. Address and Telephone No.

P.O. Box 1446 Roosevelt, Utah 84066

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

701' FEI, 2059' FNL Sec. 34, T8S, R16E SE/NE

Monument Butte GR "D"

8. Well Name and No.

Monument Butte #8-34

9. API Well No.

43-013-30843

10. Field and Pool, or Exploratory Area

Monument Butte

11. County or Parish, State

Duchesne, Utah

12. CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

- ☐
- Notice of Intent
-
- ☐
- Subsequent Report
-
- ☐
- Final Abandonment Notice

TYPE OF ACTION

- ☐
- Abandonment
-
- ☐
- Recompletion
-
- ☐
- Plugging Back
-
- ☐
- Casing Repair
-
- ☐
- Altering Casing
-
- ☒
- Other Injectivity Test

- ☐
- Change of Plans
-
- ☐
- New Construction
-
- ☐
- Non-Routine Fracturing
-
- ☐
- Water Shut-Off
-
- ☐
- Conversion to Injection
-
- ☐
- Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

LOMAX EXPLORATION COMPANY IS REQUESTING APPROVAL TO CONDUCT AN INJECTIVITY TEST ON THE ABOVE REFERENCED WELL PRIOR TO INJECTION. THIS TEST UPON APPROVAL WILL BEGIN APRIL 8, 1994.

* APPROVED BY THE STATE
OF UTAH DIVISION OF
OIL, GAS, AND MINING

DATE: 4-7-94

BY: [Signature]

* Attached conditions

14. I hereby certify that the foregoing is true and correct

Signed [Signature]

Title Reg. Production Manager

Date April 6, 1994

(This space for Federal or State office use)

Approved by Federal Approval of this
Conditions of approval, if any: Action is Necessary

Title

Date

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

Conditions for injection well step-rate test approval:

- 1) Notify the DOGM office prior to commencing operations to allow witnessing of the test.
- 2) Steps must be of equal time length.
- 3) Either rate or pressure must be held constant during each time step.
- 4) Test should include a minimum of 4 data points below the parting pressure and a minimum of 3 data points above the parting pressure.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals

5. Lease Designation and Serial No.

**U-16535
8368806800**

6. If Indian, Allottee or Tribe Name

7. If Unit or CA, Agreement Designation

Monument Butte GR "D"

8. Well Name and No.

Monument Butte #8-34

9. API Well No.

43-013-30843

10. Field and Pool, or Exploratory Area

Monument Butte

11. County or Parish, State

Duchesne, Utah

SUBMIT IN TRIPLICATE

1. Type of Well

☐ Oil Well ☐ Gas Well ☒ Other **Water Injection**

2. Name of Operator

LOMAX EXPLORATION

3. Address and Telephone No.

P.O. Box 1446 Roosevelt, Utah 84066

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

701' FEL 2059' FNL Sec. 34, T8S, R16E SE/NE

12. CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

- ☐ Notice of Intent
☐ Subsequent Report
☐ Final Abandonment Notice

TYPE OF ACTION

- ☐ Abandonment
☐ Recompletion
☐ Plugging Back
☐ Casing Repair
☒ Altering Casing
☒ Other **Injectivity Test**

- ☐ Change of Plans
☐ New Construction
☐ Non-Routine Fracturing
☐ Water Shut-Off
☐ Conversion to Injection
☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)


13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

LOMAX EXPLORATION COMPANY IS REQUESTING APPROVAL TO CONDUCT AN INJECTIVITY TEST ON THE ABOVE REFERENCED WELL PRIOR TO INJECTION. THIS TEST UPON APPROVAL WILL BEGIN APRIL 8, 1994.

Accepted by the State
of Utah Division of
Oil, Gas and Mining

Date: 4-26-94

By: [Signature]



14. I hereby certify that the foregoing is true and correct

Signed [Signature]

Title **Reg. Production Manager**

Date **April 6, 1994**

(This space for Federal or State office use)

Approved by Federal Approval of the
Conditions of approval, if any: None

Title _____

Date _____

Lomax Exploration Company

P.O. Box 1446
Roosevelt, Utah 84066
(801) 722-5103
FAX (801) 722-9149

April 6, 1994



*State of Utah
Attn: Dan Jarvis
355 West North Temple
Three Triad Center - Suite #350
Salt Lake City, Utah 84180-1203*

*Bureau of Land Management
Attn: Ed Forsman
170 South 500 East
Vernal, Utah 84078*

*RE: MONUMENT BUTTE FEDERAL #8-34
Monument Butte Green River "D" Unit*

Gentlemen:

Please find enclosed a "Sundry Notice and Report on Wells" for the above referenced well. This is for approval of an injectivity test prior to injection.

If you have any questions or need further information, please don't hesitate to call me.

Sincerely,

A handwritten signature in dark ink, appearing to read "Brad Meham". The signature is fluid and cursive, with the first name "Brad" and last name "Meham" clearly distinguishable.

*Brad Meham
Regional Production Manager*

Enclosures

/kj

Lomax Exploration Company

P.O. Box 1446
Roosevelt, Utah 84066
(801) 722-5103
FAX (801) 722-9149

April 15, 1994



State of Utah
355 West North Temple
Three Triad Center - Suite #350
Salt Lake City, Utah 84180-1203

Bureau of Land Management
Attn: Ed Forsman
170 South 500 East
Vernal, Utah 84078

APR 17 1994

RE: MONUMENT FEDERAL #8-34
SE/NE Sec. 34, T8S, R16E
MONUMENT BUTTE GR "D" UNIT
Duchesne County, Utah

Gentlemen:

Please find enclosed the results of a casing integrity test conducted on the above referenced well. I have also enclosed a copy of the chart used during the test.

If you have any questions or need further information, please don't hesitate to call me.

Sincerely,

A handwritten signature in black ink, appearing to read "Jody Liddell".

Jody Liddell
Field Foreman

Enclosures

/kj

143 SOUTH MAIN ST.
P.O. BOX 45838
SALT LAKE CITY, UTAH 84145
FED. TAX I.D. # 87-0217663

Newspaper Agency Corporation
The Salt Lake Tribune (NA) DESERET NEWS

CUSTOMER'S
COPY

LEGAL ADVERTISING INVOICE

CUSTOMER NAME AND ADDRESS	ACCOUNT NUMBER	BILLING DATE
DIV OF OIL, GAS & MINING 355 W NO TEMPLE, #350 SALT LAKE CITY, UT 84180	LE-5385340	03/28/94
FOR BILLING INFORMATION CALL (801) 237-2822		

AFFIDAVIT OF PUBLICATION

AS NEWSPAPER AGENCY CORPORATION LEGAL BOOKKEEPER, I CERTIFY THAT THE ATTACHED ADVERTISEMENT OF NOTICE OF AGENCY ACTION CAUSE NO. UIC-148BEFOR FOR DIV OF OIL, GAS & MINING WAS PUBLISHED BY THE NEWSPAPER AGENCY CORPORATION, AGENT FOR THE SALT LAKE TRIBUNE AND DESERET NEWS, DAILY NEWSPAPERS PRINTED IN THE ENGLISH LANGUAGE WITH GENERAL CIRCULATION IN UTAH, AND PUBLISHED IN SALT LAKE CITY, SALT LAKE COUNTY IN THE STATE OF UTAH.

PUBLISHED ON MAR 28 1994

SIGNATURE

03/28/94

NOTICE OF AGENCY ACTION
CAUSE NO. UIC-148
BEFORE THE DIVISION OF OIL,
GAS AND MINING
DEPARTMENT OF NATURAL
RESOURCES, STATE OF UTAH

IN THE MATTER OF THE APPLICATION OF LOMAX EXPLORATION COMPANY FOR ADMINISTRATIVE APPROVAL OF THE MONUMENT FEDERAL #8-34 WELL LOCATED IN SECTION 34, TOWNSHIP 8 SOUTH, RANGE 16 EAST, 31M., DUCHECHNE COUNTY, UTAH, AS A CLASS II INJECTION WELL

THE STATE OF UTAH TO ALL PERSONS INTERESTED IN THE ABOVE ENTITLED MATTER.

Notice is hereby given that the Division is commencing an informal adjudicative proceeding to consider the application of Lomax Exploration Company for administrative approval of the Monument Federal #8-34 Well, located at Section 34, Township 8 South, Range 16 East, Duchesne County, Utah, for conversion to a Class II injection well. The proceeding will be conducted in accordance with Utah Admin. R. 649-10, Administrative Procedures.

The well will be selectively perforated from 5024' to 5043' in the Green river formation (D and interval). The applicant has requested a maximum injection rate of approximately 1000 bbls/day.

Any person desiring to object to the application or otherwise intervene in the proceeding, must file a written protest or notice of intervention with the Division within fifteen days of the date of publication of this notice. If such a protest or notice of intervention is received, a hearing will be scheduled before the Board of Oil, Gas and Mining. Protestants and/or intervenors should be prepared to demonstrate at the hearing how this matter affects their interests.

DATED this 22nd day of March, 1994.

STATE OF UTAH
DIVISION OF OIL, GAS
AND MINING
/s/ R. J. Ritt
Associate Director, Oil and Gas
36820050

ACCOUNT NAME			TELEPHONE
OIL, GAS & MINING			801-538-5340
SCHEDULE			AD NUMBER
1994			30820050
REF. NO.	CAPTION		MISC. CHARGES
C-148	NOTICE OF AGENCY ACTION CAUSE NO. UIC-148BEFOR		.00
SIZE	TIMES	RATE	AD CHARGE
ES 1 COLUMN	1	1.64	124.64
PAYABLE ON RECEIPT OF THIS INVOICE			TOTAL AMOUNT DUE
			124.64

THANK YOU FOR USING LEGAL ADVERTISING.

PLEASE RETURN THIS PORTION
WITH YOUR PAYMENT IN THE ENCLOSED ENVELOPE

LEGAL ADV06-NT

ACCOUNT NUMBER	AD NUMBER	BILLING DATE	PAY THIS AMOUNT
LE-5385340	30820050	03/28/94	124.64

LEGAL ADVERTISING

PLEASE REMIT TO:

NEWSPAPER AGENCY CORPORATION
P.O. BOX 45838
SALT LAKE CITY, UTAH 84145-0838

MAKE CHECKS PAYABLE TO:
NEWSPAPER AGENCY CORPORATION

DIV OF OIL, GAS & MINING
355 W NO TEMPLE, #350
SALT LAKE CITY, UT 84180

0763177062005090000000000000012464187428817311610111111111111111123575

Division: POD; Place of Use = POU; Nature of Use = USE)
 APPLICATION(S) TO APPROPRIATE WATER 43-10452 (A67616): Susan M. Dye QUANTITY: 1.73 ac-ft. SOURCE: 6 in well 100 ft. to 300 ft. deep. POD: (1) S. 900 E. 1350 from NW Cor, Sec 28, T1S, R1W. (3 miles north of Roosevelt) USE: Irrigation: from Apr 1 to Oct 31, total acreage 0.25 acs; Stockwatering: 10 head of livestock; Domestic: 1 family. POU: NE 1/4 NW 1/4 Sec 28, T1S, R1W.

APPLICATION(S) TO WATER (a17837): Leonie K. Wilkins(s) the POD & POU is evidenced by on 1194.

ET OFORE: FY: 0.8458 cfs. 3: Duchesne D: (1) S 255 E 90 Cor, Sec 5, T4S, SE: Irrigation: 1 to Nov 15, total 1.19 acs. POU: S 1 Sec 34; SW 1/4 Sec 35, T3S; NW 1/4 Sec 2; N 1/2 Sec 3, T4S, R4W. AFTER: QUANTITY: 0.8458 cfs. 3: Duchesne D: Same as Here: adding the following: (1) N 120 E 200 1/4 Cor, Sec 13, T. USE: Same as e. POU: Same as e, but adding the following: SW 1/4 SE 1/4 3S, R4W.

L. Morgan, P.E. ENGINEER
 l in the Uintah Standard on March 1994

APPLICATION(S) TO CHANGE WATER 43-10450 (a17901): Dry Gulch Irr. Co. - Owner -- Edwin Fisher - User

SOURCE: 6 in well 0 ft. to 215 ft. deep. POD: (1) N 736 E 56 from S 1/4 Cor, Sec 25, T2N, R1E. (9 miles north of Lapoint) USE: Same as Heretofore. POU: SW 1/4 SE 1/4 Sec 25; NW 1/4 NE 1/4 Sec 36, T2N, R1E.

Robert L. Morgan, P.E. STATE ENGINEER
 Published in the Uintah Basin Standard March 29, April 5, 12, 1994

NOTICE OF AGENCY ACTION

CAUSE NO. UIC-148
 IN THE MATTER OF THE APPLICATION OF LOMAX EXPLORATION COMPANY FOR ADMINISTRATIVE APPROVAL OF THE MONUMENT FEDERAL #8-34 WELL LOCATED IN SECTION 34, TOWNSHIP 8 SOUTH, RANGE 16 EAST, S.L.M., DUCHESNE COUNTY, UTAH, AS A CLASS II INJECTION WELL

THE STATE OF UTAH TO ALL PERSONS INTERESTED IN THE ABOVE ENTITLED MATTER.

Notice is hereby given that the Division is commencing an informal adjudicative proceeding to consider the application of Lomax Exploration Company for administrative approval of the Monument Federal #8-34 Well, located in Section 34, Township 8 South, Range 16 East, Duchesne County, Utah, for conversion to a Class II injection well. The proceeding will be conducted in accordance with Utah Admin. R. 649-10, Administrative Procedures.

The well will be selected



Older Mobile Home - 12x65, 2 Bedrooms, \$2,500. Available Now.
 Dean Frandsen Realty 722-2235
 Klyn McMickell 722-8236

3-29-94 **A cabin on the hill - 10 acres - 4 bedrooms and family room - YES! \$4

HERE'S SOMEONE WE'RE REALLY SOLD ON.




Liz Dahlburg 644-3062

COLDWELL BANKER
 R.S. West Real Estate
 721 East 200 North
 Roosevelt, Utah 84066
 801-722-3533

When You Put Your Trust in Number One... It's as Good



SUN WARMING SOUTH EXPOSURE—3 Bedroom Ranch Style home partially finished basement - Unique floor plan - Will qualify for any financing program. #3823



GREAT NEIGHBORHOOD FOR THE KIDS—4 Bedroom, 2 bath home with basement completely finished. Fully fenced & spot for garden. All auto sprinklers. Financing available. #3806

Lynn Snow 722-4425
 Gordon Snow 722-4162
 Gene Ostler 722-3739

Century 21
Country Realty

722-4553

865 East 200 North Roosevelt, Utah
"Each Office is Independently Owned and Operated."



RENT THE APARTMENT—Live in the house. 4 Bedroom home approximately 2000 sq. ft. total. Close to school. Call for more details. #3743

Sandy Biggs 722-4771
 Susan Hamilton 738-2314



HORSES, HAY & HAYRACK—able 4 bedroom home on Very private location. #3814



CABIN FEVER?—Unfinished deck on lower level. Beautiful view & 738-2314.

Sue Denver
 Sheri Pettingill

Call our office today at 722-4553 or

ICES

family expe-
linavian, Eu-
h American,
h school ex-
nts arriving
ome a Host
Call Wanda
7 or 1-800-
can) 2-29 1tp

ed Pageant to
ust 5 and 6,
lt Lake Qual-
sted girls age
967-8733.
p

The
ifieds
2-5131

AL NOTICES

ur Right To Know!

LIC ICE

sin Associa-
ernments is
provide ser-
PA program
July 1, 1994
ility determi-
n JTPA Law,
nent, Devel-
ervice Strat-
ent in train-
nent ND fol-

sted parties
ict Gordon
0 South 100
4 Roosevelt,
n an official
posal. Cony
March 31,
riting,
the Uintah
ard March

E TO ER RS

ngineer re-
following
to Appropri-
e Water in
nty (Loca-
M).
ecting to an-
st file a Pro-

GARAGE SALES

Cleaning Out the Garage?
It's time for a Garage Sale!
Advertise your Sale in the
Uintah Basin Standard for
only \$3.00 for 20 words.
Call in your ad and Charge
it to your VISA or
MasterCard or stop by 268
S 200 E in Roosevelt
3-15 ups

MISCELLANEOUS

\$CANS \$CANS \$ - We
buy: All Scrap, Batteries,
Aluminum, Steel, Brass,
Autos, Copper, Radiators.
40 cents lb for aluminum
cans with this ad. 601 S.
Main, Spanish Fork, 798-
3548, 1-800-359-2172.
Offer expires 3/31/94.
(ucan)3-29 1tp

tively perforated form 5024'
to 5043' (Green River
formation (D sand interval).
The applicant has requested
a maximum injection pres-
sure of 2000 psig which
will be confirmed by con-
ducting a step-rate pressure
test following the comple-
tion of the well. The re-
quested injection volume
is approximately 1000
bwpd.

Any person desiring to
object to the application or
otherwise intervene in the
proceeding, must file a writ-
ten protest or notice of in-
tervention with the Divi-
sion within fifteen days of
the date of publication of
this notice. If such a protest
or notice of interventions is
received, a hearing will be
scheduled before the Board
of Oil, Gas and Mining.
Protestants and/or interve-
nors should be prepared to
demonstrate at the hearing
how this matter affects their
interests.

DATED this 22nd day
of March 1994.

STATE OF UTAH DI-
VISION OF OIL, GAS
AND MINING. R.J.
FIRTH, Associate Direc-
tor, Oil and Gas
Published in the Uintah
Basin Standard March 29,
1994

NOTICE

The Town of Altamont
will be accepting bids on
the following surplus
equipment: One (1) 1961
Adams Motor-Grader
(Grader will be sold in AS-
IS condition, with no war-
ranties)

Scaled bids will be ac-
cepted until 5:00 p.m.
Wednesday April 13, 1994.
Bids should be mailed to:
Town of Altamont, Box 57,
Altamont, Utah 84001. A
minimum bid of \$1500,
must be submitted. Any-
one wishing to examine the
equipment can see it at the
Altamont City Shed located
behind 1st Security Band
on April 8, 1994 between
the hours of 10:00 a.m. and
12:00 p.m. Bids will be
opened at 7:30 p.m. on
April 13, 1994 at the
Altamont Town Hall.

The Town of Altamont
reserves the right to accept
or reject any or all bids.
Published in the Uintah
Basin Standard March 29,
1994

NOTICE OF PUBLIC HEARING

The Town of Altamont
will be conducting a Public
Hearing on the status of it's
garbage collection system.
Hearing Date: April 6, 1994
Time: 7:00 p.m. Location:
Altamont Town Hall.

Altamont is facing a
change in the cost of gar-
bage collection. A Public
Hearing is being held to
gather in-put from town
citizens on the garbage col-
lection system. Several op-
tions will be discussed. This
effects all residents in the
town. Please plan to attend
this meeting.

Town Council
Published in the Uintah
Basin Standard March 29,
1994

PUBLIC NOTICE

On March 22, 1994,
Ashley National Forest
Supervisor, Duane Tucker
made a decision to imple-
ment Alternative #2 in the
Environmental Assessment
for Noxious Weed Man-
agement. Alternative #2
involves treating noxious
weeds using preventive,
manual, mechanical, bio-
logical and/or chemical
methods.

The associated Decision
Notice and Finding of No
Significant Impact are
available upon request from
the Ashley National For-
est, 355 North Vernal Ave.,
Vernal, Utah 84078.

This decision is subject
to appeal pursuant to For-
est Service regulations 36
CFR 217. Appeals must be
filed within 45 days from
the date of publication of
this notice in the Vernal
Express. An appeal must
be postmarked by May 7,
1994. Notice of Appeals
must meet the requirements
of 36 CFR 217.9.

Published in the Uintah
Basin Standard March 29,
1994

NOTICE OF PUBLIC HEARING

PUBLIC NOTICE is
hereby given that a public
hearing will be held on
April 12th, 1994 from
11:00 am to 11:30 am in
the Commission Cham-
bers, in Duchesne, Utah.

The purpose of the hear-
ing is for review and com-
ment on the following item:
A Zone Change to the 2.5
Acre Zone for Tom
Golinski.

Said Zone Change to be
located as follows: Town-
ship 2 South, Range 1 West
USM: Section 7: Begin at
the SW Corner of Section;
thence N 1130; thence E
495; thence N 190; thence
E 825; thence 1320; thence
E 660; thence S 660; thence
E 660; thence S 1980;
thence W 2640 to Point of
Beginning (Proposed Cove-
ntry Cove Estates) (North
of Sterling Meadows Sub-
division)

Duchesne County Com-
mission

Attest Pat Stratton
For further information
contact Jack Wood, Plan-
ning and Community De-
velopment Director, at 738-
2435, 722-3997 or 1-800-
448-2107, extension 195.
Published in the Uintah
Basin Standard March 29,
April 5, 1994

GENERAL NOTICE TO CONTROL NOXIOUS WEEDS

Notice is hereby given
this 1st day of April, 1994,
pursuant to the Utah Nox-
ious Weed Act, Section 7,
to every person who owns
or controls land in
Duchesne County, Utah,
that noxious weeds stand-
ing, being, or growing on
such land shall be con-
trolled and the spread of
same prevented by effec-

tive cutting, tillage, crop-
ping, pasturing, or treating
with chemicals or other ef-
fective methods, or combi-
nation thereof, approved by
the County Weed Supervi-
sor, as often as may be re-
quired to prevent the weed
from blooming and matur-
ing seeds, or spreading by
root, root stalks or other
means.

Upon failure to comply
with this notice, the owner
or person in possession of
property upon which nox-
ious weeds are present shall
be deemed negligent and
enforced control measures
may be imposed at the dis-
cretion of county authori-
ties. Expenses of control
measures employed by the
county shall be paid directly
by the owner or person in
possession of the property,
or shall constitute a lien on
the property, and become
collectible by taxes.

The following are de-
clared noxious weeds for
the State of Utah and the
county of Duchesne;

*Bermudagrass, Musk
Thistle, Bindweed,

(Wi
Qua
Pep
Whi
wee
Scot
Gra:
Spru
fuse
Woa
ted
Kna
This

*
ingto
C
of w
Dast
C
sor,
Publ
Basi
Apri

FOR
AND
Th
Park

Roosevelt Fridays in

Clean-up will begin April 1. I
dumpsters will be provided
Roosevelt City at the follow-
ing locations: vacant lot at 650 N
600 East; vacant lot on Lay
Street between 300 East and
east; vacant lot by Roosevelt Ci
and Roosevelt City Building, n
side of the lot. These dumps
will be in place until Satur
April 9 only.

No tree limbs to be place
dumpsters. Please take limbs to
designated spot south of Stew
Thriftway.

During the month of April,
crews will pick up citizens clear
debris each Friday as follows: Fri
April 8, west of State Street
north of Lagoon Street #1; Fri
April, 15, east of State Street
north of Lagoon #2; Friday, Apri

CALL COLDWELL

DEADLINES
FOR THE

Lomax Exploration Company


P.O. Box 1446
Roosevelt, Utah 84066
(801) 722-5103
FAX (801) 722-9149

May 5, 1994



State of Utah
Division of Oil, Gas & Mining
Attn: Dan Jarvis
355 West North Temple
Three Triad Center - Ste. 350
Salt Lake City, Utah 84180-1203

Bureau of Land Management
Attn: Ed Foresman
170 North 500 East
Vernal, Utah 84078



MAY 6 1994

DIVISION OF
OIL GAS & MINING

RE: MONUMENT BUTTE FEDERAL #8-34
SE/NE SECTION 34, T8S, R16E
MONUMENT BUTTE GR "D" UNIT
LEASE #U-16535
UNIT #83688U6800

Dear Gentlemen:

Please find enclosed a "Step Rate Test" that was conducted on May 5, 1994 for the above referenced well. As the test indicates the parting pressure appears to be 1360#, were currently injecting at 1350#

If you should have any questions, please don't hesitate to call me in the Roosevelt office at 801-722-5103.

Sincerely,




Brad Mecham
Regional Production Manager


Enclosures

/kj

MONUMENT BUTTE 8-34

STEP RATE TEST (5/5/94)

DEPT OF
MINE & MINING



LOMAX EXPLORATION COMPANY

MONUMENT BUTTE FEDERAL #8-34

SE/NE SEC. 34, T8S, R16E

DUCHESNE CO., UTAH

API #43-013-30843

MONUMENT BUTTE GREEN RIVER "D" UNIT


CASING INTEGRITY TEST

APRIL 11, 1994

<u>TIME</u>	<u>TEST</u>
0 MIN	1040# PSIG
10 MIN	1040#
20 MIN	1030#
30 MIN	1030#
40 MIN	1030#
50 MIN	1030#
60 MIN	1020#
70 MIN	1020#
80 MIN	1020#
90 MIN	1020#
100 MIN	1020#
110 MIN	1020#
120 MIN	1020#

TUBING PRESSURE WAS 0#

TEST CONDUCTED BY - JODY LIDDELL W/ LOMAX EXPLORATION



AFFIDAVIT OF PUBLICATION

County of Duchesne,

STATE OF UTAH

I, Craig L. Ashby on oath, say that I am the
PUBLISHER of the Uintah Basin Standard, a weekly
newspaper of general circulation, published at
Roosevelt, State and County aforesaid, and that a certain
notice, a true copy of which is hereto attached, was
published in the full issue of such newspaper
for 1 consecutive issues, and that the first
publication was on the 29 day of March,
1994, and that the last publication of such notice was
in the issue of such newspaper dated the 29 day
of March, 1994.


Subscribed and sworn to before me this

1 day of

April, 1994

Jean Ercanbrack

Notary Public



NOTICE OF AGENCY ACTION

CAUSE NO. UIC-148

IN THE MATTER OF
THE APPLICATION OF
LOMAX EXPLORA-
TION COMPANY FOR
ADMINISTRATIVE AP-
PROVAL OF THE
MONUMENT FEDERAL
#8-34 WELL LOCATED
IN SECTION 34, TOWN-
SHIP 8 SOUTH, RANGE
16 EAST, S.L.M.,
DUCHESENE COUNTY,
UTAH, AS A CLASS II
INJECTION WELL

THE STATE OF UTAH
TO ALL PERSONS IN-
TERESTED IN THE
ABOVE ENTITLED
MATTER.

Notice is hereby given
that the Division is com-
mencing an informal adju-
dicative proceeding to con-
sider the application of
Lomax Exploration Com-
pany for administrative ap-
proval of the Monument
Federal #8-34 Well, located
in Section 34, Township 8
South, Range 16 East,
Duchesne County, Utah,
for conversion to a Class II
injection well. The pro-
ceeding will be conducted
in accordance with Utah
Admin. R. 649-10, Admin-
istrative Procedures.

The well will be selec-

tively perforated from 5024'
to 5043' in the Green River
formation (D sand interval).
The applicant has requested
a maximum injection pres-
sure of 2000 psig which
will be confirmed by con-
ducting a step-rate pressure
test following the comple-
tion of the well. The re-
quested injection volume
is approximately 1000
bwpd.

Any person desiring to
object to the application or
otherwise intervene in the
proceeding, must file a writ-
ten protest or notice of in-
tervention with the Divi-
sion within fifteen days of
the date of publication of
this notice. If such a protest
or notice of interventions is
received, a hearing will be
scheduled before the Board
of Oil, Gas and Mining.
Protestants and/or interve-
nors should be prepared to
demonstrate at the hearing
how this matter affects their
interests.

DATED this 22nd day
of March 1994.

STATE OF UTAH DI-
VISION OF OIL, GAS
AND MINING. R.J.
FIRTH, Associate Direc-
tor, Oil and Gas
Published in the Uintah
Basin Standard March 29,
1994

143 SOUTH MAIN ST.
P.O. BOX 45838
SALT LAKE CITY, UTAH 84145
ED. TAX I.D. # 87-0217663

Newspaper Agency Corporation

The Salt Lake Tribune (NA) DESERET NEWS

gil
pff

CUSTOMER'S
COPY

LEGAL ADVERTISING INVOICE

CUSTOMER NAME AND ADDRESS	ACCOUNT NUMBER	BILLING DATE
DIV OF OIL, GAS & MINING 355 W NO TEMPLE, #350 SALT LAKE CITY, UT 84180	LE-5385340	03/28/94

FOR BILLING INFORMATION
CALL (801) 237-2822

AFFIDAVIT OF PUBLICATION

AS NEWSPAPER AGENCY CORPORATION LEGAL BOOKKEEPER, I CERTIFY THAT THE ATTACHED ADVERTISEMENT OF NOTICE OF AGENCY ACTION CAUSE NO. UIC-148 BEFORE FOR DIV OF OIL, GAS & MINING WAS PUBLISHED BY THE NEWSPAPER AGENCY CORPORATION, AGENT FOR THE SALT LAKE TRIBUNE AND DESERET NEWS, DAILY NEWSPAPERS PRINTED IN THE ENGLISH LANGUAGE WITH GENERAL CIRCULATION IN UTAH, AND PUBLISHED IN SALT LAKE CITY, SALT LAKE COUNTY IN THE STATE OF UTAH.

PUBLISHED ON MAR 28 1994
SIGNATURE [Signature]
DATE 03/28/94

ACCOUNT NAME			TELEPHONE
DIV OF OIL, GAS & MINING			801-538-5340
SCHEDULE			AD NUMBER
MAR 28 1994			30820050
CUST. REF. NO.	CAPTION		MISC. CHARGES
CAUSE #UIC-148	NOTICE OF AGENCY ACTION CAUSE NO. UIC-148 BEFORE		.00
SIZE	TIMES	RATE	AD CHARGE
76 LINES 1 COLUMN	1	1.64	124.64
DUE AND PAYABLE ON RECEIPT OF THIS INVOICE			TOTAL AMOUNT DUE 124.64

THANK YOU FOR USING LEGAL ADVERTISING.

PLEASE RETURN THIS PORTION WITH YOUR PAYMENT IN THE ENCLOSED ENVELOPE

LEGAL ADVERTISING ADV06-NT

ACCOUNT NUMBER	AD NUMBER	BILLING DATE	PAY THIS AMOUNT
LE-5385340	30820050	03/28/94	124.64

LEGAL ADVERTISING

PLEASE REMIT TO:

NEWSPAPER AGENCY CORPORATION
P.O. BOX 45838
SALT LAKE CITY, UTAH 84145-0838

MAKE CHECKS PAYABLE TO:
NEWSPAPER AGENCY CORPORATION
DIV OF OIL, GAS & MINING
355 W NO TEMPLE, #350
SALT LAKE CITY, UT 84180


COPY

07631770620050900000000000000012464187428817311610111111111111111123575

PLEASE REMOVE THIS STUB

Lomax Exploration Company

P.O. Box 1446
Roosevelt, Utah 84066
(801) 722-5103
FAX (801) 722-9149



August 10, 1994

Lomax



Bureau of Land Management
170 South 500 East
Vernal, Utah 84078

State of Utah
Division of Oil, Gas & Mining
Attn: Dan Jarvis
355 West North Temple
3 Triad Center, Suite 350
Salt Lake City, Utah 84180-1203

RE: Monument Butte Federal #8-34
SE/NE Sec. 34, T8S, R16E
Duchesne County, Utah

Gentlemen:

Please find enclosed the "Sundry Notice and Report of Wells" report, converting the above referenced well to a water injection well. I have also enclosed a copy of the chronological report of the conversion and a down hole diagram of the well after conversion.

If you should have any questions, please don't hesitate to call me in the Roosevelt office at 801-722-5103.

Sincerely,

Brad Mechem
Regional Production Manager

/kj

Enclosures

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well

☐ Oil Well ☐ Gas Well ☒ Other **Water Injector**

2. Name of Operator

LOMAX EXPLORATION

3. Address and Telephone No.

P.O. Box 1446 Roosevelt, Utah 84066 (801) 722-5103

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

701' FEL 2059' FNL Sec. 34, T8S, R16E SE/NE

5. Lease Designation and Serial No.

**U-16535
8368806800**

6. If Indian, Allottee or Tribe Name

7. If Unit or CA, Agreement Designation

Monument Butte GR "D"

8. Well Name and No.

MONUMENT BUTTE #8-34

9. API Well No.

43-013-30843

10. Field and Pool, or Exploratory Area

Monument Butte

11. County or Parish, State

Duchesne, Utah

12. CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

- ☐ Notice of Intent
☐ Subsequent Report
☐ Final Abandonment Notice

TYPE OF ACTION

- ☐ Abandonment
☐ Recompletion
☐ Plugging Back
☐ Casing Repair
☐ Altering Casing
☐ Other _____
- ☐ Change of Plans
☐ New Construction
☐ Non-Routine Fracturing
☐ Water Shut-Off
☒ Conversion to Injection
☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Operator reports that the referenced well was converted to injection as follows:

3/22/94 - POOH w/ tbg, breaking & redoping collars w/ teflon dope

3/23/94 - Set 5½" pkr @ 4974' in 13,000# tension. Test csg to 1200# - held. Wait for final approval for injection

4/11/94 - Conduct casing integrity test

4/19/94 - Put well on injection @ 10:00 A.M.

14. I hereby certify that the foregoing is true and correct

Signed Brad Meckam Title Production Manager Date August 10, 1994

(This space for Federal or State office use)

Approved by _____ Title _____ Date _____
Conditions of approval, if any:

MONUMENT BUTTE FEDERAL #8-34
SE/NE Sec. 34, T8S, R16E
Duchesne County, Utah

CONVERSION TO WATER INJECTION

B & B WELL SERVICE

3/22/94

(DAY 1)

Present Operation: RIH w/casing scraper.

Remarks: 3/21/94 - MI & RU - B & B Well Service. RU hot oil truck to csg, pump 140 bbls water w/ 10 gals Well Aid 314. Jar on pump to unseat. Flush tbg w/ 50 bbls, POOH & lay down polish rod, 1-6' pony and 94 - 3/4" scraped rods, 100 - 3/4" plain rods, 4 weight rods, 1 - 1/2" THD pump. Change over for tbg, NDWH. Release anchor, NUBOPS. RU floor and tongs, SDFN.

3/23/94

(DAY 2)

Present Operation: RIH w/ BHA

Remarks: 3/22/94 - POOH & lay down anchor and seat nipple. Make up csg scraper, RIH to 5220'. POOH w/ tbg, breaking and redoping collars with Teflon dope. Lay down scraper, SDFN.


3/24/94

(DAY 3)

Present Operation: Wait on final approval for injection

Remarks: 3/23/94 - Make up 5 1/2" Arrow Set I PKR. RIH w/ 158 jts and set pkr. Rig up hot oil truck to tbg, pressure tbg up to 2000# to test BP - held. Release pkr, pull above perms, leaving 151 jts tbg in hole. NDBOPS. Displace 70 bbls wtr w/ pkr fluid down csg. Set pkr in 13,000# tension @ 4974'. NUWH, pressure csg to 1200# - held. RDSU & MOL. Wait for final approval to place well on injection.

MONUMENT FEDERAL #8-34
SE/NE SECTION 34, T8S, R16E
DUCHESNE COUNTY, UTAH



BM 4/15/94



State of Utah
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

RECEIVED APR 28 1994

Michael O. Leavitt
Governor

Ted Stewart
Executive Director

James W. Carter
Division Director

355 West North Temple
3 Triad Center, Suite 350
Salt Lake City, Utah 84180-1203
801-538-5340
801-359-3940 (Fax)
801-538-5319 (TDD)

April 15, 1994

Lomax Exploration Company
P.O. Box 1446
Roosevelt, Utah 84066

Re: Monument Federal #8-34 Well, Section 34, Township 8 South, Range 16 East,
Duchesne County, Utah

Gentlemen:

Pursuant to Utah Admin. Code R649-5-3-3, the Division of Oil, Gas and Mining (the "Division") issues its administrative approval for conversion of the referenced well to a Class II injection well. Accordingly, the following stipulations shall apply for full compliance with this approval:

1. Compliance with all applicable requirements for the operation, maintenance and reporting for Underground Injection Control ("UIC") Class II injection wells pursuant to Utah Admin. Code R649-1 et seq.
2. Conformance with all conditions and requirements of the complete application submitted by Lomax Exploration Company.

Enclosed with this letter is the Underground Injection Control Permit for this well. If you have any questions regarding this approval or the necessary requirements, please contact Dan Jarvis at this office.


Sincerely,

R.J. Firth

Associate Director

ldc

cc: Dan Jackson, Environmental Protection Agency
Bureau of Land Management, Vernal





State of Utah
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

Michael O. Leavitt
Governor

Ted Stewart
Executive Director

James W. Carter
Division Director

355 West North Temple
3 Triad Center, Suite 350
Salt Lake City, Utah 84180-1203
801-538-5340
801-359-3940 (Fax)
801-538-5319 (TDD)

UNDERGROUND INJECTION CONTROL
PERMIT

Cause No.: UIC-148

API No.: 43-013-30843

Well Name/Number: Monument Federal #8-34

Operator: Lomax Exploration Company

Well Type: Enhanced Recovery (waterflood)

Location: Section 34 , Township 8S, Range 16E, County: Duchesne

Approval Date: April 15, 1994

PERMIT CONDITIONS


Maximum Allowed Injection Pressure: 2000 psig

Maximum Allowed Injection Rate: 1000 bbls per day

Stipulations of Approval

None

Approved:




Date 15 April '94

R.J. Firth, Associate Director, Oil and Gas

Lomax Exploration Company

A subsidiary of Inland Resources Inc.



Announcing
Our Name Change

From

Lomax Exploration Company

To

**Inland Production
Company**

XN 5160 assigned 7/26/95. Lee

Field And Corporate Office Locations Remain The Same:

Corporate Office:

Inland Resources Inc.

475 Seventeenth Street, Suite 1500

Denver, CO 80202

Field Office:


W. Pole Line Road

P.O. Box 1446

Roosevelt, Utah 84066

United States Department of the Interior
BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, Utah 84145-0155



IN REPLY REFER TO:
3100
SL-065914 et al
(UT-923)

JUL 25 1995

NOTICE

Inland Production Company : Oil and Gas Leases
475 Seventeenth St., Ste. 1500 : SL-065914 et al
Denver, Colorado 80202 :

Name Change Recognized

Acceptable evidence has been received in this office concerning the change of name of Lomax Exploration Company to Inland Production Company on Federal oil and gas leases.

The oil and gas lease files identified on the enclosed exhibit have been noted as to the name change. We are notifying the Minerals Management Service and all applicable Bureau of Land Management offices of the name change by a copy of this notice. If additional documentation for changes of operator are required by our Field Offices, you will be contacted by them.

For our purposes, the name change is recognized effective June 29, 1995 (Secretary of State's approval date).

Due to the name change, the name of the principal/obligor on the bond is required to be changed from Lomax Exploration Company to Inland Production Company on Bond No. 4488944 (BLM Bond No. UT0056). You may accomplish this name change either by consent of the surety on the original bond or by a rider to the original bond. Otherwise, a replacement bond with the new name should be furnished to this office. BLM Bond Nos. MT0771 and WY0821 should also be changed for the bonds held by Montana and Wyoming respectively.

/s/ ROBERT LOPEZ

Chief, Branch of Mineral
Leasing Adjudication

Enclosure
1-Exhibit (1 p)

cc: Hartford Accident & Indemnity Co.
Hartford Plaza
Hartford, CT 06115

bc: Moab District Office
Vernal District Office
Montana State Office
Wyoming State Office
Eastern States Office
MMS--Data Management Division, MS 3113, P.O. Box 5860, Denver, CO 80217
State of Utah, Attn: Lisha Cordova, Division of Oil, Gas & Mining,
355 West North Temple, 3 Triad Center, Suite 350, SLC, UT 84180
Teresa Thompson (UT-922)
Dianne Wright (UT-923)

EXHIBIT

SL-065914	U-36846	UTU-66185
SL-071572A	U-38428	UTU-67170
U-02458	U-45431	UTU-68548
U-15855	U-47171	UTU-69060
U-16535	U-50376	UTU-69061
U-26026	U-62848	UTU-72103
U-34173	UTU-65965	UTU-72104
U-36442	UTU-66184	UTU-73088

Lomax Exploration Company

A subsidiary of Inland Resources Inc.



July 13, 1995

State of Utah Department of Natural Resources
Attention: Ms Becky Pritchett
355 W. North Temple
3 Triad Center, Suite 400
Salt Lake City, Utah 84180-1204

RE: Corporate Name Change

Dear Sir or Madame:

Effective July 1, 1995, Lomax Exploration Company will have taken the steps necessary to change its name to **Inland Production Company**. A Certificate issued by the Texas Secretary of State evidencing the name change is attached for your files. We have also attached to this letter those Utah State leases (Exhibit "B") and wells (Exhibit "A") affected by this name change. We have attempted to provide a complete list from the records we have. The intent is to include all leases and wells that Lomax Exploration Company operates or has an interest in.


Riders changing the Principal from Lomax Exploration Company to Inland Production Company under Nationwide Oil and Gas Bond # 4488944 for Lomax Exploration Company will be furnished to the State of Utah in the very near future.

Please amend your records by substituting Inland Production Company in place of Lomax Exploration Company on the leases and wells listed on the attached exhibits. In the future we will begin submitting notices and permits for new operations after July 1, 1995 in the name of Inland Production Company.

Should a fee be required or should you need further information or documents relating to our name change please contact the undersigned at your convenience at the following number: (303) 292-0900 or Cheryl Cameron at our Roosevelt, Utah office (801) 722-5103.

Sincerely yours,

Chris A Potter, CPL
Manager of Land



The State of Texas

Secretary of State
JUNE 30, 1995

MIKE PARSONS...GLAST, PHILLIPS & MURRAY
2200 ONE GALLERIA TWR, 13355 NOEL RD, LB48
DALLAS ,TX 75240-6657

RE:
INLAND PRODUCTION COMPANY
CHARTER NUMBER 00415304-00

IT HAS BEEN OUR PLEASURE TO APPROVE AND PLACE ON RECORD YOUR ARTICLES OF AMENDMENT. A COPY OF THE INSTRUMENT FILED IN THIS OFFICE IS ATTACHED FOR YOUR RECORDS.

THIS LETTER WILL ACKNOWLEDGE PAYMENT OF THE FILING FEE.

IF WE CAN BE OF FURTHER SERVICE AT ANY TIME, PLEASE LET US KNOW.

VERY TRULY YOURS,




Antonio O. Garza, Jr., Secretary of State



The State of Texas

Secretary of State

CERTIFICATE OF AMENDMENT

FOR

INLAND PRODUCTION COMPANY

FORMERLY

LOMAX EXPLORATION COMPANY
CHARTER NUMBER 00415304

THE UNDERSIGNED, AS SECRETARY OF STATE OF THE STATE OF TEXAS,
HEREBY CERTIFIES THAT THE ATTACHED ARTICLES OF AMENDMENT FOR THE ABOVE
NAMED ENTITY HAVE BEEN RECEIVED IN THIS OFFICE AND ARE FOUND TO
CONFORM TO LAW.

ACCORDINGLY THE UNDERSIGNED, AS SECRETARY OF STATE, AND BY VIRTUE
OF THE AUTHORITY VESTED IN THE SECRETARY BY LAW, HEREBY ISSUES THIS
CERTIFICATE OF AMENDMENT.

DATED JUNE 29, 1995

EFFECTIVE JUNE 29, 1995




Antonio O. Garza, Jr., Secretary of State

ARTICLES OF AMENDMENT
TO THE
ARTICLES OF INCORPORATION
OF
LOMAX EXPLORATION COMPANY

FILED
In the Office of the
Secretary of State of Texas

JUN 29 1995

Corporations Section

Pursuant to the provisions of Part Four of the Texas Business Corporation Act, the undersigned corporation adopts the following articles of amendment to its Articles of Incorporation:

1. Name. The name of the corporation is LOMAX EXPLORATION COMPANY.
2. Statement of Amendment. The amendment alters or changes Article One of the original Articles of Incorporation to read in full as follows:

"Article One. The name of the corporation is INLAND PRODUCTION COMPANY."
3. Shareholders. The number of shares of the corporation outstanding at the time of such adoption was 205,315, there being 107,546 Common Shares and 97,769 Non-voting Preferred Shares; and the number of shares entitled to vote thereon was 107,546.
4. Adoption by Shareholders. Only the holders of Common Shares of the corporation are entitled to vote on the amendment. The shareholders adopted the foregoing amendment by unanimous written consent dated June 23, 1995, pursuant to the provisions of Article 9.10 of the Texas Business Corporation Act and, therefore, no notice was required to be delivered under said Article 9.10.
5. Adoption by Board of Directors. The Board of Directors adopted said amendment by a consent in writing signed by all Directors.
6. Future Effective Date. This amendment will become effective on July 1, 1995, at 12:01 a.m.

EXECUTED June 26, 1995.



Kyle R. Miller, President

S:\CLIENT-709004\LOMAX.AMD


STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

TRANSFER OF AUTHORITY TO INJECT - UIC FORM 5

Well name and number: _____
Field or Unit name: MONUMENT BUTTE (GREEN RIVER "D") UNIT API no. _____
Well location: QQ _____ section _____ township 8S & ^{9S} range 16E county Duchesne
Effective Date of Transfer: June 29, 1995

CURRENT OPERATOR


Transfer approved by:

Name Chris A Potter Company Lomax Exploration Company
Signature  Address 475 17th Street, Ste 1500
Title Attorney-in-Fact Denver, Colorado 80202
Date August 1, 1995 Phone (303) 292-0900

Comments:

NEW OPERATOR

Transfer approved by:

Name Chris A Potter Company Inland Production Company
Signature  Address 475 17th Street, Ste 1500
Title Attorney-in-Fact Denver, Colorado 80202
Date August 1, 1995 Phone (303) 292-0900

Comments:

(State use only)

Transfer approved by  Title E. Van M...Approval Date 8-7-95

FAX COVER SHEET



RESOURCES INC.
475 17th Street, Suite 1500
Denver, CO 80202
303-292-0900, Fax #303-296-4070

DATE: August 8, 1995
TO: Lisha Cordova
COMPANY: State of Utah - Division of Oil, Gas and Mining
FAX NUMBER: 801 359 3940
FROM: Chris A Potter

NUMBER OF PAGES: 1 (INCLUDING COVER SHEET):

RE: Transfer of Authority to Inject
Lomax Exploration Company to Inland Production Company

I hope the info I sent to you August 1st was acceptable regarding our name change and your phone call to me last week.....

If there is anything missing or you need additional info, please let me know. I am located in our Denver office.....

Division of Oil, Gas and Mining
OPERATOR CHANGE WORKSHEET

Attach all documentation received by the division regarding this change.
 Initial each listed item when completed. Write N/A if item is not applicable.

Routing: (GIL) *[initials]*

1-DEC 7-PL
2-LWP 8-SJ
3-DTS 9-FILE
4-VLC
5-RJF
6-LWP

- ☒ Change of Operator (well sold) ☐ Designation of Agent
☐ Designation of Operator ☐ Operator Name Change Only

(MERGER)

The operator of the well(s) listed below has changed (EFFECTIVE DATE: 6-29-95)

TO (new operator) INLAND PRODUCTION COMPANY
 (address) PO BOX 1446
ROOSEVELT UT 84066
KEBBIE JONES
 phone (801) 722-5103
 account no. N 5160

FROM (former operator) LOMAX EXPLORATION COMPANY
 (address) PO BOX 1446
ROOSEVELT UT 84066
KEBBIE JONES
 phone (801) 722-5103
 account no. N 0580

Well(s) (attach additional page if needed):

Name: **SEE ATTACHED**	API: <u>013-30843</u>	Entity: _____	Sec. _____	Twp. _____	Rng. _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec. _____	Twp. _____	Rng. _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec. _____	Twp. _____	Rng. _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec. _____	Twp. _____	Rng. _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec. _____	Twp. _____	Rng. _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec. _____	Twp. _____	Rng. _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec. _____	Twp. _____	Rng. _____	Lease Type: _____

OPERATOR CHANGE DOCUMENTATION

- See* 1. (Rule R615-8-10) Sundry or other legal documentation has been received from former operator (Attach to this form). *(Ref'd 7-14-95)*
- N/A* 2. (Rule R615-8-10) Sundry or other legal documentation has been received from new operator (Attach to this form).
- See* 3. The Department of Commerce has been contacted if the new operator above is not currently operating any wells in Utah. Is company registered with the state? (yes no) ____ If yes, show company file number: ____ *(7-28-95)*
- See* 4. (For Indian and Federal Wells ONLY) The BLM has been contacted regarding this change (attach Telephone Documentation Form to this report). Make note of BLM status in comments section of this form. Management review of **Federal and Indian** well operator changes should take place prior to completion of steps 5 through 9 below.
- See* 5. Changes have been entered in the Oil and Gas Information System (Wang/IBM) for each well listed above. *(7-31-95)*
- LWP* 6. Cardex file has been updated for each well listed above. *8-16-95*
- LWP* 7. Well file labels have been updated for each well listed above. *8-22-95*
- See* 8. Changes have been included on the monthly "Operator, Address, and Account Changes" memo for distribution to State Lands and the Tax Commission. *(7-31-95)*
- See* 9. A folder has been set up for the Operator Change file, and a copy of this page has been placed there for reference during routing and processing of the original documents.

ENTITY REVIEW

- Yes 1. (Rule R615-8-7) Entity assignments have been reviewed for all wells listed above. Were entity changes made? (yes/no) no (If entity assignments were changed, attach copies of Form 6, Entity Action Form).
- N/A 2. State Lands and the Tax Commission have been notified through normal procedures of entity changes.

BOND VERIFICATION (~~Fee wells only~~) *Trust Lands Admin. / Rider or Repl. in Progress.*

- N/A Yes 1. (Rule R615-3-1) The new operator of any fee lease well listed above has furnished a proper bond.
- ___ 2. A copy of this form has been placed in the new and former operators' bond files.
- ___ 3. The former operator has requested a release of liability from their bond (yes/no) ___. Today's date _____ 19___. If yes, division response was made by letter dated _____ 19__.

LEASE INTEREST OWNER NOTIFICATION RESPONSIBILITY

- N/A 1. (Rule R615-2-10) The former operator/lessee of any **fee lease** well listed above has been notified by letter dated _____ 19__, of their responsibility to notify any person with an interest in such lease of the change of operator. Documentation of such notification has been requested.
- OTS 2. Copies of documents have been sent to State Lands for changes involving State leases.
8/23/95 sent to Ed Bower

FILMING

- ✓ 1. All attachments to this form have been microfilmed. Date: August 30 1995.

FILING

- ___ 1. Copies of all attachments to this form have been filed in each well file.
- ___ 2. The original of this form and the original attachments have been filed in the Operator Change file.

COMMENTS

950726 BLM/SL Appr. eff. 6-29-95.

STATE OF UTAH
INVENTORY OF INJECTION WELLS

OPERATOR	API NO.	WELL	TNS	RGE	SE	WELLTYPE	INDIAN COUNT
*****	*****	*****	***	***	**	*****	*****
✓LOMAX	4-35/43-013-30605	MONUMENT BUT	08S	16E	35	INJW	U16535 N
✓LOMAX	43-013-30624	STATE 5-36	08S	16E	36	INJW	ML22061 N
✓LOMAX	43-013-30592	STATE 1-36	08S	16E	36	INJW	ML22061 N
✓LOMAX	43-013-30787	12-32	08S	17E	32	INJW	ML22060 Y
✓LOMAX	43-013-30779	FED.15-28	08S	16E	28	INJW	U26026A N
✓LOMAX	43-013-31372	14A-28	08S	16E	28	INJW	U68528A N U75L071572A
✓LOMAX	13-32/43-013-31403	GILSONITE ST	08S	17E	32	INJW	ML22060 Y
✓LOMAX	43-013-30658	GILSONITE 7-32	08S	17E	32	INJW	ML22060 Y
✓LOMAX	8-34/43-013-30843	MONUMENT BUT	08S	16E	34	INJW	U16535 Y
✓LOMAX	43-013-30693	FEDERAL 3-33	08S	16E	33	INJW	U34173 N
✓LOMAX	15-35/43-013-31264	MONUMENT FED	08S	16E	35	INJW	U16535 N
✓LOMAX	43-013-30686	FEDERAL 5-35	08S	16E	35	INJW	U16535 N
✓LOMAX	2-35/43-013-30606	MONUMENT BUT	08S	16E	35	INJW	U16535 N
✓LOMAX	3-35/43-013-30608	MONUMENT BUT	08S	16E	35	INJW	U16535 N
✓LOMAX	13-35/43-013-30745	MONUMENT BUT	08S	16E	35	INJW	U16535 N

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS, AND MINING

1. SUNDRY NOTICES AND REPORTS ON WELLS (Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use "APPLICATION FOR PERMIT-" for such proposals.)		5. LEASE DESIGNATION AND SERIAL NO. U-16535	
2. NAME OF OPERATOR INLAND PRODUCTION COMPANY		6. IF INDIAN, ALLOTTEE OR TRIBAL NAME N/A	
3. ADDRESS OF OPERATOR Route 3, Box 3630, Myton Utah 84052 (435-646-3721)		7. UNIT AGREEMENT NAME NA	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.* See also space 17 below.) At surface SE/NE 2059 FNL 0701 FEL		8. FARM OR LEASE NAME MONUMENT FEDERAL 8-34	
14. API NUMBER 43-013-30843		9. WELL NO. MONUMENT FEDERAL 8-34	
15. ELEVATIONS (Show whether DF, RT, GR, etc.) 5600 GR		10. FIELD AND POOL OR WILDCAT MONUMENT BUTTE	
		11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA SE/NE Section 34, T08S R16E	
		12. COUNTY OR PARISH DUCHESNE	13. STATE UT

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data			
NOTICE OF INTENTION TO:		SUBSEQUENT REPORT OF:	
TEST WATER SHUT-OFF <input type="checkbox"/>	PULL OR ALTER CASING <input type="checkbox"/>	WATER SHUT-OFF <input type="checkbox"/>	REPAIRING WELL <input type="checkbox"/>
FRACTURE TREAT <input type="checkbox"/>	MULTIPLE COMPLETE <input type="checkbox"/>	FRACTURE TREATMENT <input type="checkbox"/>	ALTERING CASING <input type="checkbox"/>
SHOOT OR ACIDIZE <input type="checkbox"/>	ABANDON* <input type="checkbox"/>	SHOOTING OR ACIDIZING <input type="checkbox"/>	ABANDONMENT* <input type="checkbox"/>
REPAIR WELL <input type="checkbox"/>	<input type="checkbox"/>	(OTHER) <u>Perform 5 year MIT</u>	<input type="checkbox"/>
(OTHER) <input type="checkbox"/>	<input type="checkbox"/>	(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)	

17 DESCRIBE PROPOSED OR COMPLETED OPERATIONS. (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

The MIT was conducted on the subject well to satisfy the five year MIT. On 6-7-00 the casing was pressured up to 950 psi and charted for thirty minutes with no leak off. Mr. Dennis Ingram with the DOGM was in attendance and approved the test.

Accepted by the
Utah Division of
Oil, Gas and Mining

18 I hereby certify that the foregoing is true and correct
SIGNED Rod Bird TITLE Production Foreman DATE 6/7/00

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____

CONDITIONS OF APPROVAL, IF ANY:

* See Instructions On Reverse Side

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY

RECEIVED

JUN 09 2000

DIVISION OF
OIL, GAS AND MINING

Mechanical Integrity Test Casing or Annulus Pressure Test

Inland Production Company

Rt. 3 Box 3630

Myton, UT 84052

435-646-3721

Witness: Dennis Ingram Date 6/7/00 Time 8:00 (a)m/pm
Test Conducted by: Roy Liddell
Others Present: _____

Well: Monument Butte 8-34-8-16 Field: Monument Butte

Well Location: SE/NE sec 34, T8S, R16E API No: 43-013-30843
Duchesne Co, UT

Time	Casing Pressure	
0 min	<u>950</u>	psig
5	<u>950</u>	psig
10	<u>950</u>	psig
15	<u>950</u>	psig
20	<u>950</u>	psig
25	<u>950</u>	psig
30 min	<u>950</u>	psig
35		psig
40		psig
45		psig
50		psig
55		psig
60 min		psig

Tubing pressure: 1950 psig Injecting @ 21.74 BPD

Result: Pass Fail


Signature of Witness: Dennis Ingram

Signature of Person Conducting Test: Roy Liddell

RECEIVED

JUN 09 2000

DIVISION OF
OIL, GAS AND MINING



SIGNED *hal*
MW-M2500-H
3900 W100
DATE PUT ON 8:00 A.M.
TIME PUT ON 8:00 A.M.
METER NUMBER
TIME TAKEN OFF 8:30 A.M.
DATE TAKEN OFF 8-3-54
TUBE BORE SIZE
M.I.T.
MBF 8-34-8-16
TEXAS INSTRUMENT ENGINEERS

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS, AND MINING

1. SUNDRY NOTICES AND REPORTS ON WELLS (Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use "APPLICATION FOR PERMIT-" for such proposals.)		5. LEASE DESIGNATION AND SERIAL NO. U-16535	
2. NAME OF OPERATOR INLAND PRODUCTION COMPANY		6. IF INDIAN, ALLOTTEE OR TRIBAL NAME N/A	
3. ADDRESS OF OPERATOR Rt. 3 Box 3630, Myton Utah 84052 435-646-3721		7. UNIT AGREEMENT NAME NA	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.* See also space 17 below.) At surface SE/NE Section 34, T08S R16E 2059 FNL 701 FEL		8. FARM OR LEASE NAME MONUMENT FEDERAL 8-34-8-16	
		9. WELL NO. MONUMENT FEDERAL 8-34-8-16	
		10. FIELD AND POOL, OR WILDCAT MONUMENT BUTTE	
		11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA SE/NE Section 34, T08S R16E	
14. API NUMBER 43-013-30843	15. ELEVATIONS (Show whether DF, RT, GR, etc.) 5600 GR	12. COUNTY OR PARISH DUCHESNE	13. STATE UT

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data			
NOTICE OF INTENTION TO:		SUBSEQUENT REPORT OF:	
TEST WATER SHUT-OFF <input type="checkbox"/>	PULL OR ALTER CASING <input type="checkbox"/>	WATER SHUT-OFF <input type="checkbox"/>	REPAIRING WELL <input type="checkbox"/>
FRACTURE TREAT <input type="checkbox"/>	MULTIPLE COMPLETE <input type="checkbox"/>	FRACTURE TREATMENT <input type="checkbox"/>	ALTERING CASING <input type="checkbox"/>
SHOOT OR ACIDIZE <input type="checkbox"/>	ABANDON* <input type="checkbox"/>	SHOOTING OR ACIDIZING <input type="checkbox"/>	ABANDONMENT* <input type="checkbox"/>
REPAIR WELL <input type="checkbox"/>	<input type="checkbox"/>	(OTHER) <input checked="" type="checkbox"/>	Conversion to Production
(OTHER) <input type="checkbox"/>	<input type="checkbox"/>	(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)	

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

On 1/16/01 the subject well was changed from injection to a producing status. The injection packer was removed and the production assembly was run in the hole. The well was put on to production 5/7/01.

18. I hereby certify that the foregoing is true and correct

SIGNED <u>Krishna Russell</u> Krishna Russell	TITLE <u>Production Clerk</u>	DATE <u>5/9/01</u>
--	-------------------------------	--------------------

cc: BLM
(This space for Federal or State office use)

APPROVED BY _____ TITLE _____
CONDITIONS OF APPROVAL, IF ANY:

DATE **RECEIVED**

* See Instructions On Reverse Side

DIVISION OF
OIL, GAS AND MINING

STATE OF UTAH
DIVISION OF OIL GAS AND MINING

INJECTION WELL - PRESSURE TEST

Well Name: <u>MON Butte Fld 8-34-8-16</u>	API Number: <u>43-013-30843</u>
Qtr/Qtr: <u>SE/NE</u>	Section: <u>34</u>
Township: <u>8S</u>	Range: <u>16E</u>
Company Name: <u>INLAND PRODUCTION COMPANY</u>	
Lease: State <u> </u>	Fee <u> </u>
Federal <u>U-16535</u>	Indian <u> </u>
Inspector: <u>Lennis L Ingram</u>	Date: <u>06-07-00</u>

Initial Conditions:

Tubing - Rate: Pressure: 1950 psiCasing/Tubing Annulus - Pressure: 950 psi

Conditions During Test:

Time (Minutes)	Annulus Pressure	Tubing Pressure
0	<u>950 PSI</u>	<u>1950 PSI</u>
5	<u>"</u>	<u>1950 "</u>
10	<u>"</u>	<u>1950 "</u>
15	<u>"</u>	<u>1950 "</u>
20	<u>"</u>	<u>1950 "</u>
25	<u>"</u>	<u>1950 "</u>
30	<u>"</u>	<u>1950 "</u>

Results: Pass/Fail

Conditions After Test:

Tubing Pressure: 1950 psiCasing/Tubing Annulus Pressure: 950 psi

COMMENTS: Tested for 5 year rule. Injecting @ 21.74 BPD.
Chart dropped from 1000 PSI To 950 in first few minutes
of test then leveled off. However gauge showed 1000 PSI
throughout test, no drop. Test ended 8:00 AM

Ray Liddell
 Operator Representative

P. 02

FAX NO. 5 646 3031

MAY-31-01 THU 09:13 AM INLAND PRODUCTION CO

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING
ENTITY ACTION FORM - FORM 6

OPERATOR: INLAND PRODUCTION COMPANY
ADDRESS: RT. 3 BOX 3630
MYTON, UT 84052

OPERATOR ACCT. NO. N5160

ACTION CODE	CURRENT ENTITY NO	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					CO	SC	TP	RG	COUNTY		
B A	99999	12391	43-013-32228	Boundary #1-27-8-17	NE/NE	27	8S	17E	Duchesne	May 10, 2001	05/10/01

WELL 1 COMMENTS:

5-31-01

ACTION CODE	CURRENT ENTITY NO	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					CO	SC	TP	RG	COUNTY		
B A	99999	12391	43-013-32226	Boundary #12-27-8-17	NW/SW	27	8S	17E	Duchesne	May 18, 2001	05/18/01

WELL 2 COMMENTS:

5-31-01

ACTION CODE	CURRENT ENTITY NO	NEW ENTITY NO	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					CO	SC	TP	RG	COUNTY		
B	99999	10835	43-013-30843	Mon. Butte #8-34-8-16	SE/NE	34	8S	16E	Duchesne	February 28, 1984	05/07/01

WELL 3 COMMENTS:

ACTION CODE	CURRENT ENTITY NO	NEW ENTITY NO	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					CO	SC	TP	RG	COUNTY		

WELL 4 COMMENTS:

ACTION CODE	CURRENT ENTITY NO	NEW ENTITY NO	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					CO	SC	TP	RG	COUNTY		


WELL 5 COMMENTS:

ACTION CODES (See instructions on back of form)

- A - Establish new entity for new well, single well only.
- B - Add new well to existing entity, group or individual.
- C - Re-assign well from one existing entity to another existing entity.
- D - Re-assign well from one existing entity to a new entity.
- E - Other (explain in comments section)

NOTE: Use COMMENTS section to explain why each Action Code was selected

355


Kacie S. Jones
Production Clerk
May 31, 2001

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry a different reservoir.
Use "APPLICATION FOR PERMIT -" for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well
☒ Oil Well ☐ Gas Well ☐ Other

RECEIVED

JAN 03 2003

2. Name of Operator
INLAND PRODUCTION COMPANY

DIV. OF OIL, GAS & MINING

3. Address and Telephone No.
Rt. 3 Box 3630, Myton Utah, 84052 435-646-3721

4. Location of Well (Footage, Sec., T., R., m., or Survey Description)
2059 FNL 0701 FEL SE/NE Section 34, T8S R16E

5. Lease Designation and Serial No.

U-16535

6. If Indian, Allottee or Tribe Name
NA

7. If Unit or CA, Agreement Designation
MONUMENT BUTTE UNIT

8. Well Name and No.
MONUMENT FED 8-34

9. API Well No.
43-013-30843

10. Field and Pool, or Exploratory Area
MONUMENT BUTTE

11. County or Parish, State
DUCHESNE COUNTY, UTA

12. CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☐ Notice of Intent
☒ Subsequent Report
☐ Final Abandonment Notice

TYPE OF ACTION

☐ Abandonment
☐ Recompletion
☐ Plugging Back
☐ Casing Repair
☐ Altering Casing
☒ Other **Re-completion**

☐ Change of Plans
☐ New Construction
☐ Non-Routine Fracturing
☐ Water Shut-Off
☐ Conversion to Injection
☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Re-completion procedures were initiated in the Green River formation on subject well on 12/13/2002. Existing production equipment was pulled from well. Perfs @ 5024'-5038' and 5040'-5043' were squeezed W/ 100 sks class G cmt W/ .75% FL-62 & .2% SMS (1.15 cf/sk yld & 15.8 ppg). Cement retainer & cmt was drilled out. Squeeze was pressure tested to 500 psi (held). CIBP @ 5610' was drilled out and well was cleaned out to PBTD @ 6245'. Four new Green River intervals were perforated and hydraulically fracture treated as follows: Stage #1: CP .5 sds @ 5911'-5919', CP1 sds @ 5947'-5962', CP2 sds @ 5996'-5999', CP3 sds @ 6011'-6015', 6024'-6028' & 6031'-6034', CP4 sds @ 6088'-6094' and BS @ 6219'-6236' (existing perfs originally @ 1 JSPF), 6246'-6252' & 6267'-6273' (All @ 4 JSPF) fraced down 2 7/8 N-80 tbg W/ 197,938# 20/40 mesh sand in 1482 bbls Viking I-25 fluid. Stage #2: A .5 sds @ 5444'-5450', A3 sds @ 5502'-5521', LODC sds @ 5596'-5603' & 5629'-5634' (All @ 4 JSPF) fraced down 2 7/8 N-80 tbg W/ 99,421# 20/40 mesh sand in 737 bbls Viking I-25 fluid (screened out W/ approx. 93,076# sand in formation). Stage #3: C sds @ 5190'-5193' & 5203'-5207', B1 sds @ 5258'-5261' & 5279'-5284' and B2 sds @ 5340'-5344' (All @ 4 JSPF) fraced down 2 7/8 N-80 tbg W/ 60,044# 20/40 mesh sand in 472 bbls Viking I-25 fluid. Stage #4: GB2 sds @ 4432'-4436' and GB6 sds @ 4570'-4577' (All @ 4 JSPF) fraced down 5 1/2" 15.5# casing W/ 26,820# 20/40 mesh sand in 263 bbls Viking I-25 fluid. All fracs were flowed back through chokes. Sand was cleaned from wellbore. Frac tbg & tools were pulled from well. New zones were swab and flow tested for sand cleanup. A revised BHA & production tbg string was ran in and anchored in well W/ tubing anchor @ 6124', pump seating nipple @ 6157' and end of tubing string @ 6225'. A repaired 1 1/2" bore rod pump was ran in well on sucker rods. Well returned to production via rod pump on 12/30/02.

14. I hereby certify that the foregoing is true and correct

Signed

Gary Dietz

Title

Completion Foreman

Date

1/2/2002

CC: UTAH DOGM

(This space for Federal or State office use)

Approved by

Title

Date

Conditions of approval, if any:



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155
<http://www.blm.gov>



IN REPLY REFER TO:
3106
(UT-924)

September 16, 2004

Memorandum

To: Vernal Field Office
From: Acting Chief, Branch of Fluid Minerals
Subject: Merger Approval

Attached is an approved copy of the name change recognized by the Utah State Office. We have updated our records to reflect the merger from Inland Production Company into Newfield Production Company on September 2, 2004.

Michael Coulthard
Acting Chief, Branch of
Fluid Minerals

Enclosure

1. State of Texas Certificate of Registration

cc: MMS, Reference Data Branch, James Sykes, PO Box 25165, Denver CO 80225
State of Utah, DOGM, Attn: Earlene Russell, PO Box 145801, SLC UT 84114
Teresa Thompson
Joe Incardine
Connie Seare



Office of the Secretary of State

The undersigned, as Secretary of State of Texas, does hereby certify that the attached is a true and correct copy of each document on file in this office as described below:

Newfield Production Company
Filing Number: 41530400

Articles of Amendment

September 02, 2004

In testimony whereof, I have hereunto signed my name officially and caused to be impressed hereon the Seal of State at my office in Austin, Texas on September 10, 2004.



A handwritten signature in black ink, appearing to read "G. Connor".

Secretary of State

ARTICLES OF AMENDMENT
TO THE
ARTICLES OF INCORPORATION
OF
INLAND PRODUCTION COMPANY

FILED
In the Office of the
Secretary of State of Texas

SEP 02 2004
Corporations Section

Pursuant to the provisions of Article 4.04 of the Texas Business Corporation Act (the "TBCA"), the undersigned corporation adopts the following articles of amendment to the articles of incorporation:

ARTICLE 1 – Name

The name of the corporation is Inland Production Company.

ARTICLE 2 – Amended Name

The following amendment to the Articles of Incorporation was approved by the Board of Directors and adopted by the shareholders of the corporation on August 27, 2004.

The amendment alters or changes Article One of the Articles of Incorporation to change the name of the corporation so that, as amended, Article One shall read in its entirety as follows:

"ARTICLE ONE – The name of the corporation is Newfield Production Company."

ARTICLE 3 – Effective Date of Filing

This document will become effective upon filing.

The holder of all of the shares outstanding and entitled to vote on said amendment has signed a consent in writing pursuant to Article 9.10 of the TBCA, adopting said amendment, and any written notice required has been given.

IN WITNESS WHEREOF, the undersigned corporation has executed these Articles of Amendment as of the 1st day of September, 2004.

INLAND RESOURCES INC.

By: Susan G. Riggs
Susan G. Riggs, Treasurer

UTSL-	15855	61052	73088	76561	
071572A	16535	62848	73089	76787	
065914	16539	63073B	73520A	76808	
	16544	63073D	74108	76813	
	17036	63073E	74805	76954	63073X
	17424	63073O	74806	76956	63098A
	18048	64917	74807	77233	68528A
UTU-	18399	64379	74808	77234	72086A
	19267	64380	74389	77235	72613A
02458	26026A	64381	74390	77337	73520X
03563	30096	64805	74391	77338	74477X
03563A	30103	64806	74392	77339	75023X
04493	31260	64917	74393	77357	76189X
05843	33992	65207	74398	77359	76331X
07978	34173	65210	74399	77365	76788X
09803	34346	65635	74400	77369	77098X
017439B	36442	65967	74404	77370	77107X
017985	36846	65969	74405	77546	77236X
017991	38411	65970	74406	77553	77376X
017992	38428	66184	74411	77554	78560X
018073	38429	66185	74805	78022	79485X
019222	38431	66191	74806	79013	79641X
020252	39713	67168	74826	79014	80207X
020252A	39714	67170	74827	79015	81307X
020254	40026	67208	74835	79016	
020255	40652	67549	74868	79017	
020309D	40894	67586	74869	79831	
022684A	41377	67845	74870	79832	
027345	44210	68105	74872	79833	
034217A	44426	68548	74970	79831	
035521	44430	68618	75036	79834	
035521A	45431	69060	75037	80450	
038797	47171	69061	75038	80915	
058149	49092	69744	75039	81000	
063597A	49430	70821	75075		
075174	49950	72103	75078		
096547	50376	72104	75089		
096550	50385	72105	75090		
	50376	72106	75234		
	50750	72107	75238		
10760	51081	72108	76239		
11385	52013	73086	76240		
13905	52018	73087	76241		
15392	58546	73807	76560		

OPERATOR CHANGE WORKSHEET

ROUTING

1. GLH

2. CDW

3. FILE

Change of Operator (Well Sold)

Designation of Agent/Operator

X Operator Name Change**Merger**

The operator of the well(s) listed below has changed, effective:

9/1/2004**FROM: (Old Operator):**

N5160-Inland Production Company

Route 3 Box 3630

Myton, UT 84052

Phone: 1-(435) 646-3721

TO: (New Operator):

N2695-Newfield Production Company

Route 3 Box 3630

Myton, UT 84052

Phone: 1-(435) 646-3721

CA No.**Unit:****MONUMENT BUTTE (GR D)****WELL(S)**

NAME	SEC TWN RNG			API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
FEDERAL 1-34	34	080S	160E	4301330808	10835	Federal	WI	A
MONUMENT FED 8-34	34	080S	160E	4301330843	10835	Federal	OW	P
MONUMENT FED 10-34	34	080S	160E	4301331371	10835	Federal	OW	P
MON FED 9-34	34	080S	160E	4301331407	10835	Federal	WI	A
FEDERAL 1-35	35	080S	160E	4301330561	10835	Federal	OW	P
FEDERAL 4-35	35	080S	160E	4301330605	10835	Federal	WI	A
FEDERAL 2-35	35	080S	160E	4301330606	10835	Federal	WI	A
FEDERAL 3-35	35	080S	160E	4301330608	10835	Federal	WI	A
FEDERAL 5-35	35	080S	160E	4301330686	10835	Federal	WI	A
FEDERAL 12-35	35	080S	160E	4301330744	10835	Federal	OW	P
MON FED 13-35	35	080S	160E	4301330745	10835	Federal	WI	A
FEDERAL 6-35	35	080S	160E	4301330751	10835	Federal	OW	P
FEDERAL 10-35	35	080S	160E	4301330801	10835	Federal	OW	P
FEDERAL 14-35	35	080S	160E	4301330812	10835	Federal	OW	P
MONUMENT FED 8-35	35	080S	160E	4301331263	10835	Federal	OW	P
MON FED 15-35	35	080S	160E	4301331264	10835	Federal	WI	A
STATE 1-36	36	080S	160E	4301330592	10835	State	WI	A
STATE 13-36	36	080S	160E	4301330623	10835	State	WI	A
STATE 5-36	36	080S	160E	4301330624	10835	State	WI	A
STATE 12-36	36	080S	160E	4301330746	10835	State	OW	P
STATE 1-2	02	090S	160E	4301330596	10835	State	WI	A
STATE 3-2	02	090S	160E	4301330627	10835	State	WI	A

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

1. (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 9/15/20042. (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 9/15/20043. The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 2/23/20054. Is the new operator registered in the State of Utah: YES Business Number: 755627-01435. If **NO**, the operator was contacted on:

6a. (R649-9-2)Waste Management Plan has been received on: IN PLACE
6b. Inspections of LA PA state/fee well sites complete on: waived

7. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM BIA

8. **Federal and Indian Units:**

The BLM or BIA has approved the successor of unit operator for wells listed on: n/a

9. **Federal and Indian Communization Agreements ("CA"):**

The BLM or BIA has approved the operator for all wells listed within a CA on: na/

10. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: 2/23/2005

DATA ENTRY:

1. Changes entered in the **Oil and Gas Database** on: 2/28/2005
2. Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 2/28/2005
3. Bond information entered in RBDMS on: 2/28/2005
4. Fee/State wells attached to bond in RBDMS on: 2/28/2005
5. Injection Projects to new operator in RBDMS on: 2/28/2005
6. Receipt of Acceptance of Drilling Procedures for APD/New on: waived

FEDERAL WELL(S) BOND VERIFICATION:

1. Federal well(s) covered by Bond Number: UT 0056

INDIAN WELL(S) BOND VERIFICATION:

1. Indian well(s) covered by Bond Number: 61BSBDH2912

FEE & STATE WELL(S) BOND VERIFICATION:

1. (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number 61BSBDH2919

2. The **FORMER** operator has requested a release of liability from their bond on: n/a*
The Division sent response by letter on: n/a

LEASE INTEREST OWNER NOTIFICATION:

3. (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: n/a

COMMENTS:

*Bond rider changed operator name from Inland Production Company to Newfield Production Company - received 2/23/05

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-16535
		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
1. TYPE OF WELL Oil Well		7. UNIT or CA AGREEMENT NAME: GMBU (GRRV)
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		8. WELL NAME and NUMBER: MONUMENT FED 8-34
3. ADDRESS OF OPERATOR: Rt 3 Box 3630, Myton, UT, 84052		9. API NUMBER: 43013308430000
PHONE NUMBER: 435 646-4825 Ext		9. FIELD and POOL or WILDCAT: MONUMENT BUTTE
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2059 FNL 0701 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENE Section: 34 Township: 08.0S Range: 16.0E Meridian: S		COUNTY: DUCHESNE
		STATE: UTAH

11.

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input checked="" type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input checked="" type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input type="text"/>
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 10/9/2013			
<input type="checkbox"/> SPUD REPORT Date of Spud:			
<input type="checkbox"/> DRILLING REPORT Report Date:			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

The subject well has been converted from a producing oil well to an injection well on 10/08/2013. On 10/08/2013 Chris Jensen with the State of Utah DOGM was contacted concerning the initial MIT on the above listed well. On 10/09/2013 the casing was pressured up to 1375 psig and charted for 30 minutes with no pressure loss. The well was not injecting during the test. The tubing pressure was 0 psig during the test. There was not a State representative available to witness the test.

**Accepted by the
Utah Division of
Oil, Gas and Mining**

Date: October 17, 2013

By: 

NAME (PLEASE PRINT) Lucy Chavez-Naupoto	PHONE NUMBER 435 646-4874	TITLE Water Services Technician
SIGNATURE N/A		DATE 10/10/2013

Mechanical Integrity Test Casing or Annulus Pressure Test

Newfield Production Company
Rt. 3 Box 3630
Myton, UT 84052
435-646-3721

Witness: _____ Date 10/9/2013 Time 9:00 am pm

Test Conducted by: Kim Giles

Others Present: Troy Lazenby

Conversion

Well: Monument Butte Federal 8-34-8-16 Field: Monument Butte

Well Location: SE/NE sec. 34, T8S, R16E API No: 43-013-30843
Ducheme County Utah


<u>Time</u>	<u>Casing Pressure</u>	
0 min	<u>1375</u>	psig
5	<u>1375</u>	psig
10	<u>1375</u>	psig
15	<u>1375</u>	psig
20	<u>1375</u>	psig
25	<u>1375</u>	psig
30 min	<u>1375</u>	psig
35	_____	psig
40	_____	psig
45	_____	psig
50	_____	psig
55	_____	psig
60 min	_____	psig

Tubing pressure: 0 psig


Result: Pass Fail

Signature of Witness: _____

Signature of Person Conducting Test: Kim Giles



Day 1

NEWFIELD		Final Daily Workover Report		Well Name:	MON 8-34-8-16
		LOE		AFE:	
Field:	GMBU CTB4	Rig Name:		Report Date:	10/4/2013
Location:	S34 T8S R16E	Supervisor:	David Cloward	Operation:	FLUSHED CSG W/60 BBLS @ 250 DEGREES
County:	DUCHESNE	Phone:	435- 823-0012	Work Performed:	10/1/2013
State:	UT	Email:	dcloward@newfield.com	Day:	1
Reason for Workover:	Conversion			Daily Cost:	\$14,645
				Cum DWR:	\$14,645

Failures

Failure Date	Failure 1	Failure 2	Failure 3	Failure 4	Failure 5
--------------	-----------	-----------	-----------	-----------	-----------

Summaries

24 Hr. Summary:	RD PU JARRED ON ROD STRING TELL PUMP CAME FREE LD POLISH ROD				
24 Hr. Plan Forward:	CONTINUE CONVERSION				
Incidents	None	Newfield Pers:	1	Contract Pers:	5
				Conditions:	

Activity Summary

P: RU RIG FLUSHED CSG 60 BBLS @250 DEGREES, RD PU JARRED ON ROD STRING TELL PUMP CAME FREE LD POLISH ROD, 2 RODS, PU POLISHED ROD FLUSHED TBG W/ 40 BBLS@ 250 DEGREES LD POLISH ROD PU THREE RODS SOFT SEATED PUMP SIWFN SHUT DOWN DUE TO RIG MAINTAINCE, RIG MAINTAINCE.

Activity Summary

P: CREW TRAVEL JSA SAFETY MEETING RIG MAINTAINCE LD 1-1/2' POLISH RODS, 2-7/8"X8' PONY RODS, 4-PER GUIDED RODS 106- 3/4" SLICK SUCKER RODS, 45-3/4" 4-PER GUIDED RODS, 6-1/2" C(API) WT BARS, 1-SUCKER PUMP ON TRAILER FLUSHING AND INSPECTION RODS COMING OUT OF HOLE SIWFN.

P:

Activity Summary

P: CREW TRAVEL JSA SAFETY MEETING RD PU, ND WH, NU BOPS, RD RIG FLOOR RELEASED TAC, TOOHH 134 JTS TBG BREAKING AND RE- DOPING EVERY CONNECTION W/ LIQUID O-RING GREEN DOPE WAITED ON RUNNERS FOR TBG LAY DOWN TRAILER LD 53 JTS TBG ON TRAILER TIH 134 JTS TBG, PUMPED 10 BBLS DOWN TBG , DROPPED SV CHASED W/ 25 BBLS PRESSURED UP TBG TO 500 PSI SIWFN

Activity Summary

P: CREW TRAVEL JSA SAFETY MEETING PT TBG UP TO 3K PSI HELD 100% FOR 30 MIN. GOOD TEST RIH W/ SL RETRIEVED SV POOH SL RU RIG FLOOR ND BOPS NU INJECTION WH, CIRCULATED 50 BBLS OF PKR FLUID DOWN CSG SET PKR LOADED CSG W/ PKR FLUID PT CSG TO 1400 PSI HELD 100% FOR 30 MIN. GOOD TEST RD RIG PRE-TRIP INSPECTION

Activity Summary

9:00 AM - 9:30 AM; 0.5 Hr(s); P: On 10/08/2013 Chris Jensen with the State of Utah DOGM was contacted concerning the initial MIT on the above listed well. On 10/09/2013 the casing was pressured up to 1375 psig and charted for 30 minutes with no pressure loss. The well was not injecting during the test. The tubing pressure was 0 psig during the test. There was not a State representative available to witness the test.

					0	0	
					0	0	
					0	0	
					0	0	
					0	0	

Spud Date: 2/28/1984
 Put on Production: 3//1984
 Put on Injection: 3/25/1994
 Convert to Producer: 4/18/01
 GL: 5617' KB: 5627'

Monument Butte Fed. 8-34-8-16

Initial Production: 35 BOPD,
 139 MCFD, 0 BWPD

Injection Wellbore
 Diagram

SURFACE CASING


CSG SIZE: 8-5/8" / J-55 / 24#
 LENGTH: 6 jts (279')
 DEPTH LANDED: 302'
 HOLE SIZE: 12-1/4"
 CEMENT DATA: 210 sxs Class "G" cmt.

PRODUCTION CASING

CSG SIZE: 5-1/2" / J-55 / 17#
 LENGTH: 161 jts (6388')
 DEPTH LANDED: 6369'
 HOLE SIZE: 7-7/8"
 CEMENT DATA: 150 sxs HiFill & 325 sxs Gypseal.
 CEMENT TOP AT: 3284' per CBL

TUBING

SIZE/GRADE/WT: 2-7/8" / J-55 / 6.5#
 NO. OF JOINTS: 134 jts (4337')
 SEATING NIPPLE: 2-7/8" (1.10')
 SN LANDED AT: 4351' KB
 ON/OFF TOOL AT: 4352.1'
 ARROW #1 PACKER CE AT: 4357.3'
 SWEDGE AT: 4360.9'
 TBG PUP 2-3/8 J-55 AT: 4361.4'
 X/N NIPPLE AT: 4365.5'
 TOTAL STRING LENGTH: EOT @ 4367.3'



FRAC JOB

4/05/84 5024'-5043' **Frac D1 sand as follows:** 89,500# 20/40 sand in 655 bbls frac fluid. Treated @ avg press of 2100 psi w/avg rate of 31 BPM. ISIP 2160 psi. Flushed to perfs.

10/09/90 5024'-5043' **Reperf D1 zone.**

10/13/90 **Acidize D1 w/ 100 gal 15% HCl + 60% N2.**

4/19/94 **Put on Injection.**

4/18/01 **Convert to producer.**

12/18/02 5024'-5043' **Squeezed perfs**

12/18/02 5911'-6273' **Frac BS and CP sands as follows:** 197,938# 20/40 sand in 1005 bbls Viking I-25 fluid. Treated @ avg. pressure of 3330 psi w/avg. rate of 15.2 BPM. ISIP - 2200 psi. Calc. flush: 1562 gals. Actual flush: 1437 gals.

12/20/02 5444'-5634' **Frac A and LODC sands as follows:** 93,076# 20/40 sand in 512 bbls Viking I-25 fluid. Treated @ avg. pressure of 3950 psi w/avg. rate of 15.0 ISIP - 3700 psi. Calc. flush: 1451 gals. Actual flush: 42 gals.

12/21/02 5190'-5344' **Frac B and C sands as follows:** 60,044# 20/40 sand in 305 bbls Viking I-25 fluid. Treated @ avg. pressure of 3830 psi w/avg. rate of 15.0 BPM. ISIP - 2750 psi. Calc. flush: 1365 gals. Actual flush: 1283 gals.

12/22/02 4432'-4577' **Frac GB sands as follows:** 26,820# 20/40 sand in 121 bbls Viking I-25 fluid. Treated @ avg. pressure of 2550 psi w/avg. rate of 24.5 BPM. ISIP - 3300 psi. Calc. flush: 4432 gals. Actual flush: 3570 gals.

5/18/04 **Stuck Pump.** Update rod detail.

6/24/04 **Stuck Pump.** Update rod detail.

6-19-08 **Parted rods.** Updated rod & tubing details.

1/8/09 **Parted rods.** Updated rod & tubing details.

10/08/13 **Convert to Injection Well**

10/09/13 **Conversion MIT Finalized** - update tbg detail

PERFORATION RECORD

Date	Depth Range	Tool Joint	Holes	Notes
3/31/84	6219'-6236'	1 JSPF	17 holes	
4/04/84	5040'-5043'	1 JSPF	04 holes	Squeeze 12/02
4/04/84	5024'-5038'	1 JSPF	14 holes	Squeeze 12/02
10/09/90	5040'-5043'	3 JSPF	12 holes	
10/09/90	5024'-5038'	3 JSPF	42 holes	
12/18/02	6267'-6273'	4 JSPF	24 holes	
12/18/02	6246'-6252'	4 JSPF	24 holes	
12/18/02	6219'-6236'	5 JSPF	85 holes	reperf
12/18/02	6088'-6094'	4 JSPF	24 holes	
12/18/02	6031'-6034'	4 JSPF	28 holes	
12/18/02	6024'-6028'	4 JSPF	28 holes	
12/18/02	6011'-6015'	4 JSPF	16 holes	
12/18/02	5996'-5999'	4 JSPF	12 holes	
12/18/02	5947'-5962'	4 JSPF	92 holes	
12/18/02	5911'-5919'	4 JSPF	92 holes	
12/18/02	5629'-5634'	4 JSPF	20 holes	
12/18/02	5596'-5603'	4 JSPF	28 holes	
12/18/02	5502'-5521'	4 JSPF	76 holes	
12/18/02	5444'-5450'	4 JSPF	24 holes	
12/18/02	5340'-5344'	4 JSPF	16 holes	
12/18/02	5279'-5284'	4 JSPF	32 holes	
12/18/02	5258'-5261'	4 JSPF	32 holes	
12/18/02	5203'-5207'	4 JSPF	16 holes	
12/18/02	5190'-5193'	4 JSPF	12 holes	
12/18/02	4570'-4577'	4 JSPF	28 holes	
12/18/02	4432'-4436'	4 JSPF	16 holes	

NEWFIELD

Monument Butte Fed. 8-34-8-16
 2059' FNL & 701' FEL
 SENE Section 34-T8S-R16E
 Duchesne Co, Utah
 API #43-013-30843; Lease #U-16535

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: U-16535
1. TYPE OF WELL Water Injection Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		7. UNIT or CA AGREEMENT NAME: GMBU (GRRV)
3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT, 84052		8. WELL NAME and NUMBER: MONUMENT FED 8-34
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2059 FNL 0701 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENE Section: 34 Township: 08.0S Range: 16.0E Meridian: S		9. API NUMBER: 43013308430000
PHONE NUMBER: 435 646-4825 Ext		9. FIELD and POOL or WILDCAT: MONUMENT BUTTE
COUNTY: DUCHESNE		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 10/23/2013	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR	
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE TUBING	
	<input checked="" type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> CONVERT WELL TYPE	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PLUG BACK	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. <div style="display: flex; justify-content: space-between;"> <div style="width: 60%;"> The above reference well was put on injection at 11:15 AM on 10/23/2013. </div> <div style="width: 35%; text-align: right;"> Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY October 29, 2013 </div> </div>		
NAME (PLEASE PRINT) Lucy Chavez-Naupoto	PHONE NUMBER 435 646-4874	TITLE Water Services Technician
SIGNATURE N/A	DATE 10/28/2013	

NEWFIELD



Newfield Exploration Company

1001 17th Street | Suite 2000

Denver, Colorado 80202

PH 303-893-0102 | FAX 303-893-0103

April 22, 2013

RECEIVED

APR 24 2013

DIV. OF OIL, GAS & MINING

Mr. Mark Reinbold
State of Utah
Division of Oil, Gas and Mining
1594 W North Temple
Salt Lake City, Utah 84114-5801

RE: Permit Application for Water Injection Well
Monument Butte Federal #8-34-8-16
Monument Butte Field, Lease #UTU-16535
Section 34-Township 8S-Range 16E
Duchesne County, Utah

Dear Mr. Reinbold:

Newfield Production Company herein requests approval to convert the Monument Butte Federal #8-34-8-16 from a producing oil well to a water injection well in the Monument Butte (Green River) Field.

I hope you find this application complete; however, if you have any questions or require additional information, please contact me at (303) 893-0102.

Sincerely,

Eric Sundberg
Environmental Manager

NEWFIELD PRODUCTION COMPANY
APPLICATION FOR APPROVAL OF CLASS II INJECTION WELL
MONUMENT BUTTE FEDERAL #8-34-8-16
MONUMENT BUTTE FIELD (GREEN RIVER) FIELD
LEASE #UTU-16535
APRIL 22, 2013


TABLE OF CONTENTS

LETTER OF INTENT	
COVER PAGE	
TABLE OF CONTENTS	
UIC FORM 1 – APPLICATION FOR INJECTION WELL	
WELLBORE DIAGRAM OF PROPOSED INJECTION	
WORK PROCEDURE FOR INJECTION CONVERSION	
COMPLETED RULE R615-5-1 QUESTIONNAIRE	
COMPLETED RULE R615-5-2 QUESTIONNAIRE	
ATTACHMENT A	ONE-HALF MILE RADIUS MAP
ATTACHMENT A-1	WELL LOCATION PLAT
ATTACHMENT B	LIST OF SURFACE OWNERS WITHIN ONE-HALF MILE RADIUS
ATTACHMENT C	CERTIFICATION FOR SURFACE OWNER NOTIFICATION
ATTACHMENT E	WELLBORE DIAGRAM – MONUMENT BUTTE FEDERAL #8-34-8-16
ATTACHMENT E-1	WELLBORE DIAGRAM – MONUMENT BUTTE #2-34-8-16
ATTACHMENT E-2	WELLBORE DIAGRAM – MONUMENT BUTTE #H-34-8-16
ATTACHMENT E-3	WELLBORE DIAGRAM – MONUMENT BUTTE #S-34-8-16
ATTACHMENT E-4	WELLBORE DIAGRAM – MONUMENT BUTTE #G-35-8-16
ATTACHMENT E-5	WELLBORE DIAGRAM – GREATER MONUMENT BUTTE #B-34-8-16
ATTACHMENT E-6	WELLBORE DIAGRAM – GREATER MONUMENT BUTTE #M-34-8-16
ATTACHMENT E-7	WELLBORE DIAGRAM – GREATER MONUMENT BUTTE #T-34-8-16
ATTACHMENT E-8	WELLBORE DIAGRAM – GREATER MONUMENT BUTTE #E-35-8-16
ATTACHMENT E-9	WELLBORE DIAGRAM – MONUMENT BUTTE FEDERAL #16-27-8-16
ATTACHMENT E-10	WELLBORE DIAGRAM – MONUMENT BUTTE FEDERAL #6-34-8-16
ATTACHMENT E-11	WELLBORE DIAGRAM – MONUMENT BUTTE FEDERAL #7-34-8-16
ATTACHMENT E-12	WELLBORE DIAGRAM – MONUMENT BUTTE FEDERAL #9-34-8-16
ATTACHMENT E-13	WELLBORE DIAGRAM – MONUMENT BUTTE FEDERAL #10-34-8-16
ATTACHMENT E-14	WELLBORE DIAGRAM – MONUMENT BUTTE FEDERAL #16-34-8-16
ATTACHMENT E-15	WELLBORE DIAGRAM – MONUMENT BUTTE FEDERAL #1-34-8-16
ATTACHMENT E-16	WELLBORE DIAGRAM – MONUMENT BUTTE FEDERAL #J-34-8-16
ATTACHMENT E-17	WELLBORE DIAGRAM – MONUMENT BUTTE FEDERAL #L-34-8-16
ATTACHMENT E-18	WELLBORE DIAGRAM – MONUMENT BUTTE FEDERAL #4A-35R-8-16
ATTACHMENT E-19	WELLBORE DIAGRAM – MONUMENT BUTTE FEDERAL #5-35-8-16
ATTACHMENT E-20	WELLBORE DIAGRAM – MONUMENT BUTTE FEDERAL #6-35-8-16
ATTACHMENT E-21	WELLBORE DIAGRAM – MONUMENT BUTTE FEDERAL #12-35-8-16
ATTACHMENT E-22	WELLBORE DIAGRAM – MONUMENT BUTTE FEDERAL #N-35-8-16
ATTACHMENT E-23	WELLBORE DIAGRAM – MONUMENT BUTTE FEDERAL #O-35-8-16
ATTACHMENT F	WATER ANALYSIS
ATTACHMENT G	FRACTURE GRADIENT CALCULATIONS
ATTACHMENT G-1	FRACTURE REPORTS DATED – 3/28/84 – 4/12/84
ATTACHMENT H	WORK PROCEDURE FOR PROPOSED PLUG AND ABANDON
ATTACHMENT H-1	WELLBORE DIAGRAM OF PROPOSED PLUGGED WELL

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

APPLICATION FOR INJECTION WELL - UIC FORM 1

OPERATOR Newfield Production Company
ADDRESS 1001 17th Street, Suite 2000
Denver, Colorado 80202

Well Name and number: <u>Monument Butte Federal #8-34-8-16</u>	
Field or Unit name: <u>Monument Butte (Green River)</u>	Lease No. <u>UTU-16535</u>
Well Location: QQ <u>SENE</u> section <u>34</u> township <u>8S</u> range <u>16E</u> county <u>Duchesne</u>	
Is this application for expansion of an existing project? Yes [X] No []	
Will the proposed well be used for:	
Enhanced Recovery?	Yes [X] No []
Disposal?	Yes [] No [X]
Storage?	Yes [] No [X]
Is this application for a new well to be drilled? Yes [] No [X]	
If this application is for an existing well,	
has a casing test been performed on the well? Yes [] No [X]	
Date of test: _____	
API number: <u>43-013-30843</u>	
Proposed injection interval: from <u>4322</u> to <u>6350</u>	
Proposed maximum injection: rate <u>500 bpd</u> pressure <u>2127</u> psig	
Proposed injection zone contains [x] oil, [] gas, and/or [] fresh water within 1/2 mile of the well.	
<div style="border: 1px solid black; padding: 5px; display: inline-block;">IMPORTANT: Additional information as required by R615-5-2 should accompany this form.</div>	
List of Attachments: <u>Attachments "A" through "H-1"</u>	
I certify that this report is true and complete to the best of my knowledge.	
Name: <u>Eric Sundberg</u>	Signature <u></u>
Title <u>Environmental Manager</u>	Date <u>4/22/13</u>
Phone No. <u>(303) 893-0102</u>	
(State use only)	
Application approved by _____	Title _____
Approval Date _____	
Comments:	

Spud Date: 2/28/1984
Put on Production: 3/1/1984
Put on Injection: 3/25/1994
Convert to Producer: 4/18/01
GL: 5617' KB: 5627'

Monument Butte Fed. #8-34-8-16

Initial Production: 35 BOPD,
139 MCFD, 0 BWPD

Proposed Injection Wellbore Diagram

SURFACE CASING


CSG SIZE: 8-5/8" / J-55 / 24#
LENGTH: 6 jts. (279')
DEPTH LANDED: 302'
HOLE SIZE: 12-1/4"
CEMENT DATA: 210 sxs Class "G" cmt.

PRODUCTION CASING

CSG SIZE: 5-1/2" / J-55 / 17#
LENGTH: 161 jts. (6388')
DEPTH LANDED: 6369'
HOLE SIZE: 7-7/8"
CEMENT DATA: 150 sxs HiFill & 325 sxs Gypseal.
CEMENT TOP AT: 3284' per CBL

TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55
NO. OF JOINTS: 180 jts (5835.60')
TUBING ANCHOR: 5849.60'
NO. OF JOINTS: 2 jts (64.84')
SEATING NIPPLE: 2-7/8" (1.10')
SN LANDED AT: 5917.24' KB
NO. OF JOINTS: 5 jts (162.10')
TOTAL STRING LENGTH: EOT @ 6119.43'



FRAC JOB

4/05/84	5024'-5043'	Frac D1 sand as follows: 89,500# 20/40 sand in 655 bbls frac fluid. Treated @ avg press of 2100 psi w/avg rate of 31 BPM. ISIP 2160 psi. Flushed to perfs.
10/09/90		Reperf D1 zone.
10/13/90		Acidize D1 w/ 100 gal 15% HCl + 60% N2.
4/19/94		Put on Injection.
4/18/01		Convert to producer.
12/18/02	5911'-6273'	Frac BS and CP sands as follows: 197,938# 20/40 sand in 1005 bbls Viking I-25 fluid. Treated @ avg. pressure of 3330 psi w/avg. rate of 15.2 BPM. ISIP - 2200 psi. Calc. flush: 1562 gals. Actual flush: 1437 gals.
12/20/02	5444'-5634'	Frac A and LODC sands as follows: 93,076# 20/40 sand in 512 bbls Viking I-25 fluid. Treated @ avg. pressure of 3950 psi w/avg. rate of 15.0 ISIP - 3700 psi. Calc. flush: 1451 gals. Actual flush: 42 gals.
12/21/02	5190'-5344'	Frac B and C sands as follows: 60,044# 20/40 sand in 305 bbls Viking I-25 fluid. Treated @ avg. pressure of 3830 psi w/ avg. rate of 15.0 BPM. ISIP - 2750 psi. Calc. flush: 1365 gals. Actual flush: 1283 gals.
12/22/02	4432'-4577'	Frac GB sands as follows: 26,820# 20/40 sand in 121 bbls Viking I-25 fluid. Treated @ avg. pressure of 2550 psi w/avg. rate of 24.5 BPM. ISIP - 3300 psi. Calc. flush: 4432 gals. Actual flush: 3570 gals.
		Stuck Pump. Update rod detail.
		Stuck Pump. Update rod detail.
		Parted rods. Updated rod & tubing details.
		Parted rods. Updated rod & tubing details.

PERFORATION RECORD

3/31/84	6219'-6236'	1 JSPF	17 holes
4/04/84	5040'-5043'	1 JSPF	04 holes
4/04/84	5024'-5038'	1 JSPF	14 holes
10/09/90	5040'-5043'	3 JSPF	12 holes
10/09/90	5024'-5038'	3 JSPF	42 holes
12/18/02	6267'-6273'	4 JSPF	24 holes
12/18/02	6246'-6252'	4 JSPF	24 holes
12/18/02	6219'-6236'	5 JSPF	85 holes reperf
12/18/02	6088'-6094'	4 JSPF	24 holes
12/18/02	6031'-6034'	4 JSPF	28 holes
12/18/02	6024'-6028'	4 JSPF	28 holes
12/18/02	6011'-6015'	4 JSPF	16 holes
12/18/02	5996'-5999'	4 JSPF	12 holes
12/18/02	5947'-5962'	4 JSPF	92 holes
12/18/02	5911'-5919'	4 JSPF	92 holes
12/18/02	5629'-5634'	4 JSPF	20 holes
12/18/02	5596'-5603'	4 JSPF	28 holes
12/18/02	5502'-5521'	4 JSPF	76 holes
12/18/02	5444'-5450'	4 JSPF	24 holes
12/18/02	5340'-5344'	4 JSPF	16 holes
12/18/02	5279'-5284'	4 JSPF	32 holes
12/18/02	5258'-5261'	4 JSPF	32 holes
12/18/02	5203'-5207'	4 JSPF	16 holes
12/18/02	5190'-5193'	4 JSPF	12 holes
12/18/02	4570'-4577'	4 JSPF	28 holes
12/18/02	4432'-4436'	4 JSPF	16 holes



Monument Butte Fed. #8-34-8-16
2059' FNL & 701' FEL
SENE Section 34-T8S-R16E
Duchesne Co, Utah
API #43-013-30843; Lease #U-16535

WORK PROCEDURE FOR INJECTION CONVERSION

1. Rig up hot oil truck to casing. Pump water. Unseat pump. Flush rods. Trip out of hole with rods and pump.
2. Trip out of hole with tubing, breaking and doping every connection. Trip in hole with packer and tubing. Rig up water truck to casing. Pump packer fluid. Set packer.
3. Test casing and packer.
4. Rig down and move out.

**REQUIREMENTS FOR INJECTION OF FLUIDS INTO RESERVOIRS
RULE R615-5-1**

- 1. Operations to increase ultimate recovery, such as cycling of gas, the maintenance of pressure, the introduction of gas, water or other substances into a reservoir for the purpose of secondary or other enhanced recovery or for storage and the injection of water into any formation for the purpose of water disposal shall be permitted only by order of the Board after notice and hearing.**
- 2. A request for agency action for authority for the injection of gas, liquified petroleum gas, air, water or any other medium into any formation for any reason, including but not necessarily limited to the establishment of or the expansion of waterflood projects, enhanced recovery projects, and pressure maintenance projects shall contain:**

- 2.1 The name and address of the operator of the project.**

Newfield Production Company
1001 17th Street, Suite 2000
Denver, Colorado 80202

- 2.2 A plat showing the area involved and identifying all wells, including all proposed injection wells, in the project area and within one-half mile of the project area.**

See Attachment A.

- 2.3 A full description of the particular operation for approval is requested.**

Approval is requested to convert the Monument Butte Federal #8-34-8-16 from a producing oil well to a water injection well in Monument Butte (Green River) Field.

- 2.4 A description of the pools from which the identified wells are producing or have produced.**

The proposed injection well will inject into the Green River Formation.

- 2.5 The names, description and depth of the pool or pools to be affected.**

The injection zone is in the Green River Formation. For the Monument Butte Federal #8-34-8-16 well, the proposed injection zone is from Garden Gulch to Basal Carbonate (4322' - 6350'). The confining strata directly above and below the injection zones are the Garden Gulch and the top of the Wasatch Formation or TD, whichever is shallower. The Garden Gulch Marker top is at 3994' and the TD is at 6400'.

- 2.6 A copy of a log of a representative well completed in the pool.**

The referenced log for the Monument Butte Federal #8-34-8-16 is on file with the Utah Division of Oil, Gas and Mining.

- 2.7 A statement as to the type of fluid to be used for injection, its source and the estimated amounts to be injected daily.**

The primary type and source of fluid to be used for injection will be culinary water commingled with produced water. The average estimated injection of fluids will be at a rate of 300 BPD, and the estimated maximum injection will be at a rate of 500 BPD.

- 2.8 A list of all operators and surface owners within one-half mile radius of the proposed project.**

See Attachment B.

- 2.9 An affidavit certifying that said operators or owners and surface owners within a one-half mile radius have been provided a copy of the petition for injection.**

See Attachment C.

- 2.10 Any additional information the Board may determine is necessary to adequately review the petition.**

Newfield Production Company will supply any additional information requested by the Utah Division of Oil, Gas and Mining.

- 4.0 Establish recovery projects may be expanded and additional wells placed on injection only upon authority from the Board after notice and hearing or by administrative approval.**

This proposed injection well is on a Federal lease (Lease #UTU-16535) in the Monument Butte Federal (Green River) Field, and this request is for administrative approval.

**REQUIREMENTS FOR CLASS II INJECTION WELLS INCLUDING WATER DISPOSAL,
STORAGE AND ENHANCED RECOVERY WELLS
SECTION V – RULE R615-5-2**

- 1. Injection well shall be completed, equipped, operated, and maintained in a manner that will prevent pollution and damage to any USDW, or other resources and will confine injected fluids to the interval approved.**
- 2. The application for an injection well shall include a properly completed Form DOGM-UIC-1 and the following:**
 - 2.1 A plat showing the location of the injection well, all abandoned or active wells within a one-half mile radius of the proposed wells, and the surface owner and the operator of any lands or producing leases, respectively, within a one-half mile radius of the proposed injection well.**

See Attachments A and B.
 - 2.2 Copies of electrical or radioactive logs, including gamma ray logs, for the proposed well run prior to the installation of casing and indicating resistivity, spontaneous potential, caliper and porosity.**

All logs are on file with the Utah Division of Oil, Gas and Mining.
 - 2.3 A copy of a cement bond or comparable log run for the proposed injection well after casing was set and cemented.**

A copy of the cement bond log is on file with the Utah Division of Oil, Gas and Mining.
 - 2.4 Copies of logs already on file with the Division should be referenced, but need not be refiled.**

All copies of logs are on file with the Utah Division of Oil, Gas and Mining.
 - 2.5 A description of the casing or proposed casing program of the injection well and of the proposed method for testing the casing before use of the well.**

The casing program is 8-5/8", 24# surface casing run to 302' KB, and 5-1/2", 15.5# casing run from surface to 6369' KB. A casing integrity test will be conducted at the time of conversion. See Attachment E.
 - 2.6 A statement as to the type of fluid to be used for injection, its source and estimated amounts to be injected daily.**

The primary type and source of fluid to be used for injection will be culinary water commingled with produced water. The estimated average rate of injection will be 300 BPD, and the estimated maximum rate of injection will be 500 BPD.
 - 2.7 Standard laboratory analysis of the fluid to be injected, the fluid in the formation into which the fluid is being injected, and the compatibility of the fluids.**

See Attachment F.

The proposed average and maximum injection pressures.

The proposed average injection pressure will be approximately 1100 psig and the maximum injection pressure will not exceed 2127 psig.

2.8 Evidence and data to support a finding that the proposed injection well will not initiate fractures through the overlying strata or a confining interval that could enable the injected fluid or formation fluid to enter the fresh water strata.

The minimum fracture gradient for the Monument Butte Federal #8-34-8-16, for existing perforations (4432' - 5273') calculates at 0.86 psig/ft. The maximum injection pressures will be limited so as not to exceed this gradient. A step rate test will be performed periodically to ensure we are below parting pressure. The proposed maximum injection pressure is 2127 psig. We may add additional perforations between 3994' and 6400'. See Attachments G and G-1.

2.9 Appropriate geological data on the injection interval and confining beds, including the geologic name, lithologic description, thickness, depth, and lateral extent.

In the Monument Butte Federal #8-34-8-16, the proposed injection zone (4322' - 6350') is in the Garden Gulch to the Basal Carbonate of the Green River Formation. The reservoir is a very fine-grained sandstone with minor imbedded shale streaks. The estimated porosity is 13%. The members are composed of porous and permeable lenticular calcareous sandstone and low porosity carbonates and calcareous shale. The porous and lenticular sandstone varies in thickness from 0-31' and is confined to the Monument Butte Federal Field. Outside the Monument Butte Federal Field, the sandstone is composed of tight, very fine, silty, calcareous sandstone, less than 3' thick. The stratum confining the injection zone is composed of tight, moderately calcareous, sandy lacustrine shale. All of the confining strata are impermeable, and will effectively seal off the oil, gas, and water of the injection zone from any strata directly above or below it.

2.10 A review of the mechanical condition of each well within a one-half mile radius of the proposed injection well to assure that no conduit exists that could enable fluids to migrate up or down the wellbore and enter the improper intervals.

See Attachments E through E-23.


Additionally, the injection system will be equipped with high and low pressure shut down devices that will automatically shut in injection waters if a system blockage or leakage occurs. One way check valves will also ensure proper flow management. Relief valves will also be utilized for high-pressure relief.

2.11 An affidavit certifying that a copy of the application has been provided to all operators or owners, and surface owners within a one-half mile radius of the proposed injection well.

See Attachment C.

2.12 Any other information that the Board or Division may determine is necessary to adequately review the application.

Newfield Production Company will supply any requested information to the Board or Division.



X = Section Corners Located

EXHIBIT B

#	Legal Description	Lessor & Expiration	Lessee & Operating Rights	Surface Owner
1	T9S-R16E Section 34: NE,N2SE, SESE Section 35: All	USA UTU-16535 HBP	Newfield Production Company Newfield RMI LLC Newfield Explor Gulf Coast Inc AGK Energy LLC Marian Brennan Raymond Brennan Chorney Oil Company Raymond Chorney Estate Codvington OG Inc COG Partnership Davis Brothers Davis Resources Beverly Fischgrund James Fischgrund Green River OG Partnership Green River Oil Inc Thomas Ingle Jackson King Oil & Gas of Texas Ltd Jack J Rawitscher Turnkey Pipeline Company War-Gal LLC	USA
2	T8S-R16E Section 34: SWSE	USA UTU - 76787 HBP	Newfield Production Company Newfield RMI LLC James Fischgrund	USA
3	T8S-R16E Section 34: SW	USA UTU -47171 HBP	Newfield Production Company Newfield RMI LLC Chorney Oil Company LOEX Properties 1984	USA


4	T8S-R16E Section 27: S2S2 Section 34: NW	USA UTU - 62848 HBP	Newfield Production Company Raymond Brennan Beverly Fischgrund James Fischgrund Jack H Edwards Inc Thomas Ingle Jackson King Oil & Gas of Texas Ltd	USA
5	T8S-R16E Section 23: SE Section 25: W2nw Section 26: SW, N2SE	USA UTU - 34346 HBP	Newfield Production Company Newfield RMI LLC Citation Oil & Gas Corp	USA

ATTACHMENT C

CERTIFICATION FOR SURFACE OWNER NOTIFICATION

RE: Application for Approval of Class II Injection Well
Monument Butte Federal #8-34-8-16


I hereby certify that a copy of the injection application has been provided to all surface owners within a one-half mile radius of the proposed injection well.

Signed: 
Newfield Production Company
Eric Sundberg
Environmental Manager

Sworn to and subscribed before me this 22nd day of April, 2013.

Notary Public in and for the State of Colorado: Candice L. Kowalski

My Commission Expires: My Commission Expires Feb. 25, 2017



Attachment E

Monument Butte Fed. #8-34-8-16

Spud Date: 2/28/1984
 Put on Production: 3/1/1984
 Put on Injection: 3/25/1994
 Convert to Producer: 4/18/01
 GL: 5617' KB: 5627'

Initial Production: 35 BOPD,
 139 MCFD, 0 BWPD

Wellbore Diagram

SURFACE CASING

CSG SIZE: 8-5/8" / J-55 / 24#
 LENGTH: 6 jts. (279")
 DEPTH LANDED: 302'
 HOLE SIZE: 12-1/4"
 CEMENT DATA: 210 sxs Class "G" cmt.

PRODUCTION CASING


CSG SIZE: 5-1/2" / J-55 / 17#
 LENGTH: 161 jts. (6388")
 DEPTH LANDED: 6369'
 HOLE SIZE: 7-7/8" *3.25*
 CEMENT DATA: 150 sxs HiFill & 325 sxs Gypseal.
 CEMENT TOP AT: 3284' per CBL/

TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55
 NO. OF JOINTS: 180 jts (5835.60')
 TUBING ANCHOR: 5849.60'
 NO. OF JOINTS: 2 jts (64.84')
 SEATING NIPPLE: 2-7/8" (1.10')
 SN LANDED AT: 5917.24' KB
 NO. OF JOINTS: 5 jts (162.10')
 TOTAL STRING LENGTH: EOT @ 6119.43'

SUCKER RODS

POLISHED ROD: 1-1/2" x 26' SM
 SUCKER RODS: 6-1 1/2" weight bars; 63-3/4" guided rods; 73-3/4" plain rods; 89-7/8" guided rods, 2-8", 1-4' x 7/8" Pony rods.
 PUMP SIZE: 2-1/2" x 1-1/2" x 10' x 16' RHAC
 STROKE LENGTH: 84"
 PUMP SPEED, SPM: 5 SPM

FRAC JOB

4/05/84 5024'-5043' **Frac D1 sand as follows:**
 89,500# 20/40 sand in 655 bbls frac fluid.
 Treated @ avg press of 2100 psi w/avg rate of 31 BPM. ISIP 2160 psi. Flushed to perfs.
 10/09/90 **Reperf D1 zone.**
 10/13/90 **Acidize D1 w/ 100 gal 15% HCl + 60% N2.**
 4/19/94 **Put on Injection.**
 4/18/01 **Convert to producer.**
 12/18/02 5911'-6273' **Frac BS and CP sands as follows:**
 197,938# 20/40 sand in 1005 bbls Viking I-25 fluid. Treated @ avg. pressure of 3330 psi w/avg. rate of 15.2 BPM. ISIP - 2200 psi. Calc. flush: 1562 gals. Actual flush: 1437 gals.
 12/20/02 5444'-5634' **Frac A and LODC sands as follows:**
 93,076# 20/40 sand in 512 bbls Viking I-25 fluid. Treated @ avg. pressure of 3950 psi w/avg. rate of 15.0 ISIP - 3700 psi. Calc. flush: 1451 gals. Actual flush: 42 gals.
 12/21/02 5190'-5344' **Frac B and C sands as follows:**
 60,044# 20/40 sand in 305 bbls Viking I-25 fluid. Treated @ avg. pressure of 3830 psi w/avg. rate of 15.0 BPM. ISIP - 2750 psi. Calc. flush: 1365 gals. Actual flush: 1283 gals.
 12/22/02 4432'-4577' **Frac GB sands as follows:**
 26,820# 20/40 sand in 121 bbls Viking I-25 fluid. Treated @ avg. pressure of 2550 psi w/avg. rate of 24.5 BPM. ISIP - 3300 psi. Calc. flush: 4432 gals. Actual flush: 3570 gals.

PERFORATION RECORD

Date	Depth Range	Perforation Type	Holes
3/31/84	6219'-6236'	1 JSPF	17 holes
4/04/84	5040'-5043'	1 JSPF	04 holes
4/04/84	5024'-5038'	1 JSPF	14 holes
10/09/90	5040'-5043'	3 JSPF	12 holes
10/09/90	5024'-5038'	3 JSPF	42 holes
12/18/02	6267'-6273'	4 JSPF	24 holes
12/18/02	6246'-6252'	4 JSPF	24 holes
12/18/02	6219'-6236'	5 JSPF	85 holes reperf
12/18/02	6088'-6094'	4 JSPF	24 holes
12/18/02	6031'-6034'	4 JSPF	28 holes
12/18/02	6024'-6028'	4 JSPF	28 holes
12/18/02	6011'-6015'	4 JSPF	16 holes
12/18/02	5996'-5999'	4 JSPF	12 holes
12/18/02	5947'-5962'	4 JSPF	92 holes
12/18/02	5911'-5919'	4 JSPF	92 holes
12/18/02	5629'-5634'	4 JSPF	20 holes
12/18/02	5596'-5603'	4 JSPF	28 holes
12/18/02	5502'-5521'	4 JSPF	76 holes
12/18/02	5444'-5450'	4 JSPF	24 holes
12/18/02	5340'-5344'	4 JSPF	16 holes
12/18/02	5279'-5284'	4 JSPF	32 holes
12/18/02	5258'-5261'	4 JSPF	32 holes
12/18/02	5203'-5207'	4 JSPF	16 holes
12/18/02	5190'-5193'	4 JSPF	12 holes
12/18/02	4570'-4577'	4 JSPF	28 holes
12/18/02	4432'-4436'	4 JSPF	16 holes



Monument Butte Fed. #8-34-8-16
 2059' FNL & 701' FEL
 SENE Section 34-T8S-R16E
 Duchesne Co, Utah
 API #43-013-30843; Lease #U-16535

Monument Butte 2-34-8-16

Spud Date: 3/19/97
Put on Production: 6/10/97
GL: 5591' KB: 5603'

Initial Production: 45 BOPD,
64 MCFPD, 8 BWPD

SURFACE CASING


CSG SIZE: 8-5/8"
GRADE: J-55
WEIGHT: 24#
LENGTH: 287.30' (7 jts.)
DEPTH LANDED: 287.30' GL
HOLE SIZE: 12-1/4"
CEMENT DATA: 120 sxs Premium cmt, w/8 bbls cmt to surface.

PRODUCTION CASING

CSG SIZE: 5-1/2"
GRADE: J-55
WEIGHT: 15.5#
LENGTH: 146 jts.
DEPTH LANDED: 6138'
HOLE SIZE: 7-7/8"
CEMENT DATA: 420 sk Hibond mixed & 370 sxs thixotropic
CEMENT TOP AT: 478' per CBL

TUBING

SIZE/GRADE/WT.: 2-7/8" / M-50 / 6.5#
NO. OF JOINTS: 143 jts (4439.9')
SEATING NIPPLE: 2-7/8" (1.10')
SN LANDED AT: 4451.9'
CE @ 4456.33'
TOTAL STRING LENGTH: EOT @ 4460' W/12' KB

Injection Wellbore
DiagramFRAC JOB

5/28/97	6009'-6020'	Frac CP-2 sand as follows: 103,400# of 20/40 sand in 526 bbls of Boragel. Perfs broke @ 2159 psi. Treated @ avg rate of 26 bpm w/avg press of 1900 psi. ISIP-2295, 5-min 2084 psi. Flowback on 12/64" ck for 3-1/2 hours and died.
5/29/97	5827'-5869'	Frac LODC sand as follows: 113,100# of 20/40 sand in 541 bbls of Boragel. Perfs broke @ 3212 psi. Treated @ avg rate of 28 bpm w/avg press of 2980 psi. Screened out w/8.9# sand on perfs w/1166 gal left to flush. Had 101,800# sand in perfs and 11,300# sand left in csg. ISIP-3836 psi, 5-min 2601 psi. Flowback on 12/64" ck for 4 hours and died.
6/2/97	5227'-5232'	Frac C sand as follows: 102,000# of 20/40 sand in 477 bbls Boragel. Perfs broke @ 2680 psi. Treated @ avg rate of 25 bpm w/avg press of 2680 psi. Screened out w/820 gal of flush left to pump, reduced rate and flushed remainder of flush. ISIP-3438 psi, 5-min 2311 psi. Flowback on 12/64" ck for 2-1/2 hours and died.
6/4/97	4991'-5062'	Frac D-1 & D-S3 sand as follows: 101,300# of 20/40 sand in 490 bbls of Boragel. Perfs broke @ 3180 psi. Treated @ avg rate of 26.5 bpm w/avg press of 2400 psi. ISIP-2900 psi, 5-min 2853 psi. Flowback on 12/64" ck for 2-1/2 hours and died.
6/11/01	4862'-4870'	Frac X-Stray sand as follows: 19,674# of 20/40 sand in 216 bbls of Viking 1-25. Treated w/avg press of 3480 psi. @ 28 BPM. Screened out.
6/13/01	4528'-4576'	Frac GB-4 sand as follows: 124,397# of 20/40 sand in 771 bbls of Viking 1-25. Treated w/avg press of 2340 psi. @ 31.5 BPM. ISIP - 2415 psi. Flow back 6 hours then died.
5/15/03		Stuck pump. Update tubing and rod detail.
6/28/03		Parted Rods. Update rod detail.
05/29/08		Major workover. Updated rod and tubing
5/15/09		Parted rods. Updated r & t details.
04/13/10		Convert to Injection well
04/14/10		MIT Completed - tbg detail updated

PERFORATION RECORD

5/27/97	6009'-6020'	4 JSPF	44 holes
5/29/97	5827'-5834'	4 JSPF	28 holes
5/29/97	5859'-5869'	4 JSPF	40 holes
5/31/97	5227'-5232'	4 JSPF	20 holes
6/3/97	4991'-4996'	4 JSPF	20 holes
6/3/97	5049'-5062'	4 JSPF	52 holes
6/11/01	4862'-4870'	4 JSPF	56 holes
6/13/01	4568'-4576'	4 JSPF	32 holes
6/13/01	4528'-4542'	4 JSPF	32 holes

NEWFIELD**Monument Butte 2-34-8-16**

660 FNL & 1982 FEL
NW/NE Section 34-T8S-R16E
Duchesne Co, Utah
API #43-013-31745; Lease #UTU-16535

Monument Butte H-34-8-16

Spud Date: 12/10/2010
Put on Production: 2/8/2011
GL: 5624' KB: 5636'

Wellbore Diagram

SURFACE CASING

CSG SIZE: 8-5/8"
GRADE: J-55
WEIGHT: 24#
LENGTH: 7 jts. (296.05')
DEPTH LANDED: 307.90'
HOLE SIZE: 12-1/4"
CEMENT DATA: 160 sxs Class "G" cmt

PRODUCTION CASING

CSG SIZE: 5-1/2"
GRADE: J-55
WEIGHT: 15.5#
LENGTH: 157 jts. (6622.07')
HOLE SIZE: 7-7/8"
DEPTH LANDED: 6635.32'
CEMENT DATA: 300 sxs Prem. Lite II mixed & 425 sxs 50/50 POZ.
CEMENT TOP AT: 60'

TUBING


SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
NO. OF JOINTS: 204 jts (6363.2')
TUBING ANCHOR: 6375.2'
NO. OF JOINTS: 1 jts (31.4')
SEATING NIPPLE: 2-7/8" (1.1')
SN LANDED AT: 6409.3' KB
NO. OF JOINTS: 2 jts (63.0')
TOTAL STRING LENGTH: EOT @ 6474'

SUCKER RODS

POLISHED ROD: 1-1/2" x 30'
SUCKER RODS: 250 - 7/8" = 6250' 8 per guided rods; 4 - 1 1/2" = 100' weight bars;
PUMP SIZE: 2 x 1 3/4 x 24" RHAC
STROKE LENGTH: 144
PUMP SPEED: ? SPM

FRAC JOB

1/15/11 6364'-6417' Frac CP4 & CP5 sands as follows:
Frac with 25,051# 20/40 sand in 213 bbls
Lightning 17 fluid.
1/26/11 6120' - 6125' Frac CP2 sands as follows:
Frac with 15,500# 20/40 sand in 131 bbls
Lightning 17 fluid.
1/26/11 5861' - 5937' Frac LODC sands as follows:
Frac with 43,395# 20/40 sand in 275 bbls
Lightning 17 fluid.
1/26/11 5676' - 5684' Frac A3 sands as follows:
Frac with 25,181# 20/40 sand in 214 bbls
Lightning 17 fluid.
1/26/11 5258' - 5330' Frac C & D3 sands as follows:
Frac with 25,647# 20/40 sand in 211 bbls
Lightning 17 fluid.
1/26/11 4633' - 4865' Frac GB6 & PB10 sands as follows:
Frac with 29,976# 20/40 sand in 255 bbls
Lightning 17 fluid.

PERFORATION RECORD

6413'-6417'	3 JSPF	12 holes
6364'-6367'	3 JSPF	9 holes
6120'-6125'	3 JSPF	15 holes
5933'-5397'	3 JSPF	12 holes
5925'-5927'	3 JSPF	6 holes
5870'-5874'	3 JSPF	12 holes
5861'-5863'	3 JSPF	6 holes
5676'-5684'	3 JSPF	24 holes
5325'-5330'	3 JSPF	15 holes
5258'-5261'	3 JSPF	9 holes
4861'-4865'	3 JSPF	12 holes
4640'-4641'	3 JSPF	3 holes
4633'-4637'	3 JSPF	12 holes

NEWFIELD

Monument Butte H-34-8-16
1981' FNL & 2021' FEL (SW/NE)
Section 34, T8S, R16E
Duchesne Co, Utah

API # 43-013-50225; Lease # UTU-16535

Monument Butte S-34-8-16

Spud Date: 12-14-10
Put on Production: 1-19-11
GL: 5633' KB: 5645'

Wellbore Diagram

FRAC JOB

SURFACE CASING

CSG SIZE: 8-5/8"
GRADE: J-55
WEIGHT: 24#
LENGTH: 7jts. (299.41')
DEPTH LANDED: 311.26'
HOLE SIZE: 12-1/4"
CEMENT DATA: 160 sxs Class "G", circ. 6 bbls to surf.

PRODUCTION CASING

CSG SIZE: 5-1/2"
GRADE: J-55
WEIGHT: 15.5#
LENGTH: 154 jts. (6489.79')
HOLE SIZE: 7-7/8"
DEPTH LANDED: 6504.40'
CEMENT DATA: 300 sxs Prem. Lite II mixed & 400 sxs 50/50 POZ.
CEMENT TOP AT: 290' per CBL

TUBING (GI 1/19/11)

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
NO. OF JOINTS: 196jts (6092.87')
TUBING ANCHOR: 6104.87'
NO. OF JOINTS: 1jts (29.12')
SEATING NIPPLE: 2-7/8" (1.1')
SN LANDED: 6136.79' KB
NO. OF JOINTS: 1jts (31.4')
GAS ANCHOR: 2-7/8" (5.2') @ 6169.33
NIPPLE: 2-7/8" (0.65')
TUBING: 3 jts (94.21')
BP: 2-7/8" (0.7')
TOTAL STRING LENGTH: EOT @ 6270.09'

SUCKER RODS (GI 1/19/11)

POLISHED ROD: 1-1/2" x 30'
SUCKER RODS: 2', 8" x 7/8" pony rods, 239 x 7/8" 8 per guided rods, 4 x 1-1/2" weight bars
PUMP SIZE: 2-1/2" x 1-3/4" x 20" x 24" RHAC
STROKE LENGTH: 146"
PUMP SPEED, SPM: 5.7
PUMPING UNIT: DARCO C-640-365-168

TOC @ 290'

EOT @ 6270'

PBT @ 6459'

TD @ 6505'

1-6-11 6581-6586' Frac CP5 & CP4 sands as follows: Frac with 59917# 20/40 sand in 363bbls Lightning 17 fluid.
1-12-11 5965-6048' Frac CP1, CP.5 & CP2 sands as follows: Frac with 60117# 20/40 sand in 371bbls Lightning 17 fluid.
1-12-11 5637-5640' Frac A3 sands as follows: Frac with 9215# 20/40 sand in 141bbls Lightning 17 fluid.
1-12-11 5208-5319' Frac B.5 & D3 sands as follows: Frac with 25681# 20/40 sand in 215bbls Lightning 17 fluid.
1-12-11 5087-5104' Frac D1 sands as follows: Frac with 69136# 20/40 sand in 425bbls Lightning 17 fluid.
1-12-11 4522-4532' Frac GB4 sands as follows: Frac with 15130# 20/40 sand in 170bbls Lightning 17 fluid.

PERFORATION RECORD

6346-6349'	3 JSPF	9holes
6309-6311'	3 JSPF	6holes
6292-6294'	3 JSPF	6holes
6206-6208'	3 JSPF	6holes
6152-6154'	3 JSPF	6holes
6146-6147'	3 JSPF	3holes
6045-6048'	3 JSPF	9holes
6022-6024'	3 JSPF	6holes
6003-6005'	3 JSPF	6holes
5965-5969'	3 JSPF	12holes
5637-5640'	3 JSPF	9holes
5317-5319'	3 JSPF	6holes
5208-5214'	3 JSPF	18holes
5098-5104'	3 JSPF	18holes
5087-5091'	3 JSPF	12holes
4528-4532'	3 JSPF	12holes
4522-4524'	3 JSPF	6holes

NEWFIELD**Monument Butte S-34-8-16**

SL: 1994' FSL & 1940' FEL (NW/SE)

Section 34, T8S, R16

Duchesne Co, Utah

API # 43-013-50240; Lease #UTU-16535

Monument Butte G-35-8-16

Spud Date: 6-16-10
 Put on Production: 8-5-10
 GL: 5566' KB: 5578'

Wellbore Diagram

SURFACE CASING

CSG SIZE: 8-5/8"
 GRADE: J-55
 WEIGHT: 24#
 LENGTH: 7jts (305.08')
 DEPTH LANDED: 315.08'
 HOLE SIZE: 12-1/4"
 CEMENT DATA: 160 sxs Class "G" cmt, circ 5 bbls to surf

PRODUCTION CASING

CSG SIZE: 5-1/2"
 GRADE: J-55
 WEIGHT: 15.5#
 LENGTH: 149jts (6501.18')
 HOLE SIZE: 7-7/8"
 DEPTH LANDED: 6501.18'
 CEMENT DATA: 300sxs Premilite II & 401sxs 50/50 POZ.
 CEMENT TOP AT: 54' per CBL 7/14/10

TUBING (KS 8/2/10)

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
 NO. OF JOINTS: 199jts (6263.9')
 TUBING ANCHOR: 6275.9'
 NO. OF JOINTS: 1jts (31.0')
 SEATING NIPPLE: 2-7/8" (1.1')
 SN LANDED AT: 6309.7'
 NO. OF JOINTS: 2jts (61.2')
 NOTCHED COLLAR: 2-7/8" (0.5')
 TOTAL STRING LENGTH: EOT @ 6372'

SUCKER RODS (KS 8/2/10)

POLISHED ROD: 1-1/2" x 30'
 SUCKER ROD: 2', 4', 8' x 7/8" Pony Rods, 147 x 7/8" 8per Guided Rods, 4 x 1-1/2" Weight Bars.
 PUMP SIZE: 2-1/2 x 1-3/4 x 17' x 24' RHAC
 STROKE LENGTH: 124"
 PUMP SPEED, SPM: 5.7
 PUMPING UNIT: DARCO C-456-305-144

FRAC JOB

8-2-10 6191-6331' Frac CP3 & CP5 sands as follows:
 Frac w/25124# 20/40 sand in 154 bbls
 Lightning 17.

8-2-10 5994-6044' Frac CP.5 & CP1 sands as follows:
 Frac w/35368# 20/40 sand in 169 bbls
 Lightning 17.

8-2-10 5794-5800' Frac LODC sands as follows: Frac
 w/74606# 20/40 sand in 337 bbls
 Lightning 17.

8-2-10 5546-5652' Frac A1 & A3 sands as follows: Frac
 w/18876# 20/40 sand in 115 bbls
 Lightning 17.


8-2-10 5274-5281' Frac C sands as follows: Frac
 w/18140# 20/40 sand in 112 bbls
 Lightning 17.

8-2-10 5097-5113' Frac D1 sands as follows: Frac
 w/59939# 20/40 sand in 1427 bbls
 Lightning 17.

8-2-10 4620-4630' Frac GB6 sands as follows: Frac
 w/35640# 20/40 sand in 169 bbls
 Lightning 17.

PERFORATION RECORD

6328-6331' 3 JSPF 9 holes
 6300-6303' 3 JSPF 9 holes
 6191-6195' 3 JSPF 12 holes
 6042-6044' 3 JSPF 6 holes
 5994-6001' 3 JSPF 21 holes
 5794-5800' 3 JSPF 18 holes
 5783-5788' 3 JSPF 15 holes
 5649-5652' 3 JSPF 9 holes
 5546-5550' 3 JSPF 12 holes
 5274-5281' 3 JSPF 21 holes
 5109-5113' 3 JSPF 12 holes
 5097-5104' 3 JSPF 21 holes
 4620-4630' 3 JSPF 30 holes

**NEWFIELD****Monument Butte G-35-8-16**

SL: 1792' FNL: 1900' FWL (SE/NW)

Section 35, T8S, R16

Duchesne Co, Utah

API # 43-013-34126; Lease UTU-16535

Greater Monument Butte B-34-8-16

Spud Date: 12/15/10
Put on Production: 2/17/11
GL: 5578' KB: 5590'

Wellbore Diagram

SURFACE CASING

CSG SIZE: 8-5/8"
GRADE: J-55
WEIGHT: 24#
LENGTH: 7 jts. (299.1')
DEPTH LANDED: 310.95'
HOLE SIZE: 12-1/4"
CEMENT DATA: 160 sxs Class "G" cmt

PRODUCTION CASING

CSG SIZE: 5-1/2"
GRADE: J-55
WEIGHT: 15.5#
LENGTH: 157 jts. (6667.66')
HOLE SIZE: 7-7/8"
DEPTH LANDED: 6682.27'
CEMENT DATA: 300 sxs Prem. Lite II mixed & 425 sxs 50/50 POZ.
CEMENT TOP AT: 360'

TUBING


SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
NO. OF JOINTS: 204 jts (6364')
TUBING ANCHOR: 6376'
NO. OF JOINTS: 2 jts (62.9')
SEATING NIPPLE: 2-7/8" (1.1')
SN LANDED AT: 6441.7' KB
NO. OF JOINTS: 2 jts (62.8')
TOTAL STRING LENGTH: EOT @ 6506'

SUCKER RODS

POLISHED ROD: 1-1/2" x 30'
SUCKER RODS: 1 - 7/8" = 2' pony rods; 1 - 7/8" = 4' pony rods; 251 - 7/8" = 6275' 8 per guided rods; 4 - 1 1/2" = 100' weight bars; 1 - 1" Stabilizer Bar
PUMP SIZE: 2 1/2 x 1 3/4 x 24' x 0' RHAC
STROKE LENGTH: 0
PUMP SPEED: 0 SPM

FRAC JOB

1/17/2011 6396'-6448' Frac CP5 sands as follows: Frac with 25,154# 20/40 sand in 215 bbls Lightning 17 fluid.
2/1/2011 5644' - 5651' Frac A1 sands as follows: Frac with 19,424# 20/40 sand in 170 bbls Lightning 17 fluid.
2/1/2011 5104' - 5180' Frac DS3 and DS1 sands as follows: Frac with 74,866# 20/40 sand in 464 bbls Lightning 17 fluid.
2/1/2011 4672' - 4683' Frac GB6 sands as follows: Frac with 29,022# 20/40 sand in 251 bbls Lightning 17 fluid.

PERFORATION RECORD

6445'-6448'	3 JSPF	9 holes
6396'-6402'	3 JSPF	18 holes
5644'-5651'	3 JSPF	21 holes
5175'-5180'	3 JSPF	15 holes
5121'-5123'	3 JSPF	6 holes
5111'-5116'	3 JSPF	15 holes
5104'-5106'	3 JSPF	6 holes
4672'-4683'	3 JSPF	33 holes

NEWFIELD

Greater Monument Butte B-34-8-16

770' FSL & 1998' FEL (SW/SE)

Section 27, T8S, R16E

Duchesne Co, Utah

API # 43-013-50219; Lease # UTU-62848

Greater Monument Butte M-34-8-16

Spud Date: 12-13-10
Put on Production: 2-2-11
GL: 5624' KB: 5636'

Wellbore Diagram

FRAC JOB

SURFACE CASING

CSG SIZE: 8-5/8"
GRADE: J-55
WEIGHT: 24#
LENGTH: 7jts. (295.7')
DEPTH LANDED: 307.55'
HOLE SIZE: 12-1/4"
CEMENT DATA: 160sxs Class "G" cmt

PRODUCTION CASING


CSG SIZE: 5-1/2"
GRADE: J-55
WEIGHT: 15.5#
LENGTH: 156jts. (6522.9')
HOLE SIZE: 7-7/8"
DEPTH LANDED: 6537.51'
CEMENT DATA: 300sxs Prem. Lite II mixed & 400sxs 50/50 POZ.
CEMENT TOP AT: 110'

TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
NO. OF JOINTS: 194jts (6042.9')
TUBING ANCHOR: 6054.9'
NO. OF JOINTS: 1jts (31.4')
SEATING NIPPLE: 2-7/8" (1.1')
SN LANDED: 6089.2' KB
NO. OF JOINTS: 2jts (62.8')
TOTAL STRING LENGTH: EOT @ 6154'

SUCKER RODS

POLISHED ROD: 1-1/2" x 30'
SUCKER RODS: 1-2 x 7/8" pony rods, 1-8 x 7/8" pony rods, 237-x 7/8" 8 per guided rods, 4- 1 1/2" weight bars
PUMP SIZE: 2 1/2 x 1 3/4" x 24" RHAC
STROKE LENGTH: 122
PUMP SPEED: SPM 5

PERFORATION RECORD

6075-6077'	3 JSPF	6holes
6069-6071'	3 JSPF	6holes
6031-6036'	3 JSPF	15holes
5990-5993'	3 JSPF	9holes
5622-5627'	3 JSPF	15holes
5603-5607'	3 JSPF	12holes
5593-5595'	3 JSPF	3holes
5584-5587'	3 JSPF	9holes
5318-5323'	3 JSPF	15holes
5115-5120'	3 JSPF	15holes
5100-5102'	3 JSPF	6holes
5090-5095'	3 JSPF	15holes
5032-5034'	3 JSPF	6holes
4806-4815'	3 JSPF	27holes
4615-4619'	3 JSPF	12holes
4605-4608'	3 JSPF	9holes
4589-4591'	3 JSPF	6holes
4543-4546'	3 JSPF	9holes

NEWFIELD
Greater Monument Butte M-34-8-16
SL: 1980' FNL & 2000' FEL (SW/NE)
Section 34, T8S, R16
Duchesne Co, Utah
API # 43-013-50226; Lease # UTU-16535

Greater Monument Butte T-34-8-16

Spud Date: 1/25/2011
Put on Production: 4/14/2011
GL: 5591' KB: 5603'

Wellbore Diagram

SURFACE CASING

CSG SIZE: 8-5/8"
GRADE: J-55
WEIGHT: 24#
LENGTH: 6 jts. (305.55')
DEPTH LANDED: 315.40'
HOLE SIZE: 12-1/4"
CEMENT DATA: 160 sxs Class "G", circ. 4 bbls to surf.

PRODUCTION CASING


CSG SIZE: 5-1/2"
GRADE: J-55
WEIGHT: 15.5#
LENGTH: 153 jts. (6495.51')
HOLE SIZE: 7-7/8"
DEPTH LANDED: 6510.12'
CEMENT DATA: 300 sxs Prem. Lite II mixed & 400 sxs 50/50 POZ.
CEMENT TOP AT: 136' per CBL 3/10/11

TUBING (GI 1/2/13)

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
NO. OF JOINTS: 200 jts (6214.9')
TUBING SWIVEL: 3" (2.4')
TUBING ANCHOR: 6229.3'
NO. OF JOINTS: 2 jts (62.0')
SEATING NIPPLE: 2-7/8" (1.1')
SN LANDED AT: 6304.1' KB
NO. OF JOINTS: 2 jts (62.0')
NOTCHED COLLAR: 2-7/8" (0.5')
TOTAL STRING LENGTH: EOT @ 6357.64'

SUCKER RODS (GI 1/2/13)

POLISHED ROD: 1-1/4" x 30'
SUCKER RODS: 2", 2", 2", 4", 6' x 7/8" Pony Rod, 245 x 7/8" Guided Rods(8per), 1" x 4' Stabilizer Rod, 4 x 1-1/2" Weight Bars
PUMP SIZE: 2-1/2" x 1-3/4" x 20" x 24" RHAC
STROKE LENGTH: 146"
PUMP SPEED, SPM: 5.5
PUMPING UNIT: DARCO C-640-365-168

FRAC JOB

3/10/2011 6172-6260' **Frac CP4 and CP5 sands as follows:**
Frac with 24562# 20/40 sand in 209 bbls Lightning 17 fluid.

3/16/2011 5936-6024' **Frac CP .5, CP1 and CP2 sands as follows:**
Frac with 69706# 20/40 sand in 427 bbls Lightning 17 fluid.

3/16/2011 5598-5608' **Frac A3 sands as follows:**
Frac with 24654# 20/40 sand in 208 bbls Lightning 17 fluid.

3/16/2011 5239-5246' **Frac C sands as follows:**
Frac with 29898# 20/40 sand in 248 bbls Lightning 17 fluid.

3/16/2011 5056-5083' **Frac D1 sands as follows:**
Frac with 59931# 20/40 sand in 368 bbls Lightning 17 fluid.

3/16/2011 4795-4800' **Frac PB10 sands as follows:**
Frac with 20078# 20/40 sand in 167 bbls Lightning 17 fluid.

3/16/2011 4435-4526' **Frac GB2 and GB4 sands as follows:**
Frac with 36398# 20/40 sand in 235 bbls Lightning 17 fluid.

PERFORATION RECORD

4435-4440'	3 JSFP	15 holes
4524-4526'	3 JSFP	6 holes
4532-4536'	3 JSFP	12 holes
4795-4800'	3 JSFP	15 holes
5056-5058'	3 JSFP	6 holes
5069-5071'	3 JSFP	6 holes
5075-5078'	3 JSFP	9 holes
5081-5083'	3 JSFP	6 holes
5239-5246'	3 JSFP	21 holes
5598-5601'	3 JSFP	9 holes
5605-5608'	3 JSFP	9 holes
5936-5939'	3 JSFP	9 holes
5977-5979'	3 JSFP	6 holes
5984-5987'	3 JSFP	9 holes
6020-6024'	3 JSFP	12 holes
6172-6175'	3 JSFP	9 holes
6254-6260'	3 JSFP	18 holes



Greater Monument Butte T-34-8-16
1804' FSL & 751' FWL (NW/SW)

Section 35, T8S, R16E
Duchesne Co, Utah

API # 43-013-50220; Lease #UTU-16535

Greater Monument Butte E-35-8-16

Spud Date: 11-2-10
Put on Production: 3-4-11
GL: 5365' KB: 5377'

Wellbore Diagram

FRAC JOB

SURFACE CASING

CSG SIZE: 8-5/8"
GRADE: J-55
WEIGHT: 24#
LENGTH: 8jts. (343.45')
DEPTH LANDED: 355.30'
HOLE SIZE: 12-1/4"
CEMENT DATA: 160sxs Class "G" cmt

PRODUCTION CASING

CSG SIZE: 5-1/2"
GRADE: J-55
WEIGHT: 15.5#
LENGTH: 153jts. (6484.48')
HOLE SIZE: 7-7/8"
DEPTH LANDED: 6499.09'
CEMENT DATA: 300sxs Prem. Lite II mixed & 400sxs 50/50 POZ.
CEMENT TOP AT: 300'

TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
NO. OF JOINTS: 202jts (6300.0')
TUBING ANCHOR: 6313.0'
NO. OF JOINTS: 1jts (31.4')
SEATING NIPPLE: 2-7/8" (1.1')
SN LANDED: 6347.2' KB
NO. OF JOINTS: 1jts (31.4')
GAS ANCHOR: (5.2) 6379.7
TUBING: 3jts (94.1)
TOTAL STRING LENGTH: EOT @ 6480'


SUCKER RODS

POLISHED ROD: 1-1/2" x 30'
SUCKER RODS: 1-2 x 7/8" pony rods, 1-4 x 7/8" pony rods, 1-6 x 7/8" pony rods, 1-8 x 7/8" pony rods, 101-x 7/8" 4 per guided rods, 145-x 3/4" 4 per guided rods, 6- 1 1/2" weight bars
PUMP SIZE: 2 1/2 x 1 1/2" x 20" x 24" RHAC
STROKE LENGTH: 122
PUMP SPEED: SPM 5

12-22-10 6581-6586' Frac Wasatch sands as follows: Frac with 20156# 20/40 sand in 317bbls Lightning 17 fluid.
12-29-10 6068-6134' Frac CP4 & CP3 sands as follows: Frac with 20237# 20/40 sand in 167bbls Lightning 17 fluid.
12-29-10 5522-5526' Frac A3 sands as follows: Frac with 15072# 20/40 sand in 124bbls Lightning 17 fluid.
12-29-10 5243-5248' Frac B.5 sands as follows: Frac with 14834# 20/40 sand in 124bbls Lightning 17 fluid.
12-29-10 5013-5054' Frac D1 & D2 sands as follows: Frac with 19912# 20/40 sand in 163bbls Lightning 17 fluid.
12-29-10 4709-4758' Frac PB8 & PB10 sands as follows: Frac with 33168# 20/40 sand in 219bbls Lightning 17 fluid.
12-29-10 4494-4497' Frac GB6 sands as follows: Frac with 13652# 20/40 sand in 184bbls Lightning 17 fluid.

PERFORATION RECORD

6581-6586' 3 JSPF 15holes
6130-6134' 3 JSPF 12holes
6068-6072' 3 JSPF 12holes
5522-5526' 3 JSPF 12 holes
5243-5248' 3 JSPF 15holes
5048-5054' 3 JSPF 18holes
5013-5015' 3 JSPF 6holes
4756-4758' 3 JSPF 6holes
4741-4750' 3 JSPF 27holes
4709-4711' 3 JSPF 6holes
4494-4497' 3 JSPF 9holes

**NEWFIELD****Greater Monument Butte E-35-8-16**

679 'FSL & 646 'FEL (SE/SE)

Section 27, T8S, R16E

Duchesne Co, Utah

API # 43-013-50214; Lease # EDA-14-20-H62-6386

Spud Date: 9/28/97
Put on Production: 11/1/97
GL: 5556' KB: 5569'

Monument Butte Federal 16-27-8-16

Initial Production: 74 BOPD,
120 MCFPD, 23 BWPD

SURFACE CASING

CSG SIZE: 8-5/8"
GRADE: J-55
WEIGHT: 24#
LENGTH: 301' (7 jts.)
DEPTH LANDED: 299'
HOLE SIZE: 12-1/4"
CEMENT DATA: 120 sxs Premium cmt, est 8 bbls to surf.


PRODUCTION CASING

CSG SIZE: 5-1/2"
GRADE: J-55
WEIGHT: 15.5#
LENGTH: 6098' (144 jts.)
DEPTH LANDED: 6096'
HOLE SIZE: 7-7/8"
CEMENT DATA: 400 sk Hibond mixed & 375 sxs Thixo w/ 10% CalSeal
CEMENT TOP AT: 174'

TUBING

SIZE/GRADE/WT.: 2-7/8" / M-50 / 6.5#
NO. OF JOINTS: 151jts (4702.5')
SEATING NIPPLE: 2-7/8" (1.10')
SN LANDED AT: 4714.5' KB
CE @ 4718.93'
TOTAL STRING LENGTH: EOT @ 4723' KB

Injection Wellbore Diagram



FRAC JOB

10/20/97 5992'-6015' **Frac CP sand as follows:**
72,300# 20/40 sd in 438 bbls Boragel.
Treated @ ave press of 1700 psi w/ave
rate of 22.2 bpm. ISIP: 2086 psi.

10/23/97 5863'-5874' **Frac LDC sand as follows:**
98,400# 20/40 sd in 520 bbls Boragel.
Treated @ ave press of 2470 psi w/ave
rate of 26.2 BPM. ISIP: 3116 psi.

10/25/97 5006'-5087' **Frac D/YDC sand as follows:**
113,300# 20/40 sd in 571 bbls Boragel.
Treated @ ave press of 2050 psi w/ave rate of
28.1 BPM. ISIP: 2650 psi.

10/28/97 4795'-4853' **Frac PB sand as follows:**
95,300# 20/40 sd in 487 bbls Boragel.
Treated @ ave press of 2500 psi w/ave
rate of 26 BPM. ISIP: 2832 psi.

2/08/02 **Tubing leak.** Update rod and tubing
details.

8/20/02 **Tubing leak.** Update rod and tubing
details.

04/29/05 **Stuck Pump.**

08/26/05 **Pump Change.** Update rod and tubing
detail.

2/24/09 **Tubing Leak.** Updated r & t details.

05/19/10 **Parted Rods.** Updated rod & tubing detail

08/17/11 **Convert to Injection well**

08/23/2011 **Conversion MIT Finalized** - update tbg
detail

PERFORATION RECORD

Date	Depth Range	Tool Joint	Holes
10/20/97	6013'-6015'	4 JSPF	8 holes
10/20/97	5997'-6007'	4 JSPF	40 holes
10/20/97	5992'-5994'	4 JSPF	8 holes
10/23/97	5863'-5874'	4 JSPF	44 holes
10/25/97	5085'-5087'	4 JSPF	8 holes
10/25/97	5076'-5079'	4 JSPF	12 holes
10/25/97	5068'-5072'	4 JSPF	16 holes
10/25/97	5061'-5063'	4 JSPF	8 holes
10/25/97	5006'-5014'	4 JSPF	32 holes
10/28/97	4848'-4853'	4 JSPF	20 holes
10/28/97	4795'-4800'	4 JSPF	20 holes

NEWFIELD

Monument Butte Federal 16-27-8-16
660' FSL & 660' FEL
SE/SE Section 27-T8S-R16E
Duchesne Co, Utah
API #43-013-31899; Lease #U-62848

Monument Butte Fed. 6-34-8-16

Spud Date: 2/28/1995
Put on Production: 4/09/1995

GL: 5632' KB: 5646'

SURFACE CASING


CSG SIZE: 8-5/8"
GRADE: J-55
WEIGHT: 24#
DEPTH LANDED: 310'
HOLE SIZE: 12-1/4"
CEMENT DATA: 165 sxs Class "G" cement.

PRODUCTION CASING

CSG SIZE: 5-1/2"
GRADE: J-55
WEIGHT: 15.5#
DEPTH LANDED: 6207.42'
HOLE SIZE: 7-7/8"
CEMENT DATA: 383 sxs HiLift & 307 sxs 10-0 RFC.
CEMENT TOP AT: 364'

TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
NO. OF JOINTS: 136 jts (4461.9')
SEATING NIPPLE: 2-7/8" (1.10')
SN LANDED AT: 4475.9' KB
CE @ 4482.28'
TOTAL STRING LENGTH: EOT @ 4484' w/ 14' KB

Injection Wellbore
DiagramFRAC JOB

4/06/95	5520'-5552'	Frac A3 sand as follows: 97,570# 20/40 sand in 692 bbls Viking I-35 fluid. Treated @ avg press of 2270 psi w/avg rate of 31.5 BPM. ISIP 2380 psi. Calc. flush: 5520 gal. Actual flush: 1260 gal.
6/07/95	5042'-5098'	Frac D sands as follows: 77,000# 16/30 sand in 673 bbls KCl frac fluid. Treated @ avg press of 2250 psi w/avg rate of 32 BPM. ISIP 2482 psi. Calc. flush: 5042 gal. Actual flush: 4998 gal.
7/10/01	4548'-4568'	Frac GB-6 sand as follows: 100,120# 20/40 sand in 647 bbls Viking I-25 fluid. Treated @ avg press of 2050 psi w/avg rate of 30 BPM. ISIP 2360 psi. Calc. flush: 4548 gal. Actual flush: 4452 gal.
6/10/03	5899'-5984'	Frac CP sand as follows: 79,030# 20/40 sand in 630 bbls Viking I-25 fluid. Treated @ avg press of 4000 psi w/avg rate of 16 BPM. ISIP 1885 psi. Calc. flush: 1502 gal. Actual flush: 1386 gal.
6/11/03	5705'-5822'	Frac LODC sand as follows: 117,747# 20/40 sand in 900 bbls Viking I-25 fluid. Treated @ avg press of 4400 psi w/avg rate of 17.3 BPM. ISIP 2390 psi. Calc. flush: 1491 gal. Actual flush: 1386 gal.
6/12/03	5520'-5590'	Frac Existing A and LoDC sand as follows: 100,632# 20/40 sand in 213 bbls of Viking I-25 pad, and 518 bbls Viking I-25 fluid. Treated @ 4100 avg press of psi w/avg rate of 17.3 BPM. ISIP 2400 psi. Calc. flush: 1430 gal. Actual flush: 1302 gal.
6/12/03	5181'-5252'	Frac B and C sand as follows: 38,341# 20/40 sand in 198 bbls Viking I-25 fluid. Treated @ avg press of 2750 psi w/avg rate of 17.6 BPM. ISIP 1700 psi. Calc. flush: 1323 gal. Actual flush: 1176 gal.
2/17/04		Tubing Leak. Update rod and tubing detail.
4/10/10		Convert to Injection well
4/14/10		MIT Completed -tbg detail updated

PERFORATION RECORD

4/06/95	5520'-5552'	4 JSPF	128 holes
6/06/95	5089'-5098'	4 JSPF	36 holes
6/06/95	5042'-5051'	4 JSPF	36 holes
7/10/01	4548'-4568'	4 JSPF	80 holes
6/10/03	5978'-5984'	4 JSPF	24 holes
6/10/03	5940'-5944'	4 JSPF	16 holes
6/10/03	5899'-5904'	4 JSPF	20 holes
6/11/03	5820'-5822'	4 JSPF	8 holes
6/11/03	5814'-5816'	4 JSPF	8 holes
6/11/03	5804'-5807'	4 JSPF	12 holes
6/11/03	5788'-5791'	4 JSPF	12 holes
6/11/03	5758'-5770'	4 JSPF	48 holes
6/11/03	5739'-5744'	4 JSPF	20 holes
6/11/03	5716'-5721'	4 JSPF	20 holes
6/11/03	5705'-5710'	4 JSPF	20 holes
6/11/03	5586'-5590'	4 JSPF	16 holes
6/11/03	5562'-5572'	4 JSPF	10 holes
6/11/03	5248'-5252'	4 JSPF	16 holes
6/11/03	5181'-5184'	4 JSPF	12 holes

NEWFIELD

Monument Butte Fed. #6-34-8-16
1980' FNL & 1980' FWL
SE/NW Section 34-T8S-R16E
Duchesne Co, Utah
API #43-013-31504; Lease #U-62848

Monument Butte Fed. #7-34-8-16

Spud Date: 11/7/1994
Put on Production: 12/10/94

GL: 5617' KB: 5632'

SURFACE CASING

CSG SIZE: 8-5/8"
GRADE: J-55
WEIGHT: 24#
LENGTH: 7 jts. (300')
DEPTH LANDED: 300'
HOLE SIZE: 12-1/4"
CEMENT DATA:


PRODUCTION CASING

CSG SIZE: 5-1/2"
GRADE: K-55
WEIGHT: 15.5#
LENGTH: (6369')
DEPTH LANDED: 6369'
HOLE SIZE: 7-7/8"
CEMENT DATA: 350 sk Prem. Lite II mixed & 550 sxs 50/50 POZ.
CEMENT TOP AT: 528' per CBL

TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
NO. OF JOINTS: 133 jts (4346.38')
SEATING NIPPLE: 2-7/8" (1.10')
SN LANDED AT: 4362.63' KB
PACKER: 4366.93'
TOTAL STRING LENGTH: EOT @ 4370'

Injection Wellbore Diagram



Initial Production: 65 BOPD,
41 MCFD, 8 BWPD

FRAC JOB

12/3/94	5540'-5554'	Frac A-3 sand as follows: 80,000# 20/40 sand in 724 bbls fluid. Treated @ avg press of 2000 psi w/avg rate of 5 BPM. ISIP 1870 psi.
12/6/94	5022'-5032'	Frac D-1 sand as follows: 80,000# 20/40 sand in 747 bbls fluid. Treated @ avg press of 1950 psi w/avg rate of 30 BPM. ISIP 2054 psi. 12/3/94
2/12/98	5914'-6002'	Frac CP sand as follows: 68,900# 20/40 sand in 334 bbls fluid. Treated @ avg press of 7700 psi w/avg rate of 26 BPM. Tubing ruptured.
2/16/98	4534'-4569'	Frac GB-6 sand as follows: 104,300# 20/40 sand in 488 bbls fluid. Treated @ avg press of 2180 psi w/avg rate of 26 BPM. ISIP 2643 psi.
11/19/01	4448'-4514'	Frac GB-4,2 sands as follows: 63,360# 20/40 sand in 589 bbls fluid. Treated @ avg press of 2210 psi w/avg rate of 20.1 BPM. ISIP 2155 psi. Flowed 4.5 hours then died.
12/10/02		Ready for MIT.
11/27/07		5 Year MIT completed and submitted.

PERFORATION RECORD

12/02/94	5540'-5554'	4 JSPF	56 holes
12/05/94	5022'-5032'	4 JSPF	40 holes
02/11/98	5914'-5920'	4 JSPF	24 holes
02/11/98	5952'-5955'	4 JSPF	12 holes
02/11/98	5992'-6002'	4 JSPF	40 holes
02/14/98	4534'-4538'	4 JSPF	16 holes
02/14/98	4545'-4560'	4 JSPF	60 holes
02/14/98	4565'-4569'	4 JSPF	16 holes
11/16/01	4448'-4456'	4 JSPF	32 holes
11/16/01	4470'-4476'	4 JSPF	24 holes
11/16/01	4508'-4514'	4 JSPF	24 holes
11/16/01	5460'-5468'	4 JSPF	32 holes

NEWFIELD

Monument Butte Fed. #7-34-8-16
1980' FNL & 1980' FEL
SWNE Section 34-T8S-R16E
Duchesne Co, Utah
API #43-013-31471; Lease #U-16535

Monument Butte Fed. #9-34-8-16

Spud Date: 12/02/93
 Put on Production: 1/08/94
 Put on Injection: 1/11/01
 GL: 5134' KB: 5124'

Initial Production: 174 BOPD,
 60 MCFD, 11 BWPD

Injection
Wellbore DiagramSURFACE CASING

CSG SIZE: 8-5/8" / J-55 / 24#
 LENGTH: 307'
 HOLE SIZE: 12-1/4"
 CEMENT DATA: 316 sxs Class "G" cmt.

PRODUCTION CASING

CSG SIZE: 5-1/2" / J-55 / 17#
 LENGTH: 6502.70'
 HOLE SIZE: 7-7/8"
 CEMENT DATA: 102 sxs Hilift & 407 sxs 50/50 POZ.
 CEMENT TOP AT: 3378' per CBL

TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
 NO. OF JOINTS: 134 jts (4350.27')
 SEATING NIPPLE: 2-7/8" (1.10')
 SN LANDED AT: 4360.27' KB
 TUBING PACKER: 4364.37'
 TOTAL STRING LENGTH: EOT @ 4368.58'

FRAC JOB

12/22/93	5854'-5912'	Frac zone as follows: 31,000# 20/40 sand + 80,000# 16/30 sand in 1206 bbls frac fluid. Treated @ avg press of 2500 psi w/avg rate of 40 BPM. ISIP 2190 psi. Calc. flush: 5854 gal, Actual flush: 5670 gal.
12/29/93	5334'-5360'	Frac zone as follows: 43,000# 20/40 sand + 58,000# 16/30 sand in 1266 bbls frac fluid. Treated @ avg press of 2800 psi w/avg rate of 30 BPM. ISIP 2850 psi. Calc. flush: 5334 gal, Actual flush: 5175 gal.
1/04/94	4992'-5008'	Frac zone as follows: 65,000# 16/30 sand in 860 bbls frac fluid. Treated @ avg press of 2400 psi w/avg rate of 31BPM. ISIP 2345 psi. Calc. flush: 4992 gal, Actual flush: 4875 gal.
8/8/03		Recompletion. Ready for MIT.
7/9/08		5 Year MIT completed and submitted.

SN @ 4360'

Packer @ 4364'

EOT @ 4369'

4454'-4464' GB-4 sds

4992'-4997' D sds

5000'-5008' D sds

5287'-5294' B-1 sds

5334'-5350' B sds

5355'-5360' B sds

5648'-5658' LODC sds

5854'-5868' CP sds

5902'-5912' CP sds

PBTD @ 6379'

SHOE/TD @ 6503'

PERFORATION RECORD

12/21/93	5902'-5912'	4 JSPF	40 holes
12/21/93	5854'-5868'	4 JSPF	64 holes
12/28/93	5355'-5360'	4 JSPF	20 holes
12/28/93	5334'-5350'	4 JSPF	24 holes
1/04/94	5000'-5008'	4 JSPF	32 holes
1/04/94	4992'-4997'	4 JSPF	20 holes
8/6/03	5648'-5658'	4 JSPF	40 holes
8/6/03	5287'-5294'	4 JSPF	28 holes
8/6/03	4454'-4464'	4 JSPF	40 holes



Monument Federal. #9-34-8-16
 1980' FSL & 660' FEL
 NESE Section 34-T8S-R16E
 Duchesne Co, Utah
 API #43-013-31407; Lease #U-16535

Monument Butte Federal 10-34-8-16

Spud Date: 10/1/1992
 Put on Production: 11/26/1992
 GL: 5628' KB: 5640'

SURFACE CASING


CSG SIZE: 8-5/8"
 GRADE: J-55
 WEIGHT: 24#
 DEPTH LANDED: 304.87'
 HOLE SIZE: 12-1/4"
 CEMENT DATA: 216 sxs Class "G" cmt.

PRODUCTION CASING

CSG SIZE: 5-1/2"
 GRADE: J-55
 WEIGHT: 15.5#
 DEPTH LANDED: 6400.06'
 HOLE SIZE: 7-7/8"
 CEMENT DATA: 348 sxs Hilift & 428 sxs 50/50 POZ.
 CEMENT TOP AT: 1364' per CBL

TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
 NO. OF JOINTS: 138 jts (4379.2')
 SEATING NIPPLE: 2-7/8" (1.10')
 SN LANDED AT: 4391.2' KB
 CE @ 4395.55'
 TOTAL STRING LENGTH: EOT @ 4399'

Injection Wellbore Diagram

Initial Production:

68 BOPD, 93 MCFD, 24 BWPD

FRAC JOB

11/15/92 5917'-5964' **Frac CP sand as follows:**
 109,000# 16/30 sand in 1095 bbls fluid.
 Treated @ avg press of 2100 psi w/avg rate of 35 BPM. ISIP 2097 psi. Calc. flush: 5917 gal, Act. flush: 5663 gal.

11/17/92 5798'-5816' **Frac CP sand as follows:**
 75,000# 16/30 sand in 670 bbls fluid.
 Treated @ avg press of 3000 psi w/avg rate of 30 BPM. ISIP 3100 psi. Calc. flush: 5798 gal, Act. flush: 5614 gal.

11/19/92 5506'-5517' **Frac A-3 sand as follows:**
 60,430# 16/30 sand in 583 bbls fluid.
 Treated @ avg press of 3100 psi w/avg rate of 25 BPM. ISIP 2934 psi. Calc. flush: 5506 gal, Act. flush: 5370 gal.

11/22/92 4996'-5008' **Frac D-1 sand as follows:**
 28,500# 16/30 sand in 256 bbls fluid.
 Treated @ avg press of 2400 psi w/avg rate of 25 BPM. ISIP 2014 psi. Calc. flush: 4996 gal, Act. flush: 4850 gal.

9/22/01 **Rod job.** Update rod and tubing details.

02/06/02 4462'-4490' **Frac GB-4 sand as follows:**
 36,260# 16/30 sand in 325 bbls Viking I-25 frac fluid. Treated @ avg press of 2195 psi w/avg rate of 21.2 BPM. ISIP 2500 psi. Calc. flush: 4462 gal, Act. flush: 4242 gal.

08/10/06 **Pump Change.** Update rod and tubing details.

04-01-10 **Convert well to Injection**

04-07-10 **MIT compiled - tbg detail updated**

PERFORATION RECORD

Date	Interval	Tool	Holes
11/12/92	5951'-5964'	4 JSPF	52 holes
11/12/92	5917'-5927'	4 JSPF	40 holes
11/12/92	5878'-5882'	4 JSPF	16 holes
11/12/92	5864'-5867'	4 JSPF	12 holes
11/16/92	5798'-5816'	4 JSPF	72 holes
11/18/92	5506'-5517'	4 JSPF	44 holes
11/20/92	5002'-5008'	4 JSPF	24 holes
11/20/92	4996'-5000'	4 JSPF	16 holes
02/06/02	4462'-4464'	4 JSPF	08 holes
02/06/02	4481'-4490'	4 JSPF	36 holes

NEWFIELD

Monument Butte Federal 10-34-8-16
 1980' FSL & 1980' FEL
 NW/SE Section 34-T8S-R16E
 Duchesne Co, Utah
 API #43-013-31371; Lease #UTU-16535

Monument Butte Federal 16-34-8-16

Spud Date: 10/1/97
 Put on Production: 11/15/97
 GL: 5605.7' KB: 5617.7'

Initial Production: 65 BOPD,
 85 MCFPD, 46 BWPD

SURFACE CASING


CSG SIZE: 8-5/8"
 GRADE: J-55
 WEIGHT: 24#
 LENGTH: 7 jts. (299')
 DEPTH LANDED: 298'
 HOLE SIZE: 12-1/4"
 CEMENT DATA: 120 sxs Premium cement, est 5 bbls to surface

PRODUCTION CASING

CSG SIZE: 5-1/2"
 GRADE: J-55
 WEIGHT: 15.5#
 LENGTH: 140 jts. (6006')
 DEPTH LANDED: 5999'
 HOLE SIZE: 7-7/8"
 CEMENT DATA: 420 sk Hibond mixed & 390 sxs Thixotropic
 CEMENT TOP AT: 1100'

TUBING

SIZE/GRADE/WT.: 2-7/8" / M-50 / 6.5#
 NO. OF JOINTS: 157 jts. (4900.9')
 SEATING NIPPLE: 2-7/8"
 SN LANDED AT: 4912.9'
 CE @ 4917.29'
 TOTAL STRING LENGTH: 4921'

**Injection Wellbore
Diagram****FRAC JOB**

11/5/97 5488'-5527' **Frac A sand as follows:**
 97,300# 20/40 sand in 509 bbls Boragel.
 Breakdown @ 3396 psi. Treated @ avg
 press of 1800 psi w/avg rate of 26.3 BPM.
 ISIP-2336 psi, 5 min 2104 psi. Flowback
 on 12/64" ck for 3-1/2 hrs & died.

11/7/97 5294'-5300' **Frac B sand as follows:**
 88,400# 20/40 sand in 482 bbls Boragel.
 Breakdown @ 3450 psi. Treated @ avg
 press of 2550 psi w/avg rate of 24 BPM.
 ISIP-2383, 5 min 2315. Flowback on
 12/64" ck for 3-1/2 hrs & died.

11/9/97 5130'-5155' **Frac C sand as follows:**
 97,300# 20/40 sand in 498 bbls Boragel.
 Breakdown @ 2719 psi. Treated @ avg
 press of 2200 psi w/avg rate of 24.3 BPM.
 ISIP-2586 psi, 5 min 2536 psi. Flowback
 on 12/64" ck for 3-1/2 hrs & died.

11/12/97 4962'-4979' **Frac D sand as follows:**
 88,300# 20/40 sand in 474 bbls Boragel.
 Breakdown @ 2844 psi. Treated @ avg
 press of 2000 psi w/avg rate of 24 BPM.
 ISIP-2534 psi, 5 min 2460 psi. Flowback
 on 12/64" ck for 4 hrs & died.

8/23/01 **Rod job.** Updated rod and tubing details.

02/27/06 **Pump Change.** Update rod and tubing
 details.

5/19/09 **Tubing Leak.** Updated r & t details.

04/07/10 **Convert to Injection well**

04/14/10 **MIT Completed - tbg detail updated**

PERFORATION RECORD

11/5/97	5488'- 5496'	4 JSPF	32 holes
11/5/97	5504'- 5512'	4 JSPF	32 holes
11/5/97	5519'- 5527'	4 JSPF	32 holes
11/6/97	5294'- 5300'	4 JSPF	24 holes
11/8/97	5130'-5137'	4 JSPF	28 holes
11/8/97	5150'- 5155	4 JSPF	20 holes
11/11/97	4962'- 4979'	4 JSPF	68 holes

NEWFIELD

Federal 16-34-8-16
 660 FSL & 660 FEL
 SE/SE Section 34-T8S-R16E
 Duchesne Co, Utah
 API #43-013-31913; Lease #UTU-16535

Monument Butte #1-34-8-16

Spud Date: 9/14/1983
 Put on Production: 11/2/1983
 Put on Injection: 4/10/97
 GL: 5585' KB: 5595'

Initial Production: 58 BOPD, NM MCFD,
 0 BOPD

SURFACE CASING

CSG SIZE: 8-5/8"
 GRADE: J-55
 WEIGHT: 24#
 LENGTH: 6 jts.
 DEPTH LANDED: 240' GL
 HOLE SIZE: 12-1/4"
 CEMENT DATA: 1210 sxs Class "G" cmt.


PRODUCTION CASING

CSG SIZE: 5-1/2"
 GRADE: J-55
 WEIGHT: 15.5#
 LENGTH: 144 jts.
 DEPTH LANDED: 5788'
 HOLE SIZE: 7-7/8"
 CEMENT DATA: 175 sxs Lodense & 375 sxs Thixotropic.
 CEMENT TOP AT: 2224' per CBL

TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
 NO. OF JOINTS: 140 jts (4498.79')
 SEATING NIPPLE: 2-7/8" (1.10')
 SN LANDED AT: 4499.89' KB
 TUBING PACKER: 4503.14'
 TOTAL STRING LENGTH: EOT @ 4506.09'

Injector
 Wellbore Diagram

FRAC JOB

10/18/83	5041'-5053'	Frac D-1 sand as follows: 82,000# 20/40 sand in 607 bbls gelled KCl fluid. Treated @ avg press of 2400 psi w/avg rate of 26 BPM. ISIP 3330 psi. Screened out w/ 49,800# sand in formation.
7/31/84	5366'-5380'	Frac B-2 sand as follows: 31,500# 20/40 sand in 369 bbls gelled KCl fluid. Treated @ avg press of 4820 psi w/avg rate of 20.8 BPM. ISIP 2130 psi.
2/2/85	5574'-5613'	Frac LODC sand as follows: 89,480# 20/40 sand in 686 bbls gelled KCl fluid. Treated @ avg press of 4350 psi w/avg rate of 20 BPM. ISIP 2170 psi.
4/20/95	4568'-4586'	Frac GB-6 sand as follows: 60,100# 20/40 sand in 384 bbls gelled KCl fluid. Treated @ avg press of 2700 psi w/avg rate of 35 BPM. ISIP 2400 psi.
12/5/96	5252'-5257'	Acidize Bi-Carb as follows: 1000 gal 14% HCl.
4/10/97		Convert to injector.
1/7/02	4567'-5674'	Break each zone w/ 15% HCl.
1/11/02		Put back on injection
12/22/06		5 Year MIT completed and submitted.

PERFORATION RECORD

10/15/83	5041'-5053'	1 SPF	12 holes
07/28/84	5366'-5380'	1 SPF	14 holes
01/30/85	5574'-5596'	1 SPF	05 holes
01/30/85	5600'-5613'	1 SPF	05 holes
04/20/95	4568'-4686'	4 SPF	72 holes
12/05/95	5252'-5257'	4 SPF	20 holes
01/07/02	5640'-5674'	4 SPF	136 holes
01/07/02	5622'-5630'	4 SPF	42 holes
01/07/02	5594'-5614'	4 SPF	80 holes
01/07/02	5568'-5580'	4 SPF	48 holes
01/07/02	5342'-5346'	4 SPF	16 holes
01/07/02	5040'-5053'	4 SPF	52 holes
01/07/02	4567'-4586'	4 SPF	76 holes

NEWFIELD

Monument Butte # 1-34-8-16

739' FNL & 758' FEL

NENE Section 34-T8S-R16E

Duchesne Co, Utah

API #43-013-30808; Lease #U-16535

Monument Butte Federal J-34-8-16

Spud Date: 10/19/09
 Put on Production: 2/20/10
 Well flowing as of 12/17/09
 GL: 5567' KB: 5579'

Wellbore Diagram

SURFACE CASING

CSG SIZE: 8-5/8"
 GRADE: J-55
 WEIGHT: 24#
 LENGTH: 7 jts. (309.3')
 DEPTH LANDED: 319.30'
 HOLE SIZE: 12-1/4"
 CEMENT DATA: 160 sxs Class "G" cmt, circ. 4 bbls to surf.

PRODUCTION CASING

CSG SIZE: 5-1/2"
 GRADE: J-55
 WEIGHT: 15.5#
 LENGTH: 154 jts. (6461.87')
 HOLE SIZE: 7-7/8"
 DEPTH LANDED: 6455.87'
 CEMENT DATA: 280 sxs Premilite II & 425 sxs 50/50 POZ.
 CEMENT TOP AT: 32' per CBL 12/3/09

TUBING (KS 2/20/10)


SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
 NO. OF JOINTS: 184 jts (5987.2')
 TUBING ANCHOR: 5999.2'
 NO. OF JOINTS: 1 jts (32.5')
 SEATING NIPPLE: 2-7/8" (1.10')
 SN LANDED AT: 6034.6'
 NO. OF JOINTS: 2 jts (65.1')
 NOTCHED COLLAR: 2-7/8" (0.5')
 TOTAL STRING LENGTH: 6101'

SUCKER RODS (GI 4/11/13)

POLISHED ROD: 1-1/2" x 30' Polished Rod
 SUCKER RODS: 236 x 7/8" 8per Guided Rods, 4 x 1-1/2"
 Sinker Bars
 PUMP SIZE: 2-1/2" x 1-3/4" x 20' x 24' RHAC
 STROKE LENGTH: 169"
 PUMP SPEED, SPM: 5.7
 PUMPING UNIT: DARCO C-640-365-168a

FRAC JOB

12/18/09 6028-6034' **Frac CP1 sands as follows:**
 Frac with 10075# 20/40 sand in 91 bbls
 Lightning 17 fluid.
 12/18/09 5670-5783' **Frac LODC sands as follows:**
 Frac with 290139# 20/40 sand in 1837
 bbls Lightning 17 fluid.
 12/18/09 5440-5537' **Frac A.5 & B2 sands as follows:**
 Frac with 19502# 20/40 sand in 170 bbls
 Lightning 17 fluid.
 12/18/09 5104-5315' **Frac B1, C & D1 sands as follows:**
 Frac with 50758# 20/40 sand in 319 bbls
 Lightning 17 fluid.
 12/18/09 4614-4632' **Frac GB6 sands as follows:**
 Frac with 77612# 20/40 sand in 459 bbls
 Lightning 17 fluid.

PERFORATION RECORD

6028-6037'	3 JSPP	18 holes
5778-5783'	3 JSPP	15 holes
5743-5746'	3 JSPP	9 holes
5697-5701'	3 JSPP	12 holes
5670-5673'	3 JSPP	9 holes
5535-5537'	3 JSPP	6 holes
5440-5445'	3 JSPP	15 holes
5313-5315'	3 JSPP	6 holes
5259-5261'	3 JSPP	6 holes
5104-5109'	3 JSPP	15 holes
4630-4632'	3 JSPP	6 holes
4614-4623'	3 JSPP	27 holes

NEWFIELD



Monument Butte Federal J-34-8-16
 868' FNL & 648' FWL
 NW/NW Section 35-T8S-R16E
 Duchesne Co, Utah
 API # 43-013-33936; Lease # UTU-16535

Monument Butte Fed L-34-8-16

Spud Date 6-11-10
Put on Production: 8-23-10
GL: 5691' KB: 5703'

Wellbore Diagram

SURFACE CASING

CSG SIZE: 8-5/8"
GRADE: J-55
WEIGHT: 24#
LENGTH: 7jts 302
DEPTH LANDED: 313.85'
HOLE SIZE: 12-1/4"
CEMENT DATA: 160 sxs Class "G" cmt

PRODUCTION CASING

CSG SIZE: 5-1/2"
GRADE: J-55
WEIGHT: 15.5#
LENGTH: 155jts (6557.85')
HOLE SIZE: 7-7/8"
DEPTH LANDED: 6572.46'
CEMENT DATA: 300 sxs Prem. Lite II mixed & 400sxs 50/50 POZ.
CEMENT TOP AT: 166'

TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
NO. OF JOINTS: 199jts (6253.6')
TUBING ANCHOR: 6265.6'
NO. OF JOINTS: 2jts 62.8'
SEATING NIPPLE: 2-7/8" (1.1')
SN LANDED AT: 6331.1' KB
NO. OF JOINTS: 2jts (62.9')
TOTAL STRING LENGTH: EOT @ 6396'


SUCKER RODS

POLISHED ROD: 1-1/2" x 30'
SUCKER RODS: 1 - 2x 7/8 pony rods, 1 - 4' x 7/8" pony rods, 1 - 8 x 7/8 pony rods, 248 - 8-7/8" per guided rods, 4 - 1 1/2" weight bars
PUMP SIZE: 2 1/2 x 1 3/4 x 20' x 24' RHAC
STROKE LENGTH: 144
PUMP SPEED: SPM 5

FRAC JOB

8-16-10 6304-6337' Frac GB sands as follows: Frac with 29802# 20/40 sand in 262bbls Lightning 17 fluid.
8-16-10 5989-6070' Frac GB4 sands as follows: Frac with 76858# 20/40 sand in 478bbls Lightning 17 fluid.
8-16-10 5614-5624' Frac GB4 sands as follows: Frac with 35162# 20/40 sand in 237bbls Lightning 17 fluid.
8-16-10 5090-5168' Frac GB4 sands as follows: Frac with 53606# 20/40 sand in 353 bbls Lightning 17 fluid.

Cement Top @ 166'

PERFORATION RECORD

6304-6306'	3 JSPF	6holes
6309-6311'	3 JSPF	6 holes
6314-6316'	3 JSPF	6 holes
6319-6321'	3 JSPF	6 holes
6334-6337'	3 JSPF	9holes
6066-6070'	3 JSPF	12 holes
6034-6037'	3 JSPF	9 holes
5989-5991'	3 JSPF	6 holes
5614-5624'	3 JSPF	30 holes
5164-5168'	3 JSPF	6 holes
5097-5100'	3 JSPF	9 holes
5090-5092'	3 JSPF	6 holes

NEWFIELD



Monument Butte Fed L-34-8-16

SL: 1971 FNL & 1956FEL (NW/SE)

Section 34, T8S, R16

Duchesne Co, Utah

API # 43-013-34125; Lease #UTU-16535

Monument Butte Federal 4A-35R-8-16

Spud Date: 3/4/96
Put on Production: 4/11/96
GL: 5564' KB: 5577'

Initial Production: 106 BOPD,
96 MCFGPD, 8 BWPD

Wellbore Diagram

SURFACE CASING

CSG SIZE: 8-5/8"
GRADE: J-55
WEIGHT: 24#
LENGTH: 303.93'
DEPTH LANDED: 302.73'(GL)
HOLE SIZE: 12-1/4"
CEMENT DATA: 120 sxs Premium cmt, est 4 bbls to surf.

PRODUCTION CASING

CSG SIZE: 5-1/2"
GRADE: J-55
WEIGHT: 15.5#
LENGTH: 143 jts. (6100.56')
DEPTH LANDED: 6099.94'
HOLE SIZE: 7-7/8"
CEMENT DATA: 330 sk Hyfill mixed & 355 sxs thixotropic
CEMENT TOP AT: 1100' per CBL

TUBING

SIZE/GRADE/WT.: 2-7/8" / M-50
NO. OF JOINTS: 103 jts (3154.89') 10 jts j-55 (317.43') 53 jts M-50 (1623.39') 19 jts j-55 (603.85')
TUBING ANCHOR: 5723.08'
NO. OF JOINTS: 1 jt. (31.00")
SEATING NIPPLE: 2-7/8" (1.10")
SN LANDED AT: 5757.18'
NO. OF JOINTS: 2 jts. (62.72')
TOTAL STRING LENGTH: EOT @ 5821.45'

SUCKER RODS


POLISHED ROD: 1-1/2" x 22' SM
SUCKER RODS: 4-1 1/2" weight bars, 2- 5/8" weight bars, 33-3/4" guided rods, 86-3/4" plain rods, 103-3/4" guided rods, 4', 6', 8', x 3/4" pony rods.
PUMP SIZE: 2-1/2" x 1-1/2" x 14.5' RHAC
STROKE LENGTH: 76"
PUMP SPEED, SPM: 5 SPM

FRAC JOB

4/1/96	5676'-5720'	Frac LDC sand as follows: 102,700# 20/40 sd in 581 bbls Boragel. Breakdown @ 2401'. Treated as Follows: avg rate 34 bpm, avg press 3700 psi. Had to keep reducing flush to stay below 4000# max press. ISIP-3882 psi, 5-min 3350 psi. Flowback after 5 min on 16/64" ck @ 2 bpm.
4/3/96	5515'-5521'	Frac A-1 sand as follows: 44,000# 20/40 (screen out w/2699 gal into flush 7# sd off frimn - 26,800# in frimn) used in 264 bbls fluid. Breakdown @ 2620 psi treated as follows: avg rate 15.8 bpm, avg press 2300 psi. ISIP-screen out, 5-min 2897 psi. Flowback after 5 min on 16/64" ck @ 1 bpm.
4/5/96	5341'-5351'	Frac B-2 sand as follows: 40,800# 20/40 sd in 328 bbls Boragel. Breakdown @ 1650 psi treated @ avg rate 18.5 bpm, avg press 2200 psi. ISIP 2950 psi, 5-min 2537 psi. Flowback after 5 min on 16/64" ck @ 1.5 bpm.
4/8/96	5049'-5067'	Frac D-1 sand as follows: 42,700# 20/40 sd in 316 bbls Boragel. Breakdown @ 3010 psi. Treated @ avg rate 19.5 bpm, avg press 2500 psi. ISIP-2383 psi, 5-min 2328 psi. Flowback after 5 min on 16/64" ck @ 1.8 bpm.
6/7/01	4570'-4586'	Frac GB-6 sand as follows: 97,140# 20/40 sd in 614 bbls Viking I-25 fluid. Treated @ avg rate 30.5 bpm, avg press 2330 psi. ISIP-2630 psi. Flowback on 16/64" ck @ 1 bpm.
4/28/03		Tubing Leak. Update tubing and rod details.
11/4/05		Parted rods: Update rod and tubing details.
10/2/08		Tubing Leak. Updated rod & tubing details.

PERFORATION RECORD

3/30/96	5676'-5720'	2 JSPF	80 holes
4/2/96	5515'-5521'	4 JSPF	24 holes
4/4/96	5341'-5351'	4 JSPF	40 holes
4/6/96	5049'-5056'	4 JSPF	28 holes
4/6/96	5060'-5067'	4 JSPF	28 holes
7/22/01	4570'-4586'	4 JSPF	64 holes



NEWFIELD

Monument Federal 4A-35R-8-16

859 FNL & 660 FWL

NW/NW Section 35-T8S-R16E

Duchesne Co, Utah

API #43-013-31585; Lease #UTU-16535

Spud Date: 10/3/82
Put on Production: 11/5/82
Put on Injection: 2/01/88
GL: 5584' KB: 5594'

Monument Butte Fed. 5-35-8-16

Initial Production: 176 BOPD,
NM MCFD, 16 BWPD

Injection
Wellbore Diagram

SURFACE CASING

CSG SIZE: 8-5/8"
GRADE: J-55
WEIGHT: 24#
DEPTH LANDED: 284'
HOLE SIZE: 12-1/4"
CEMENT DATA: 210 sxs Class "G" cmt.

PRODUCTION CASING


CSG SIZE: 5-1/2"
GRADE: J-55
WEIGHT: 17#
LENGTH: 143 jts.
DEPTH LANDED: 5985'
HOLE SIZE: 7-7/8"
CEMENT DATA: 375 sxs Hilift & 250 sxs RFC.
CEMENT TOP AT: 1080' per CBL

TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
NO. OF JOINTS: 140 jts. (4439.7')
SEATING NIPPLE: 2-7/8" (1.10')
SN LANDED AT: 4457.7' KB
PACKER CE @: 4462' KB
TOTAL STRING LENGTH: EOT @ 4466' KB

FRAC JOB

10/22/82	5326'-5373'	Frac B2 sand as follows: 104,000# 20/40 sand in 1023 bbls frac fluid. Treated @ avg press of 2900 psi w/avg rate of 36 BPM. ISIP 2000 psi. Flushed to perms.
10/28/82	5016'-5038'	Frac D1 sand as follows: 120,000# 20/40 sand in 1023 bbls frac fluid. Treated @ avg press of 2650 psi w/avg rate of 35 BPM. ISIP 1950 psi. Flushed to perms.
08-29-03		Conversion to Injection Well. Update tubing detail
8/6/08		5 Year MIT completed and submitted.
7/11/08		Zone stimulation
05/02/11		Tubing Leak. Rod detail updated.



PERFORATION RECORD

10/21/82	5326'-5332'	06 holes
10/21/82	5334'-5336'	02 holes
10/21/82	5364'-5373'	09 holes
10/27/82	5016'-5038'	23 holes
08/26/03	5894'-5898'	4 JSPF 16 holes
08/26/03	5190'-5199'	4 JSPF 36 holes
08/26/03	4550'-4558'	4 JSPF 32 holes
08/26/03	4512'-4520'	4 JSPF 32 holes



Monument Butte Fed. 5-35-8-16
2042' FNL & 661' FWL
SWNW Section 35-T8S-R16E
Duchesne Co, Utah
API #43-013-30686; Lease #U-16535

Monument Butte Fed. #6-35-8-16

Spud Date: 7/13/82
Put on Production: 8/18/83
GL: 5562'

SURFACE CASING


CSG SIZE: 8-5/8"
GRADE: J-55
WEIGHT: 24#
LENGTH: 7 jts. (290')
DEPTH LANDED: 280'
HOLE SIZE: 12-1/4"
CEMENT DATA: 210 sxs Class "G" cmt. to surf

PRODUCTION CASING

CSG SIZE: 5-1/2"
GRADE: J-55
WEIGHT: 15.5#
LENGTH: 140 jts.
DEPTH LANDED: 5656.58'
HOLE SIZE: 7-7/8"
CEMENT DATA: 250 sx Lodense & 300 sxs Gypseal.
CEMENT TOP AT: 2464' per CBL

TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
NO. OF JOINTS: 137 jts. (4445.38')
TUBING ANCHOR: 4459.53'
SEATING NIPPLE: 2-7/8" (1.10')
SN LANDED AT: 4455.38'
TOTAL STRING LENGTH: EOT @ 4463.85'

Injection Wellbore
Diagram**FRAC JOB**

8/3/83	5025'-5055'	Frac as follows: 102,000# 20/40 sand in 672 bbls fluid. Treated @ avg press of 2320 psi w/avg rate of 32 BPM. ISIP 2020 psi.
1/10/91	5342'-5374'	Frac as follows: 65,000# 20/40 sand in 1002 bbls fluid. Treated @ avg press of 3800 psi w/avg rate of 17 BPM. ISIP 2440 psi.
11/30/01		Tubing leak. Update rod and tubing details.
12/9/02	5506'-5514'	Frac A sands as follows: 19,730# 20/40 sand in 189 bbls Viking I-25 fluid. Treated @ avg. pressure of 4595 psi w/avg. rate of 18.2 BPM. ISIP - 7400 psi. Calc. flush: 1442 gals. Actual flush: 1302 gals.
12/9/02	5196'-5210'	Frac C sands as follows: 24,541# 20/40 sand in 222 bbls Viking I-25 fluid. Treated @ avg. pressure of 4090 psi w/avg. rate of 18.2 BPM. ISIP - 2400 psi. Calc. flush: 1442 gals. Actual flush: 1260 gals.
12/9/02	4511'-4569'	Frac GB sands as follows: 61,347# 20/40 sand in 471 bbls Viking I-25 fluid. Treated @ avg. pressure of 2010 psi w/avg. rate of 26.2 BPM. ISIP - 2150 psi. Calc. flush: 4511 gals. Actual flush: 4410 gals.
03/16/04		Parted Rods. Update rod details.
10/15/08		Well converted to an Injection Well.
10/27/08		MIT completed and submitted.
10/23/08		Tubing Leak. Updated tubing details.

PERFORATION RECORD

8/3/83	5052'-5054'	1 JSPF	3 holes
8/3/83	5032'-5044'	1 JSPF	13 holes
8/3/83	5026'-5030'	1 JSPF	6 holes
1/7/91	5052'-5054'	3 JSPF	9 holes
1/7/91	5032'-5044'	3 JSPF	39 holes
1/7/91	5025'-5030'	3 JSPF	18 holes
1/7/91	5342'-5350'	4 JSPF	32 holes
1/7/91	5360'-5374'	4 JSPF	56 holes
12/6/02	5506'-5514'	4 JSPF	32 holes
12/6/02	5205'-5210'	4 JSPF	20 holes
12/6/02	5196'-5200'	4 JSPF	16 holes
12/6/02	4561'-4569'	4 JSPF	32 holes
12/6/02	4550'-4554'	4 JSPF	16 holes
12/6/02	4511'-4515'	4 JSPF	16 holes

NEWFIELD**Monument Butte Fed. #6-35-8-16**

1831' FNL & 1968' FWL

SE/NW Section 35-T8S-R16E

Duchesne Co, Utah

API #43-013-30751; Lease #UTU-16535

Monument Butte Fed. #12-35

Spud Date: 6/5/1983
 Put on Production: 11/19/1988
 GL: 5586' KB: 5597'

Initial Production: 33 BOPD,
 80 MCFD, NM BWPD

Injection Wellbore
 Diagram

SURFACE CASING

CSG SIZE: 8-5/8"
 GRADE: J-55
 WEIGHT: 24#
 LENGTH: 7 jts.
 DEPTH LANDED: 304'
 HOLE SIZE: 12-1/4"
 CEMENT DATA: 210 sxs Class "G" cmt.


PRODUCTION CASING

CSG SIZE: 5-1/2"
 GRADE: J-55
 WEIGHT: 15.5#
 LENGTH: 140 jts.
 DEPTH LANDED: 5677'
 HOLE SIZE: 7-7/8"
 CEMENT DATA: 300 sxs LoDense & 300 sxs Gypseal
 CEMENT TOP AT: 1144' per CBL

TUBING

SIZE/GRADE/WT.: 2 7/8" / J-55 / 6.5#
 NO. OF JOINTS: 141 jts (4456.38')
 SEATING NIPPLE: 2 7/8" (1.10')
 SN LANDED AT: 4467.38' KB
 Arrowset I-X pkr (7.40)
 CE (3.30') @ 4471.78
 TOTAL STRING LENGTH: EOT @ 4475.88'

Cement Top @ 1144' per CBL

FRAC JOB

7/13/83	5000'-5022'	Frac D-1 sand as follows: 124,300# 20/40 sand in 858 bbls Viking I-25 fluid.
7/13/83	4998'-5022'	Break zones as follows: 164 bbl. 3% KCl, max press. 2500#, ISIP 1800#.
	5057'-5067'	
5/18/01	4519'-4552'	Frac GB-6 sand as follows: 146,000# 20/40 sand in 910 bbls Viking I-25 fluid. Treat @ avg. pressure of 2100 psi at 29.8 BPM. ISIP 2430 psi. Calc. Flush: 4519 bbl. Act. Flush: 4326 bbl. Flow 7 hrs. then died.
12/26/01		Rod job. Update rod and tubing details.
4/18/03		Tubing leak. Update rod and tubing details.
07/15/09		Converted to Injection well
07/17/09		MIT completed update tbg detail

PERFORATION RECORD

7/12/83	4998'-5022'	4 JSPF	96 holes
11/18/88	5057'-5067'	4 JSPF	40 holes
5/17/01	4519'-4552'	4 JSPF	132 holes



Monument Butte Fed. #12-35
 779' FWL & 1839' FSL
 NWSW Section 35-T8S-R16E
 Duchesne Co, Utah
 API #43-013-30744; Lease #U-16535

Monument Butte Federal N-35-8-16

Spud Date: 10/13/09
Put on Production: 1/21/2010
GL: 5570' KB: 5582'

Wellbore Diagram

SURFACE CASING

CSG SIZE: 8-5/8"
GRADE: J-55
WEIGHT: 24#
LENGTH: 7 jts. (309.49')
DEPTH LANDED: 321.31'
HOLE SIZE: 12-1/4"
CEMENT DATA: 160 sxs Class "G" cmt

PRODUCTION CASING

CSG SIZE: 5-1/2"
GRADE: J-55
WEIGHT: 15.5#
LENGTH: 152 jts. (6367.76')
HOLE SIZE: 7-7/8"
DEPTH LANDED: 6423.12'
CEMENT DATA: 281 sxs Prem. Lite II mixed & 425 sxs 50/50 POZ.
CEMENT TOP AT: 56'

TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
NO. OF JOINTS: 186 jts (6059.3')
TUBING ANCHOR: 6071.3'
NO. OF JOINTS: 2 jts (6074.1')
SEATING NIPPLE: 2-7/8" (1.1')
SN LANDED AT: 6139.3' KB
NO. OF JOINTS: 1 jts (32.6')
TOTAL STRING LENGTH: EOT @ 6277'

SUCKER RODS

POLISHED ROD: 1-1/2" x 30'
SUCKER RODS: 241- 7/8" guided rods (8 per), 4- 1 1/2" weight bars
PUMP SIZE: 2 1/2 x 1 3/4 x 20' x 24' RHAC
STROKE LENGTH: 142"
PUMP SPEED, SPM: 7

FRAC JOB

1/21/2010 6313-6320' **Frac CP4 sands as follows:**
Frac with 35509# 20/40 sand in 228 bbls
Lightning 17 fluid.
1/21/2010 5976-6035' **Frac CP.5 & CP1 sands as follows:**
Frac with 14873# 20/40 sand in 124 bbls
Lightning 17 fluid.
1/21/2010 5573-5726' **Frac A3 & LODC sands as follows:**
Frac with 24774# 20/40 sand in 211 bbls
Lightning 17 fluid.
1/21/2010 5274-5422' **Frac C & B2 sands as follows:**
Frac with 35618# 20/40 sand in 234 bbls
Lightning 17 fluid.
1/21/2010 5091-5165' **Frac D1 & D2 sands as follows:**
Frac with 90633# 20/40 sand in 383 bbls
Lightning 17 fluid.
1/21/2010 4562-4620' **Frac GB4 & GB6 sands as follows:**
Frac with 100094# 20/40 sand in 595
bbls Lightning 17 fluid.

Cement Top @ 56'

SN @ 6139'

Anchor @ 6071'

EOT @ 6277'

6313-6320'

PBTD @ 6380'

TD @ 6435'

PERFORATION RECORD

6313-6320'	3 JSPF	21 holes
6031-6035'	3 JSPF	12 holes
5984-5986'	3 JSPF	6 holes
5976-5978'	3 JSPF	6 holes
5719-5726'	3 JSPF	21 holes
5573-5577'	3 JSPF	12 holes
5414-5422'	3 JSPF	24 holes
5274-5276'	3 JSPF	6 holes
5162-5165'	3 JSPF	9 holes
5111-5114'	3 JSPF	9 holes
5097-5102'	3 JSPF	15 holes
4614-4620'	3 JSPF	18 holes
4576-4579'	3 JSPF	9 holes
4562-4564'	3 JSPF	6 holes

NEWFIELD

Monument Butte Federal N-35-8-16
1856' FSL & 1871' FWL
NE/SW Section 35-T8S-R16E
Duchesne Co, Utah
API # 43-013-33872; Lease # UTU-16535

Monument Butte Federal O-35-8-16

Spud Date: 10-6-09
Put on Production: 12/4/09
GL: 5606' KB: 5618'

Wellbore Diagram

SURFACE CASING

CSG SIZE: 8-5/8"
GRADE: J-55
WEIGHT: 24#
LENGTH: 7jts. (307.75')
DEPTH LANDED: 319.60'
HOLE SIZE: 12-1/4"
CEMENT DATA: 160 sxs Class "G" cmt

PRODUCTION CASING

CSG SIZE: 5-1/2"
GRADE: J-55
WEIGHT: 15.5#
LENGTH: 153 jts. (6405.41')
HOLE SIZE: 7-7/8"
DEPTH LANDED: 6440.81'
CEMENT DATA: 350 sxs Prem. Lite II mixed & 450 sxs 50/50 POZ.
CEMENT TOP AT: Surface


TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
NO. OF JOINTS: 192 jts (6030.2')
TUBING ANCHOR: 6042.2'
NO. OF JOINTS: 1 jts (30.3')
SEATING NIPPLE: 2-7/8" (1.1')
SN LANDED AT: 6075.3' KB
NO. OF JOINTS: 1 jts (30.3')
TOTAL STRING LENGTH: EOT @ 6207'

SUCKER RODS

POLISHED ROD: 1-1/2" x 30'
SUCKER RODS: 1- 4' x 7/8" pony rod, 238- 7/8" guided rods (4 per), 4- 1 1/2" weight bars
PUMP SIZE: 2 1/2 x 1 3/4 x 21' x 24' RHAC
STROKE LENGTH: 144
PUMP SPEED, SPM: 5

Cement Top @
Surface

FRAC JOB

12/4/09	6101-6309'	Frac CP2, CP3, CP4 & CP5 sands as follows: Frac with 50,416# 20/40 sand in 338 bbls Lightning 17 fluid.
12/4/09	5985-6032'	Frac CP.5 & CP1 sands as follows: Frac 34,427# 20/40 sand in 230 bbls Lightning 17 fluid.
12/4/09	5737-5747'	Frac LODC sands as follows: Frac 80,757# 20/40 sand in 480 bbls Lightning 17 fluid.
12/4/09	5546-5606'	Frac A1 & A3 sands as follows: Frac 76,214# 20/40 sand in 465 bbls Lightning 17 fluid.
12/4/09	5092-5102'	Frac D1 sands as follows: Frac 60,348# 20/40 sand in 370 bbls Lightning 17 fluid.
12/4/09	4573-4620'	Frac GB4 & GB6 sands as follows: Frac 9943# 20/40 sand in 109 bbls Lightning 17 fluid.

PERFORATION RECORD

6305-6309'	3 JSPF	12 holes
6221-6224'	3 JSPF	9 holes
6167-6169'	3 JSPF	6 holes
6101-6103'	3 JSPF	6 holes
6029-6032'	3 JSPF	9 holes
5985-5993'	3 JSPF	24 holes
5737-5747'	3 JSPF	30 holes
5599-5606'	3 JSPF	21 holes
5546-5549'	3 JSPF	9 holes
5092-5102'	3 JSPF	30 holes
4616-4620'	3 JSPF	12 holes
4573-4577'	3 JSPF	12 holes



Monument Butte Federal O-35-8-16
1900' FSL & 636' FEL
NE/SE Section 34-T8S-R16E
Duchesne Co, Utah
API # 43-013-33873; Lease # UTU-16535

Monument Butte Q-35-8-16

Spud Date: 5-18-08
Put on Production: 6-23-08

GL: 5591' KB: 5603'

SURFACE CASING

CSG SIZE: 8-5/8"
GRADE: J-55
WEIGHT: 24#
LENGTH: 7 jts (310.30')
DEPTH LANDED: 322.15'
HOLE SIZE: 12-1/4"
CEMENT DATA: 160 sxs Class "G", circ. 3 bbls to surf.

PRODUCTION CASING

CSG SIZE: 5-1/2"
GRADE: J-55
WEIGHT: 15.5#
LENGTH: 143 jts (6517.91')
DEPTH LANDED: 6531.16'
HOLE SIZE: 7-7/8"
CEMENT DATA: 300 sxs Premlite II and 450 sxs 50/50 POZ
CEMENT TOP AT: 190' per CBL 6/12/08


TUBING (GI 6/23/08)

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
NO. OF JOINTS: 188 jts (5908.84')
TUBING ANCHOR: 5920.84' kb
NO. OF JOINTS: 1jt (31.30')
SEATING NIPPLE: 2-7/8" (1.10')
SN LANDED AT: 5954.94'
NO. OF JOINTS: 2jts (62.92')
TOTAL STRING LENGTH: EOT @ 6019.41'

SUCKER RODS (GI 7/9/12)

POLISHED ROD: 1-1/2" x 26'
SUCKER RODS: 2', 6' x 7/8" pony rods, 233 x 7/8" guided rods (8per), 4 x 1-1/2" weight bars.
PUMP SIZE: 2-1/2" x 1-1/2" x 20' RHAC
STROKE LENGTH: 124"
PUMP SPEED, SPM: 5
PUMPING UNIT: DARCO C-456-305-144

Wellbore Diagram



FRAC JOB

6-17-08 5938-5950' **Frac CP.5 sds as follows:**
19,945# 20/40 sand in 339 bbls of Lightning 17 fluid. Treated w/ ave pressure of 2264 psi @ ave rate of 23.3 BPM. ISIP 1981 psi. Actual flush: 5418 gals.


6-17-08 5558-5584' **Frac A1 sds as follows:**
160,780# 20/40 sand in 1113 bbls of Lightning 17 fluid. Treated w/ ave pressure of 1421 psi @ ave rate of 26.2 BPM. ISIP 2010 psi. Actual flush: 5040 gals.

6-17-08 5060-5084' **Frac D1 sds as follows:**
40,231# 20/40 sand in 412 bbls of Lightning 17 fluid. Treated w/ ave pressure of 1962 psi @ ave rate of 23.3 BPM. ISIP 2408 psi. Actual flush: 4540 gals.

6-17-08 4592-4604' **Frac GB6 sds as follows:**
46,614# 20/40 sand in 434 bbls of Lightning 17 fluid. Treated w/ ave pressure of 2016 psi @ ave rate of 23.2 BPM. ISIP 2278 psi. Actual flush: 4498 gals.

PERFORATION RECORD

4592-4604'	4 JSPF	48 holes
5060-5084'	4 JSPF	96 holes
5558-5584'	4 JSPF	104 holes
5938-5950'	4 JSPF	48 holes



NEWFIELD

Monument Butte Q-35-8-16

1821' FSL & 764' FWL

NE/SW Section 35-T8S-R16E

Duchesne Co, Utah

API # 43-013-33752; Lease # UTU-16535

Monument Butte Federal I-34-8-16

Spud Date: 10/14/2009
Put on Production: 12/17/2009
GL: 5594' KB: 5606'

Wellbore Diagram

SURFACE CASING

CSG SIZE: 8-5/8"
GRADE: J-55
WEIGHT: 24#
LENGTH: 7 jts (310.08')
DEPTH LANDED: 321.93
HOLE SIZE: 12-1/4"
CEMENT DATA: 160 sxs Class "G" cmt

Cement Top @ 58'

PRODUCTION CASING

CSG SIZE: 5-1/2"
GRADE: J-55
WEIGHT: 15.5#
LENGTH: 156 jts (6533.04')
HOLE SIZE: 7-7/8"
DEPTH LANDED: 6548.44'
CEMENT DATA: 280 sxs Prem. Lite II mixed & 425 sxs 50/50 POZ.
CEMENT TOP AT: 58'

TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
NO. OF JOINTS: 193 jts (6284')
TUBING ANCHOR: 6283.9'
NO. OF JOINTS: 2 jts (65.0')
SEATING NIPPLE: 2-7/8" (1.1')
SN LANDED AT: 6351.7' KB
NO. OF JOINTS: 2 jts (65.0')
TOTAL STRING LENGTH: EOT @ 6418'

SUCKER RODS

POLISHED ROD: 1-1/2" x 30'
SUCKER RODS: 1 - 4' x 7/8" pony rods, 250 - 7/8" guided rods, 4 - 1 1/2" weight bars
PUMP SIZE: 2 1/2 x 1 1/4 x 21' x 24' RHAC
STROKE LENGTH: 144
PUMP SPEED: SPM 5

FRAC JOB

12-17-09	6346-6404'	Frac CP5 & BSL sands as follows: Frac with 24558# 20/40 sand in 144 bbls Lightning 17 fluid.
12-17-09	6028-6034'	Frac CP.5 sands as follows: Frac with 10657# 20/40 sand in 60 bbls Lightning 17 fluid.
12-17-09	5678-5710'	Frac LODC sands as follows: Frac with 160910# 20/40 sand in 673 bbls Lightning 17 fluid.
12-17-9-09	5566-5619'	Frac A3 & A1 sands as follows: Frac with 70541# 20/40 sand in 302 bbls Lightning 17 fluid.
12-17-09	5118-5128'	Frac D1 sands as follows: Frac with 46288# 20/40 sand in 211 bbls Lightning 17 fluid.
12-17-09	4592-4652'	Frac GB6 & GB4 sands as follows: Frac with 73363# 20/40 sand in 294 bbls Lightning 17 fluid.
01/06/2010		Stuck Pump. Updated rod and tubing details
03/29/2010		Pump Change. Updated rod and tubing details
2/3/2011		Tubing Leak. Update rod and tubing details.

SN @ 6351'

Anchor @ 6284'

6346-6350'

6366-6369'

6401-6404'

EOT @ 6418'

PBTD @ 6445'

TD @ 6555'

PERFORATION RECORD

6401-6404'	3 JSPF	9 holes
6366-6369'	3 JSPF	9 holes
6346-6350'	3 JSPF	12 holes
6028-6034'	3 JSPF	18 holes
5706-5710'	3 JSPF	12 holes
5690-5694'	3 JSPF	12 holes
5678-5681'	3 JSPF	9 holes
5616-5619'	3 JSPF	9 holes
5581-5583'	3 JSPF	6 holes
5566-5570'	3 JSPF	12 holes
5118-5128'	3 JSPF	30 holes
4648-4652'	3 JSPF	12 holes
4638-4643'	3 JSPF	15 holes
4592-4596'	3 JSPF	12 holes

NEWFIELD

Monument Butte Federal I-34-8-16

657' FNL & 1967' FEL (NW/NE)

BHL: 1534' FNL & 1142' FEL (SE/NE)

Section 34, T8S, R16E

Duchesne Co, Utah

API # 43-013-33871, Lease # UTU-16535

CB 3/10/2011

Greater Monument Butte B-3-9-16

Spud Date: 11/15/10
Put on Production: 1/13/11
GL: 5612' KB: 5624'

Wellbore Diagram

SURFACE CASING

CSG SIZE: 8-5/8"
GRADE: J-55
WEIGHT: 24#
LENGTH: 7 jts. (302.1')
DEPTH LANDED: 313.95'
HOLE SIZE: 12-1/4"
CEMENT DATA: 160 sxs Class "G" cmt

PRODUCTION CASING

CSG SIZE: 5-1/2"
GRADE: J-55
WEIGHT: 15.5#
LENGTH: 155 jts. (6526.7')
HOLE SIZE: 7-7/8"
DEPTH LANDED: 6541.31'
CEMENT DATA: 300 sxs Prem. Lite II mixed & 400 sxs 50/50 POZ.
CEMENT TOP AT: 372'

TUBING


SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
NO. OF JOINTS: 198 jts (6182')
TUBING ANCHOR: 6194'
NO. OF JOINTS: 1 jts (31.4')
SEATING NIPPLE: 2-7/8" (1.1')
SN LANDED AT: 6228.3' KB
NO. OF JOINTS: 2 jts (61.7')
TOTAL STRING LENGTH: EOT @ 6291'

SUCKER RODS

POLISHED ROD: 1-1/2" x 30'
SUCKER RODS: 1 - 7/8" = 2' pony rods; 1 - 7/8" = 4' pony rods; 243 - 7/8" = 6075' 8 per guided rods; 4 - 1 1/2" = 100' weight bars
PUMP SIZE: 2 1/2 x 1 3/4 x 20" x 24' RHAC
STROKE LENGTH: 144
PUMP SPEED: 5 SPM

FRAC JOB

1/13/2011 6214'-6241' **Frac CP5 sands as follows:**
Frac with 9,766# 20/40 sand in 165 bbls
Lightning 17 fluid.
1/13/2011 5958' - 6007' **Frac CP1 & CP2 sands as follows:**
Frac with 67,860# 20/40 sand in 422 bbls
Lightning 17 fluid.
1/13/2011 5579' - 5587' **Frac A3 sands as follows:**
Frac with 25,267# 20/40 sand in 214 bbls
Lightning 17 fluid.
1/13/2011 5373' - 5390' **Frac B2 sands as follows:**
Frac with 54,471# 20/40 sand in 346 bbls
Lightning 17 fluid.
1/13/2011 5233' - 5238' **Frac C sands as follows:**
Frac with 10,291# 20/40 sand in 92 bbls
Lightning 17 fluid.
1/13/2011 5057' - 5072' **Frac D sands as follows:**
Frac with 16,385# 20/40 sand in 153 bbls
Lightning 17 fluid.



PERFORATION RECORD

6238'-6241'	3 JSPF	9 holes
6214'-6217'	3 JSPF	9 holes
6004'-6007'	3 JSPF	9 holes
5992'-5995'	3 JSPF	9 holes
5965'-5967'	3 JSPF	6 holes
5958'-5960'	3 JSPF	6 holes
5579'-5587'	3 JSPF	24 holes
5385'-5390'	3 JSPF	15 holes
5380'-5382'	3 JSPF	6 holes
5373'-5375'	3 JSPF	6 holes
5233'-5238'	3 JSPF	15 holes
5069'-5071'	3 JSPF	6 holes
5057'-5063'	3 JSPF	18 holes

NEWFIELD



Greater Monument Butte B-3-9-16

632' FSL & 692' FEL (SE/SE)

Section 34, T8S, R16E

Duchesne Co, Utah

API # 43-013-50281; Lease # UTU-16535

Greater Monument Butte E-2-9-16

Spud Date: 11-12-10
Put on Production: 1-5-11
GL: 5612' KB: 5624'

Wellbore Diagram

FRAC JOB

SURFACE CASING

CSG SIZE: 8-5/8"
GRADE: J-55
WEIGHT: 24#
LENGTH: 7jts. 296.6'
DEPTH LANDED 308.45'
HOLE SIZE: 12-1/4"
CEMENT DATA: 160sxs Class "G" cmt

PRODUCTION CASING

CSG SIZE: 5-1/2"
GRADE: J-55
WEIGHT: 15.5#
LENGTH: 152jts. (6430.85')
HOLE SIZE: 7-7/8"
DEPTH LANDED: 6445.46'
CEMENT DATA: 275sxs Prem. Lite II mixed & 400sxs 50/50 POZ.
CEMENT TOP AT: 240'


TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
NO. OF JOINTS: 198jts (6169.7')
TUBING ANCHOR: 6181.7'
NO. OF JOINTS: 2 jts (62.8')
SEATING NIPPLE: 2-7/8" (1.1')
SN LANDED: 6247.3' KB
NO. OF JOINTS: 2jts (62.8')
TOTAL STRING LENGTH: EOT @6312'

SUCKER RODS

POLISHED ROD: 1-1/2" x 30'
SUCKER RODS: 1-2 x 7/8" pony rods, 1-4 x 7/8" pony rods, 1-6 x 7/8" pony rods, 1-8 x 7/8" pony rods, 234-x 7/8" 4 per guided rods, 4- 1 1/2" weight bars
PUMP SIZE: 2 1/2 x 1 1/4" x 20" x 24" RHAC
STROKE LENGTH: 144
PUMP SPEED: SPM 5

12-17-10	6202-6247'	Frac CP4 & CP5 sands as follows: Frac with 20441# 20/40 sand in 171bbls Lightning 17 fluid.
12-20-10	5965-6068'	Frac CP3 & CP1 sands as follows: Frac with 24806# 20/40 sand in 213bbls Lightning 17 fluid.
12-20-10	5383-5597'	Frac B2 & A3 sands as follows: Frac with 20319# 20/40 sand in 172bbls Lightning 17 fluid.
12-20-10	5058-5066'	Frac D1 sands as follows: Frac with 30311# 20/40 sand in 251bbls Lightning 17 fluid.
12-20-10	4756-4893'	Frac PB10 & Xstray sands as follows: Frac with 20440# 20/40 sand in 172bbls Lightning 17 fluid.
12-20-10	4507-4472'	Frac GB4 & GB2 sands as follows: Frac with 24503# 20/40 sand in 213bbls Lightning 17 fluid.



PERFORATION RECORD

6241-6247'	3 JSPF	18holes
6202-6206'	3 JSPF	12 holes
6065-6068'	3 JSPF	9holes
5965-5975'	3 JSPF	30 holes
5594-5597'	3 JSPF	9holes
5587-5589'	3 JSPF	6holes
5383-5385'	3 JSPF	6holes
5058-5066'	3 JSPF	24holes
4889-4893'	3 JSPF	12holes
4756-4760'	3 JSPF	12holes
4507-4511'	3 JSPF	12holes
4467-4472'	3 JSPF	15holes
4467-4472'	3 JSPF	15holes

NEWFIELD

Greater Monument Butte E-2-9-16

SHL - 645' FSL & 675' FEL (SE/SE)
Section 34, T8S, R16

BHL - 10 FNL & 10 FWL (NE/NE)

Section 2, T9S, R16

Duchesne Co, Utah

API # 43-013-50285; Lease # USA UTU-16535

Multi-Chem Analytical Laboratory

1553 East Highway 40

Vernal, UT 84078

Units of Measurement: Standard

Water Analysis Report

Production Company: NEWFIELD PRODUCTION

Well Name: MBIF

Sample Point: After Filter

Sample Date: 11/28/2012

Sample ID: WA-229143

Sales Rep: Michael McBride

Lab Tech: Gary Peterson

Scaling potential predicted using ScaleSoftPitzer from
Brine Chemistry Consortium (Rice University)

Sample Specifics		Analysis @ Properties in Sample Specifics			
		Cations		Anions	
		mg/L		mg/L	
Test Date:	12/5/2012	Sodium (Na):	2811.52	Chloride (Cl):	4000.00
System Temperature 1 (°F):	120.00	Potassium (K):	12.00	Sulfate (SO ₄):	40.00
System Pressure 1 (psig):	60.0000	Magnesium (Mg):	17.20	Bicarbonate (HCO ₃):	732.00
System Temperature 2 (°F):	210.00	Calcium (Ca):	32.50	Carbonate (CO ₃):	
System Pressure 2 (psig):	60.0000	Strontium (Sr):		Acetic Acid (CH ₃ COO)	
Calculated Density (g/ml):	1.002	Barium (Ba):	0.40	Propionic Acid (C ₂ H ₅ COO)	
pH:	7.90	Iron (Fe):	0.17	Butanoic Acid (C ₃ H ₇ COO)	
Calculated TDS (mg/L):	7645.92	Zinc (Zn):	0.02	Isobutyric Acid ((CH ₃) ₂ CHCOO)	
CO ₂ in Gas (%):		Lead (Pb):	0.00	Fluoride (F):	
Dissolved CO ₂ (mg/L):	67.00	Ammonia NH ₃ :		Bromine (Br):	
H ₂ S in Gas (%):		Manganese (Mn):	0.11	Silica (SiO ₂):	
H ₂ S in Water (mg/L):	2.00				

Notes:

(PTB = Pounds per Thousand Barrels)

		Calcium Carbonate		Barium Sulfate		Iron Sulfide		Iron Carbonate		Gypsum CaSO ₄ ·2H ₂ O		Celestite SrSO ₄		Halite NaCl		Zinc Sulfide	
Temp (°F)	PSI	SI	PTB	SI	PTB	SI	PTB	SI	PTB	SI	PTB	SI	PTB	SI	PTB	SI	PTB
210.00	60.00	1.18	22.96	0.00	0.00	1.10	0.09	0.93	0.11	0.00	0.00	0.00	0.00	0.00	0.00	6.99	0.01
200.00	60.00	1.11	22.06	0.00	0.00	1.07	0.08	0.86	0.11	0.00	0.00	0.00	0.00	0.00	0.00	7.06	0.01
190.00	60.00	1.05	21.08	0.00	0.00	1.04	0.08	0.79	0.11	0.00	0.00	0.00	0.00	0.00	0.00	7.13	0.01
180.00	60.00	0.98	20.02	0.00	0.00	1.01	0.08	0.72	0.10	0.00	0.00	0.00	0.00	0.00	0.00	7.20	0.01
170.00	60.00	0.92	18.90	0.00	0.00	0.99	0.08	0.65	0.09	0.00	0.00	0.00	0.00	0.00	0.00	7.28	0.01
160.00	60.00	0.85	17.74	0.00	0.00	0.97	0.08	0.58	0.09	0.00	0.00	0.00	0.00	0.00	0.00	7.37	0.01
150.00	60.00	0.79	16.54	0.00	0.00	0.97	0.08	0.50	0.08	0.00	0.00	0.00	0.00	0.00	0.00	7.47	0.01
140.00	60.00	0.74	15.34	0.00	0.00	0.96	0.08	0.43	0.08	0.00	0.00	0.00	0.00	0.00	0.00	7.57	0.01
130.00	60.00	0.68	14.14	0.00	0.00	0.97	0.08	0.35	0.07	0.00	0.00	0.00	0.00	0.00	0.00	7.68	0.01
120.00	60.00	0.63	12.97	0.00	0.00	0.98	0.08	0.27	0.06	0.00	0.00	0.00	0.00	0.00	0.00	7.81	0.01


		Hemihydrate CaSO ₄ ·0.5H ₂ O		Anhydrite CaSO ₄		Calcium Fluoride		Zinc Carbonate		Lead Sulfide		Mg Silicate		Ca Mg Silicate		Fe Silicate	
Temp (°F)	PSI	SI	PTB	SI	PTB	SI	PTB	SI	PTB	SI	PTB	SI	PTB	SI	PTB	SI	PTB
210.00	60.00	0.00	0.00	0.00	0.00	0.00	0.00	0.09	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	60.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
190.00	60.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
180.00	60.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
170.00	60.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
160.00	60.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
150.00	60.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
140.00	60.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
130.00	60.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
120.00	60.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

Water Analysis Report


These scales have positive scaling potential under initial temperature and pressure: Calcium Carbonate Iron Sulfide Iron Carbonate Zinc Sulfide Zinc Carbonate

These scales have positive scaling potential under final temperature and pressure: Calcium Carbonate Iron Sulfide Iron Carbonate Zinc Sulfide


Calcium Carbonate




Iron Carbonate




Iron Sulfide



Zinc Sulfide



Zinc Carbonate



Multi-Chem Analytical Laboratory

1553 East Highway 40

Vernal, UT 84078

Units of Measurement: **Standard**

Water Analysis Report

Production Company: **NEWFIELD PRODUCTION**Well Name: **MON 8-34-8-16**Sample Point: **Treater**Sample Date: **3/11/2013**Sample ID: **WA-236462**Sales Rep: **Michael McBride**Lab Tech: **Layne Wilkerson**Scaling potential predicted using ScaleSoftPitzer from
Brine Chemistry Consortium (Rice University)

Sample Specifics		Analysis @ Properties in Sample Specifics			
Test Date:	3/20/2013	Cations		Anions	
		mg/L		mg/L	
System Temperature 1 (°F):	120.00	Sodium (Na):	2918.18	Chloride (Cl):	4000.00
System Pressure 1 (psig):	60.0000	Potassium (K):	18.00	Sulfate (SO ₄):	30.00
System Temperature 2 (°F):	210.00	Magnesium (Mg):	1.00	Bicarbonate (HCO ₃):	878.40
System Pressure 2 (psig):	60.0000	Calcium (Ca):	6.30	Carbonate (CO ₃):	
Calculated Density (g/ml):	1.003	Strontium (Sr):	0.00	Acetic Acid (CH ₃ COO)	
pH:	8.50	Barium (Ba):	1.20	Propionic Acid (C ₂ H ₅ COO)	
Calculated TDS (mg/L):	7877.28	Iron (Fe):	0.90	Butanoic Acid (C ₃ H ₇ COO)	
CO ₂ in Gas (%):		Zinc (Zn):	0.14	Isobutyric Acid ((CH ₃) ₂ CHCOO)	
Dissolved CO ₂ (mg/L):	0.00	Lead (Pb):	0.04	Fluoride (F):	
H ₂ S in Gas (%):		Ammonia NH ₃ :		Bromine (Br):	
H ₂ S in Water (mg/L):	2.00	Manganese (Mn):	0.02	Silica (SiO ₂):	23.10

Notes:

B=3.8 AI=.03

(PTB = Pounds per Thousand Barrels)





		Calcium Carbonate		Barium Sulfate		Iron Sulfide		Iron Carbonate		Gypsum CaSO ₄ 2H ₂ O		Celestite SrSO ₄		Halite NaCl		Zinc Sulfide	
Temp (°F)	PSI	SI	PTB	SI	PTB	SI	PTB	SI	PTB	SI	PTB	SI	PTB	SI	PTB	SI	PTB
210.00	60.00	0.92	4.71	0.00	0.00	2.22	0.49	2.10	0.65	0.00	0.00	0.00	0.00	0.00	0.00	8.24	0.07
200.00	60.00	0.87	4.62	0.00	0.00	2.21	0.49	2.05	0.65	0.00	0.00	0.00	0.00	0.00	0.00	8.32	0.07
190.00	60.00	0.82	4.51	0.00	0.00	2.20	0.49	2.00	0.65	0.00	0.00	0.00	0.00	0.00	0.00	8.41	0.07
180.00	60.00	0.77	4.40	0.00	0.00	2.19	0.49	1.95	0.65	0.00	0.00	0.00	0.00	0.00	0.00	8.50	0.07
170.00	60.00	0.73	4.28	0.00	0.00	2.19	0.49	1.90	0.64	0.00	0.00	0.00	0.00	0.00	0.00	8.60	0.07
160.00	60.00	0.68	4.15	0.00	0.00	2.20	0.49	1.84	0.64	0.00	0.00	0.00	0.00	0.00	0.00	8.71	0.07
150.00	60.00	0.64	4.01	0.00	0.00	2.21	0.49	1.79	0.64	0.00	0.00	0.00	0.00	0.00	0.00	8.83	0.07
140.00	60.00	0.60	3.87	0.00	0.00	2.23	0.49	1.73	0.64	0.00	0.00	0.00	0.00	0.00	0.00	8.95	0.07
130.00	60.00	0.56	3.73	0.00	0.00	2.25	0.49	1.67	0.64	0.00	0.00	0.00	0.00	0.00	0.00	9.09	0.07
120.00	60.00	0.53	3.59	0.02	0.03	2.29	0.49	1.62	0.64	0.00	0.00	0.00	0.00	0.00	0.00	9.23	0.07

Water Analysis Report

Temp (°F)	PSI	Hemihydrate CaSO ₄ •0.5H ₂ O		Anhydrate CaSO ₄		Calcium Fluoride		Zinc Carbonate		Lead Sulfide		Mg Silicate		Ca Mg Silicate		Fe Silicate	
		SI	PTB	SI	PTB	SI	PTB	SI	PTB	SI	PTB	SI	PTB	SI	PTB	SI	PTB
210.00	60.00	0.00	0.00	0.00	0.00	0.00	0.00	1.38	0.09	8.76	0.02	3.36	1.83	1.69	2.94	9.83	0.70
200.00	60.00	0.00	0.00	0.00	0.00	0.00	0.00	1.30	0.09	8.91	0.02	2.97	1.77	1.46	2.82	9.55	0.70
190.00	60.00	0.00	0.00	0.00	0.00	0.00	0.00	1.22	0.09	9.07	0.02	2.58	1.69	1.23	2.63	9.27	0.70
180.00	60.00	0.00	0.00	0.00	0.00	0.00	0.00	1.13	0.09	9.24	0.02	2.17	1.58	1.00	2.36	8.99	0.70
170.00	60.00	0.00	0.00	0.00	0.00	0.00	0.00	1.04	0.08	9.42	0.02	1.75	1.43	0.76	2.00	8.70	0.70
160.00	60.00	0.00	0.00	0.00	0.00	0.00	0.00	0.94	0.08	9.61	0.02	1.33	1.23	0.52	1.55	8.42	0.70
150.00	60.00	0.00	0.00	0.00	0.00	0.00	0.00	0.83	0.08	9.81	0.02	0.91	0.96	0.28	1.01	8.13	0.70
140.00	60.00	0.00	0.00	0.00	0.00	0.00	0.00	0.72	0.08	10.03	0.02	0.48	0.61	0.04	0.39	7.84	0.70
130.00	60.00	0.00	0.00	0.00	0.00	0.00	0.00	0.61	0.07	10.25	0.02	0.05	0.17	0.00	0.00	7.56	0.70
120.00	60.00	0.00	0.00	0.00	0.00	0.00	0.00	0.49	0.06	10.50	0.02	0.00	0.00	0.00	0.00	7.29	0.70

These scales have positive scaling potential under initial temperature and pressure: Calcium Carbonate Iron Sulfide Iron Carbonate Zinc Sulfide Zinc Carbonate Lead Sulfide Mg Silicate Ca Mg Silicate Fe Silicate

These scales have positive scaling potential under final temperature and pressure: Calcium Carbonate Barium Sulfate Iron Sulfide Iron Carbonate Zinc Sulfide Zinc Carbonate Lead Sulfide Fe Silicate




Multi-Chem Analytical Laboratory

1553 East Highway 40


Vernal, UT 84078

Water Analysis Report


Lead Sulfide




Zinc Sulfide




Ca Mg Silicate




Zinc Carbonate



Mg Silicate



Water Analysis Report



Attachment "G"

**Monument 8-34-8-16
Proposed Maximum Injection Pressure**

Frac Interval (feet)		Avg. Depth (feet)	ISIP (psi)	Calculated Frac Gradient (psi/ft)	Pmax
Top	Bottom				
5024	5043	5034	2160	0.86	2127 ←
5911	6273	6092	2200	0.81	2162
5444	5634	5539	3700	1.11	3665
5190	5344	5267	2750	0.96	2716
4432	4577	4505	3300	1.18	3271
				Minimum	<u><u>2127</u></u>

Calculation of Maximum Surface Injection Pressure

$P_{max} = (\text{Frac Grad} - (0.433 \times 1.015)) \times \text{Depth of Top Perf}$
 where pressure gradient for the fresh water is .433 psi/ft and
 specific gravity of the injected water is 1.015.

$$\text{Frac Gradient} = (\text{ISIP} + (0.433 \times \text{Top Perf.})) / \text{Top Perf.}$$

Please note: These are existing perforations; additional perforations may be added during the actual conversion procedure.

LOMAX EXPLORATION

Monument Federal #8-34
Section 34, T8S, R16E
Duchesne County, Utah

COMPLETION REPORT

3/28/84 Present Operation RUSU. (1 day)
REMARKS: MISU.
CUM COST: \$156,809

3/29/84 Present Operation - Prep to TIH w/ bit & scraper. (2 days)
REMARKS: RUSU. NU BOP's. Racked 199 jts 2 7/8" 6.5# J-55
tbq. Prep to TIH w/ bit & scraper.
CUM COST: \$177,809

3/30/84 Present Operation - Pressure test casing. (3 days)
REMARKS: TIH w/ bit & Scraper to 6300' KB. Displaced hole w/
5% KCL wtr & clay stab. TOH. RUWL. Ran CBL/VDL/GR from 6300'-
4500' and across cement top. RDWL. TIH open ended to 5500'±.
Prep to test csq. SDFN.
CUM COST: \$183,774

3/31/84 Present Operation-Swabbing. (4 days)
REMARKS : Pressure test CSG to 3000 psi OK R.U. to swab.
Swabbed fluid level down to 4100' TOW. RUWL. Perforated
FDC/CNL interval 6219'-30' w/ 1JSPF. RDWL. TIH w/ pkr.
Set @ 6112' KB. Broke perfs down w/ 3000 qals. 5% KCL wtr. &
clay stab & 30 balls sealers. Breakdown @ 3100 psi ATP 2200
@ 5 1/2 BPM. 151P 1700. Good Ball action. FTP 3200 psi. @ 5 BPM.
Flowed back 7 BLW. R.U. to Swab. Made 5 runs. 1 FL @ Surf.
FFL @ 6100'. Recovered 35 BLW, 10% yellow oil on final run,
slight gas. SDFN.
CUM COST: \$190,274

4-1-84 Present Operation- SHUT- IN (5 days)
REMARKS : 13 hrs. SITP 50 psi. RU to swab 1FL @ 5300'
FFL @ 6100' Made 5 swab runs. Recovered 4 BLW 1 BNO, slight
gas. swabbed 1/2 BF, 30% yellow oil in final 3hrs. SDF SUNDAY
CUM COST: \$192,374

4/ /84 Present Operation-Swabbing (6 days)
REMARKS: 40 hr. SITP 100 psi. R.U. to swab. IFL @ 4,100'.
FFL @ 6,100'. Made 4 runs. Recovered 11 BNO, 1/2 BLW. Final
2 hourly runs, no recovery. Rel. pkr. TIH across perfs.
Reset pkr. @ 6,112' KB. Swabbed tbq. down to 6,100'. Made
5 hourly runs. Recovered 1 1/2 BF, 20-30% oil cut, very slight
gas. Wtr. analysis 13,500 ppm Cl, PH 7.3, SDFN.
CUM COST: \$ 194,924

4/4/84 Present Operation - Prep to frac. (7 days)
REMARKS: 14 hr SITP 50 psi. RU to swab. IFL @ 5600'. Made
1 run from 6100'. Recovered 2 BNO, 1 BLW. Chlorides 10,000
ppm. Released pkr & TOH. RUWL. Ran CIBP. Set @ 5610' KB.
Perforated FDC/CNL interval 5024'-38' & 5040'-43' w/ 1JSPF.
RDWL. TIH w/ pkr. Set @ 5300' & tested CIBP to 3000 psi, ok.
Released pkr & reset @ 4900'. Broke perfs down w/ rig bump
@ 1400 psi. Released pkr & swabbed fluid down to 4900'. TOH.
SDFN.
CUM COST: \$200,424

LOMAX EXPLORATION
Monument Federal #8-34
Duchesne County, Utah
COMPLETION REPORT (2)

4/5/84 Present Operation - Shut-in after frac. (8 days)
REMARKS: RU Halliburton. Frac as follows:
1) Pumped 8000 gal pad
2) " 2500 " 1 PPG 20/40 sand
3) " 3500 " 2 " " "
4) " 4500 " 4 " " "
5) " 5000 " 6 " " "
6) " 4000 " 8 " " "
7) Flush to perfs
Max TP 2650 @ 31 BPM
Avg TP 2100 @ 31 BPM
ISIP 2160, 2040 after 5 min, 1980 after 10 min, 1940
after 15 min. SDFN.
CUM COST: \$221,949

4/6/84 Present Operation - Swabbing. (9 days)
REMARKS: 21 hr SICP 0 psi. PU pkr & TIH. Set @ 4500' KB.
RU to swab. IFL @ surf, FFL @ 4000'. Made 15 swab runs.
Recovered 57 BLW, 18 BNO, moderate gas. Final swab rate
3 BPH, 40% oil. SDFN.
CUM COST: \$225,074

4/7/84 Present Operation - SI for BHPBU. (10 days)
REMARKS: 14 hr SITP 110 psi. RU to swab. IFL @ 1700', FFL
@ 4800'. Made 8 swab runs. Recovered 21 BNO, 13 BLW. Moderate
gas. Final swab rate 3-3.5 BPH. Final oil cut 80%. Released
pkr & TIH to 5250' w/o tagging fill. Reset pkr @ 5000' KB. &
swabbed tbq down to pkr RUWL. Ran BHP bombs & landed @ 4950'
KB. Shut well in for 72 hr BHPBU.
CUM COST: \$230,249

4/8/84 Present Operation - SI for BHPBU. (11 days)
REMARKS: SI for BHPBU.
CUM COST: \$230,369

4/9/84 Present Operation - SI for BHPBU. (12 days)
REMARKS: SI for BHPBU.
CUM COST: \$230,369

4/10/84 Present Operation - Prep to swab. (13 days)
REMARKS: SI for BHPBU. RUWL. TOH w/ bombs. 71 hr SIBHP
1264 psi. Prep to swab.
CUM COST: \$230,619

4/11/84 Present Operation - Prep to run pump & rods. (14 days)
REMARKS: 88 hr SITP 40 psi. (TIW valve leaking). RU to
swab. IFL @ 1800', FFL @ 3000'. Made 6 runs. Recovered 17
BNO, 28 BLW. Final swab rate 6 BPH, 60% oil, moderate gas.
Rel pkr & TIH. Tagged sand @ 5297' KB. TOH. TIH w/ NC, 3
jts 2 7/8" tbq, SN, 2 jts, tbq anchor, 151 jts. ND BOP. Set
anchor w/ 10,000# tension. NU tbq bonnet. Prep to TIH w/
pump & rods. SDFN.
CUM COST: \$233,979

4/12/84 Present Operation - WO facilities. RDMOSU. (15 days)
REMARKS: TIH w/ 1.5" Axelson pump, 4 wt rods, 100 slick 3/4"
rods, 95 scraped 3/4" rods, 1- 6' pony rod, polish rod.
Tested pump, ok. Too windy to rig down. SDFN.
CUM COST: \$248,979

ATTACHMENT H

WORK PROCEDURE FOR PLUGGING AND ABANDONMENT

1. Set CIBP @ 4382'
2. Plug #1 Set 100' plug on top of CIBP using 12 sx Class "G" cement
3. Perforate 4 JSPF @ 3292'
4. Plug #2 152' plug covering Trona/Mohogany Bench Formation using 30 sx Class "G" Cement pumped under CICR and out perforations. Follow using 13 sx Class "G" cement pumped on top of CICR
5. Perforate 4 JSPF @ 1780'
6. Plug #3 120' plug covering Uinta/Green River formation using 25sx Class "G" cement pumped under CICR and out perforations. Follow using 7 sx Class "G" cement pumped on top of CICR
7. Perforate 4 JSPF @ 352'
8. Plug #4 Circulate 83 sx Class "G" cement down 5 1/2" casing and up the 5-1/2" x 8-5/8" annulus

The approximate cost to plug and abandon this well is \$42,000.

Monument Butte Fed. #8-34-8-16

Spud Date: 2/28/1984
Put on Production: 3//1984
Put on Injection: 3/25/1994
Convert to Producer: 4/18/01
GL: 5617' KB: 5627'

Initial Production: 35 BOPD,
139 MCFD, 0 BWPD


SURFACE CASING

CSG SIZE: 8-5/8" / J-55 / 24#
LENGTH: 6 jts. (279')
DEPTH LANDED: 302'
HOLE SIZE: 12-1/4"
CEMENT DATA: 210 sxs Class "G" cmt.

PRODUCTION CASING

CSG SIZE: 5-1/2" / J-55 / 17#
LENGTH: 161 jts. (6388')
DEPTH LANDED: 6369'
HOLE SIZE: 7-7/8"
CEMENT DATA: 150 sxs HiFill & 325 sxs Gypseal.
CEMENT TOP AT: 3284' per CBL

Proposed P & A Wellbore Diagram



Monument Butte Fed. #8-34-8-16
2059' FNL & 701' FEL
SENE Section 34-T8S-R16E
Duchesne Co, Utah
API #43-013-30843; Lease #U-16535

**DIVISION OF OIL, GAS AND MINING
UNDERGROUND INJECTION CONTROL PROGRAM
PERMIT
STATEMENT OF BASIS**

Applicant: Newfield Production Company

Well: Monument Butte Federal 8-34-8-16

Location: 34/8S/16E

API: 43-013-30843

Note: Monument Butte Federal 8-34-8-16 was previously permitted as an injection well (UIC-148.1). The original application for conversion was received February 17, 1994. Public notice was issued March 30, 1994. The original UIC permit (for interval 5024-5043 feet) was issued April 15, and the first injection was April 19, 1994. Then the well was put back on production May 7, 2001. It remains on production at the time the current application was received on April 24, 2013, for conversion back to an injection well. Inasmuch as it has been twelve years since the well injected, and there has been a great deal of new activity in the area of review (AOR), it is appropriate to complete a new evaluation.

Ownership Issues: The proposed well is located on BLM land. The well is located in the Greater Monument Butte Unit. Lands in the one-half mile radius of the well are administered by the BLM. The Federal Government is the mineral owner within the area of review (AOR). Newfield and other various individuals hold the leases in the unit. Newfield has provided a list of all surface, mineral and lease holders in the half-mile radius. Newfield is the operator of the Greater Monument Butte Unit. Newfield has submitted an affidavit stating that all owners and interest owners have been notified of their intent.

Well Integrity: The proposed well has surface casing set at 302 feet and has a cement top at the surface. A 5½ inch production casing is set at 6,369 feet. The cement bond log appears to demonstrate adequate bond in this well up to about 3,284 feet. A 2 7/8 inch tubing with a packer will be set at 4,382 feet. Higher perforations may be opened at a later date. A mechanical integrity test will be run on the well prior to injection. Based on surface locations, there are 12 producing wells, 9 injection wells, 1 shut-in well, and 1 P/A well in the AOR. Three of the producing wells are directionally drilled, with a surface locations inside the AOR and bottom hole locations outside the AOR. In addition, there are 4 directional wells with surface locations outside the AOR and bottom hole locations inside the AOR. All of the existing wells have evidence of adequate casing and cement for the proposed injection interval. Inasmuch as some logs are of dubious quality or do not exhibit conclusive cement tops, it has been necessary to calculate approximate tops for “lite” cement, based on the cement indicated in the well completion report.

Ground Water Protection: As interpreted from the Utah Geological Survey’s DOE Project-Uinta Basin Water Draft Map (Paul B. Anderson, December 2, 2011), the base of moderately

Monument Butte Federal 8-34-8-16

page 2

saline water (3000-10,000 mg/l TDS) is at a depth of approximately 1000 feet. Injection shall be limited to the interval between 4,322 feet and 6,350 feet in the Green River Formation. Information submitted by Newfield indicates that the fracture gradient for the 8-34-8-16 well is 0.86 psi/ft., which was the lowest reported fracture gradient for the injection zone. The resulting minimum fracture pressure for the proposed injection interval is 2,127 psig. The requested maximum pressure is 2,127 psig. We intend to permit this well at a maximum pressure of 2,000 psig. The anticipated average injection pressure is 1100 psig. Injection at this pressure should not initiate any new fractures or propagate existing fractures in the adjacent confining intervals. Any ground water present should be adequately protected.

Oil/Gas& Other Mineral Resources Protection: At the time of the original conversion to an injection well in 1994, this well was part of an existing waterflood project in the Monument Butte Field. The Statement of Basis (3/30/1994) concluded at that time that injection into this well should have no adverse effects on any offsetting production outside the unit area. Subsequently, the Board of Oil, Gas & Mining approved the Greater Monument Butte Unit on December 1, 2009. Correlative rights issues were addressed at this time. Previous reviews in this area indicate that other mineral resources in the area have been protected or are not at issue.

Bonding: Bonded with the BLM

Actions Taken and Further Approvals Needed: Monument Butte 8-34 was originally permitted as an injection well as UIC-148.1. A notice of agency action was sent to the Salt Lake Tribune and the Uinta Basin Standard on March 30, 1994. The well was put on injection April 19, 1994 and operated as an injection well until it was put back on production on May 7, 2001. The current application for putting the well back on injection status was received April 24, 2013. A casing/tubing pressure test will be required prior to injection. It is recommended that approval of this application be granted.

Note: Applicable technical publications concerning water resources in the general vicinity of this project have been reviewed and taken into consideration during the permit review process.

Reviewer(s): Mark Reinbold

Date: 5/7/2013



GARY R. HERBERT
Governor

GREGORY S. BELL
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

May 8, 2013

Newfield Production Company
1001 Seventeenth Street, Suite 2000
Denver, CO 80202

Subject: Greater Monument Butte Unit Well: Monument Butte Federal 8-34, Section 34, Township 8 South, Range 16 East, SLBM, Duchesne County, Utah, API Well # 43-013-30843


Gentlemen:

Pursuant to Utah Admin. Code R649-5-3-3, the Division of Oil, Gas and Mining (the "Division") issues its administrative approval for conversion of the referenced well to a Class II injection well. Accordingly, the following stipulations shall apply for full compliance with this approval:

1. Compliance with all applicable requirements for the operation, maintenance and reporting for Underground Injection Control ("UIC") Class II injection wells pursuant to Utah Admin. Code R649-1 et seq.
2. Conformance with all conditions and requirements of the complete application submitted by Newfield Production Company.
3. A casing/tubing pressure test shall be conducted prior to commencing injection.
4. Pressure shall be monitored between the surface casing and the production casing on a regular basis. Any pressure changes observed shall be reported to the Division immediately.
5. The top of the injection interval shall be limited to a depth no higher than 4,322 feet in the Monument Butte Federal 8-34 well.

A final approval to commence injection will be issued upon satisfactory completion of the listed stipulations. If you have any questions regarding this approval or the necessary requirements, please contact Mark Reinbold at 801-538-5333 or Brad Hill at 801-538-5315.

Sincerely,



John Rogers
Associate Director


JR/MLR/js

cc: Bruce Suchomel, Environmental Protection Agency
Bureau of Land Management, Vernal
Duchesne County
Newfield Production Company, Myton
Well File

N:\O&G Reviewed Docs\ChronFile\UIC



Sundry Number: 43705 API Well Number: 43013308430000

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9			
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-16535			
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:			
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		7. UNIT or CA AGREEMENT NAME: GMBU (GRRV)			
3. ADDRESS OF OPERATOR: Rt 3 Box 3630, Myton, UT, 84052		8. WELL NAME and NUMBER: MONUMENT FED 8-34			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2059 FNL 0701 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENE Section: 34 Township: 08.0S Range: 16.0E Meridian: S		9. API NUMBER: 43013308430000			
PHONE NUMBER: 435 646-4825 Ext		9. FIELD and POOL or WILDCAT: MONUMENT BUTTE			
COUNTY: DUCHESNE		STATE: UTAH			
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA					
TYPE OF SUBMISSION <input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: <input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 10/9/2013 <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	TYPE OF ACTION <table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input checked="" type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input checked="" type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input checked="" type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input checked="" type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER:
<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input checked="" type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input checked="" type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: 			
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. <div style="display: flex; justify-content: space-between;"> <div style="width: 70%;"> <p>The subject well has been converted from a producing oil well to an injection well on 10/08/2013. On 10/08/2013 Chris Jensen with the State of Utah DOGM was contacted concerning the initial MIT on the above listed well. On 10/09/2013 the casing was pressured up to 1375 psig and charted for 30 minutes with no pressure loss. The well was not injecting during the test. The tubing pressure was 0 psig during the test. There was not a State representative available to witness the test.</p> </div> <div style="width: 25%; text-align: center;"> <p>Accepted by the Utah Division of Oil, Gas and Mining</p> <p>Date: October 17, 2013</p> <p>By: </p> </div> </div>					
NAME (PLEASE PRINT) Lucy Chavez-Naupoto	PHONE NUMBER 435 646-4874	TITLE Water Services Technician			
SIGNATURE N/A		DATE 10/10/2013			

RECEIVED: Oct. 10, 2013

Mechanical Integrity Test Casing or Annulus Pressure Test

Newfield Production Company

Rt. 3 Box 3630
Myton, UT 84052
435-646-3721

Witness: _____ Date 10/9/2013 Time 9:00 am pm

Test Conducted by: Kim Giles

Others Present: Troy Lazenby

Conversion

Well: Monument Butte Federal 8-34-8-16 Field: Monument Butte

Well Location: SE/NE Sec. 34, T8S, R16E API No: 43-013-30843
Ducheme County Utah

<u>Time</u>	<u>Casing Pressure</u>	
0 min	<u>1375</u>	psig
5	<u>1375</u>	psig
10	<u>1375</u>	psig
15	<u>1375</u>	psig
20	<u>1375</u>	psig
25	<u>1375</u>	psig
30 min	<u>1375</u>	psig
35	_____	psig
40	_____	psig
45	_____	psig
50	_____	psig
55	_____	psig
60 min	_____	psig


Tubing pressure: 0 psig

Result: Pass Fail

Signature of Witness: _____


Signature of Person Conducting Test: Kim Giles

Sundry Number: 43705 API Well Number: 43013308430000



Sundry Number: 43705 API Well Number: 43013308430000

Day 1

NEWFIELD		Final Daily Workover Report		Well Name:	MON 8-34-8-16
		LOE		API:	
Field:		GMBU CTB4	Rig Name:	Report Date:	10/4/2013
Location:		S34 T8S R16E	Supervisor:	Operation:	FLUSHED CSG W/60 BBLs @ 250 DEGREES
County:		DUCHESNE	Phone:	Work Performed:	10/1/2013
State:		UT	Email:	Day:	1
Reason for Workover:		Conversion		Daily Cost:	\$14,645
				Cum DWR:	\$14,645

Failures

Failure Date	Failure 1	Failure 2	Failure 3	Failure 4	Failure 5
--------------	-----------	-----------	-----------	-----------	-----------

Summaries

24 Hr. Summary:	RD PU JARRED ON ROD STRING TELL PUMP CAME FREE LD POLISH ROD				
24 Hr. Plan Forward:	CONTINUE CONVERSION				
Incidents	None	Newfield Pers:	1	Contract Pers:	5
		Conditions:			

Activity Summary

P: RU RIG FLUSHED CSG 60 BBLs @250 DEGREES, RD PU JARRED ON ROD STRING TELL PUMP CAME FREE LD POLISH ROD, 2 RODS, PU POLISHED ROD FLUSHED TBG W/ 40 BBLs @ 250 DEGREES LD POLISH ROD PU THREE RODS SOFT SEATED PUMP SIWFN SHUT DOWN DUE TO RIG MAINTAINCE. RIG MAINTAINCE.

Activity Summary

P: CREW TRAVEL JSA SAFETY MEETING RIG MAINTAINCE LD 1-1/2" POLISH RODS, 2-7/8"X8' PONY RODS, 4-PER GUIDED RODS 106- 3/4" SLICK SUCKER RODS, 45-3/4" 4-PER GUIDED RODS, 6-1/2" C(API) WT BARS, 1-SUCKER PUMP ON TRAILER FLUSHING AND INSPECTION RODS COMING OUT OF HOLE SIWFN.

Activity Summary

P: CREW TRAVEL JSA SAFETY MEETING RD PU, ND WH, NU BOPS, RD RIG FLOOR RELEASED TAC, TOOH 134 JTS TBG BREAKING AND RE- DOPING EVERY CONNECTION W/ LIQUID O-RING GREEN DOPE WAITED ON RUNNERS FOR TBG LAY DOWN TRAILER LD 53 JTS TBG ON TRAILER TIH 134 JTS TBG, PUMPED 10 BBLs DOWN TBG , DROPPED SV CHASHED W/ 25 BBLs PRESSURED UP TBG TO 500 PSI SIWFN

Activity Summary

P: CREW TRAVEL JSA SAFETY MEETING PT TBG UP TO 3K PSI HELD 100% FOR 30 MIN. GOOD TEST RIH W/ SL RETRIEVED SV POOH SL RU RIG FLOOR ND BOPS NU INJECTION WH, CIRCULATED 50 BBLs OF PKR FLUID DOWN CSG SET PKR LOADED CSG W/ PKR FLUID PT CSG TO 1400 PSI HELD 100% FOR 30 MIN. GOOD TEST RD RIG PRE-TRIP INSPECTION

Activity Summary

9:00 AM - 9:30 AM; 0.5 Hr(s); P: On 10/08/2013 Chris Jensen with the State of Utah DOGM was contacted concerning the initial MIT on the above listed well. On 10/09/2013 the casing was pressured up to 1375 psig and charted for 30 minutes with no pressure loss. The well was not injecting during the test. The tubing pressure was 0 psig during the test. There was not a State representative available to witness the test.

					0	0	
					0	0	
					0	0	
					0	0	
					0	0	

Sundry Number: 43705 API Well Number: 43013308430000

Spud Date: 2/28/1984
Put on Production: 3/1/1984
Put on Injection: 3/25/1994
Convert to Producer: 4/18/01
GL: 5617' KB: 5627'

Monument Butte Fed. 8-34-8-16

Initial Production: 35 BOPD,
139 MCFD, 0 BWPD

Injection Wellbore
Diagram

SURFACE CASING


CSG SIZE: 8-5/8" / J-55 / 24#
LENGTH: 6 jts (279')
DEPTH LANDED: 302'
HOLE SIZE: 12-1/4"
CEMENT DATA: 210 sxs Class "G" cmt

PRODUCTION CASING

CSG SIZE: 5-1/2" / J-55 / 17#
LENGTH: 161 jts (6388')
DEPTH LANDED: 6369'
HOLE SIZE: 7-7/8"
CEMENT DATA: 150 sxs HiFill & 325 sxs Gypseal
CEMENT TOP AT: 3284' per CBL

TUBING

SIZE/GRADE/WT: 2-7/8" / J-55 / 6.5#
NO OF JOINTS: 134 jts (4337')
SEATING NIPPLE: 2-7/8" (1 10')
SN LANDED AT: 4351' KB
ON/OFF TOOL AT: 4352 1'
ARROW #1 PACKER CE AT: 4357 3'
SWEDGE AT: 4360 9'
TBG PUP 2-3/8 J-55 AT: 4361 4'
X/N NIPPLE AT: 4365 5'
TOTAL STRING LENGTH: EOT @ 4367 34'



FRAC JOB

4/05/84 5024'-5043' **Frac D1 sand as follows:** 89,500# 20/40 sand in 655 bbls frac fluid. Treated @ avg press of 2100 psi w/avg rate of 3.1 BPM ISIP 2160 psi. Flushed to perfs

10/09/90 5024'-5043' **Reperf D1 zone.**

10/13/90 **Acidize D1 w/ 100 gal 15% HCl + 60% N2**

4/19/94 **Put on Injection**

4/18/01 **Convert to producer.**

12/18/02 5024'-5043' **Squeezed perfs**

12/18/02 5911'-6273' **Frac BS and CP sands as follows:** 197,938# 20/40 sand in 1005 bbls Viking I-25 fluid. Treated @ avg pressure of 3330 psi w/avg rate of 15.2 BPM ISIP - 2200 psi. Calc flush: 1562 gals. Actual flush: 1437 gals

12/20/02 5444'-5634' **Frac A and LODC sands as follows:** 93,076# 20/40 sand in 512 bbls Viking I-25 fluid. Treated @ avg. pressure of 3950 psi w/avg rate of 15.0 ISIP - 3700 psi. Calc flush: 1451 gals. Actual flush: 42 gals

12/21/02 5190'-5344' **Frac B and C sands as follows:** 60,044# 20/40 sand in 305 bbls Viking I-25 fluid. Treated @ avg. pressure of 3830 psi w/avg rate of 15.0 BPM ISIP - 2750 psi. Calc flush: 1365 gals. Actual flush: 1283 gals

12/22/02 4432'-4577' **Frac GB sands as follows:** 26,820# 20/40 sand in 121 bbls Viking I-25 fluid. Treated @ avg. pressure of 2550 psi w/avg rate of 24.5 BPM ISIP - 3300 psi. Calc flush: 4432 gals. Actual flush: 3570 gals

Stuck Pump. Update rod detail

Stuck Pump. Update rod detail

Parted rods. Updated rod & tubing details

Parted rods. Updated rod & tubing details

Convert to Injection Well

Conversion MIT Finalized - update tbg detail

PERFORATION RECORD

Date	Depth Range	Tool	Holes
3/31/84	6219'-6236'	1 JSPF	17 holes
4/04/84	5040'-5043'	1 JSPF	04 holes Squeeze 12/02
4/04/84	5024'-5038'	1 JSPF	14 holes Squeeze 12/02
10/09/90	5040'-5043'	3 JSPF	12 holes
10/09/90	5024'-5038'	3 JSPF	42 holes
12/18/02	6267'-6273'	4 JSPF	24 holes
12/18/02	6246'-6252'	4 JSPF	24 holes
12/18/02	6219'-6236'	5 JSPF	85 holes reperf
12/18/02	6088'-6094'	4 JSPF	24 holes
12/18/02	6031'-6034'	4 JSPF	28 holes
12/18/02	6024'-6028'	4 JSPF	28 holes
12/18/02	6011'-6015'	4 JSPF	16 holes
12/18/02	5996'-5999'	4 JSPF	12 holes
12/18/02	5947'-5962'	4 JSPF	92 holes
12/18/02	5911'-5919'	4 JSPF	92 holes
12/18/02	5629'-5634'	4 JSPF	20 holes
12/18/02	5596'-5603'	4 JSPF	28 holes
12/18/02	5502'-5521'	4 JSPF	76 holes
12/18/02	5444'-5450'	4 JSPF	24 holes
12/18/02	5340'-5344'	4 JSPF	16 holes
12/18/02	5279'-5284'	4 JSPF	32 holes
12/18/02	5258'-5261'	4 JSPF	32 holes
12/18/02	5203'-5207'	4 JSPF	16 holes
12/18/02	5190'-5193'	4 JSPF	12 holes
12/18/02	4570'-4577'	4 JSPF	28 holes
12/18/02	4432'-4436'	4 JSPF	16 holes

NEWFIELD

Monument Butte Fed. 8-34-8-16
2059' FNL & 701' FEL
SENE Section 34-T8S-R16E
Duchesne Co, Utah
API #43-013-30843; Lease #U-16535



GARY R. HERBERT
Governor

GREGORY S. BELL
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

UNDERGROUND INJECTION CONTROL PERMIT

Cause No. UIC-148

Operator: Newfield Production Company
Well: Monument Federal 8-34
Location: Section 34, Township 8 South, Range 16 East
County: Duchesne
API No.: 43-013-30843
Well Type: Enhanced Recovery (waterflood)

Stipulations of Permit Approval

1. Approval for conversion to Injection Well issued on May 8, 2013.
2. Maximum Allowable Injection Pressure: 2,000 psig
3. Maximum Allowable Injection Rate: (restricted by pressure limitation)
4. Injection Interval: Green River Formation (4,322' – 6,350')
5. Any subsequent wells drilled within a ½ mile radius of this well shall have production casing cement brought up to or above the top of the unitized interval for the Greater Monument Butte Unit.

Approved by:


John Rogers
Associate Director

10/21/2013
Date

JR/MLR/js

cc: Bruce Suchomel, Environmental Protection Agency
Bureau of Land Management, Vernal
Eric Sundberg, Newfield Production Company, Denver
Newfield Production Company, Myton
Duchesne County
Well File

N:\O&G Reviewed Docs\ChronFile\UIC



Spud Date: 2/28/1984
Put on Production: 3/1/1984
Put on Injection: 3/25/1994
Convert to Producer: 4/18/01
GL: 5617' KB: 5627'

Monument Butte Fed. 8-34-8-16

Initial Production: 35 BOPD,
139 MCFD, 0 BWPD

Injection Wellbore
Diagram

SURFACE CASING

CSG SIZE: 8-5/8" / J-55 / 24#
LENGTH: 6 jts. (279')
DEPTH LANDED: 302'
HOLE SIZE: 12-1/4"
CEMENT DATA: 210 sxs Class "G" cmt.

PRODUCTION CASING

CSG SIZE: 5-1/2" / J-55 / 17#
LENGTH: 161 jts. (6388')
DEPTH LANDED: 6369'
HOLE SIZE: 7-7/8"
CEMENT DATA: 150 sxs HiFill & 3.25 sxs Gypseal
CEMENT TOP AT: 3284' per CBL

TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
NO. OF JOINTS: 134 jts (4337')
SEATING NIPPLE: 2-7/8" (1.10')
SN LANDED AT: 4351' KB
ON/OFF TOOL AT: 4352.1'
ARROW #1 PACKER CE AT: 4357.3'
SWEDGE AT: 4360.9'
TBG PUP 2-3/8 J-55 AT: 4361.4'
X/N NIPPLE AT: 4365.5'
TOTAL STRING LENGTH: EOT @ 4367.34'

TOC @ 3284'

SN @ 4351'

On Off Tool @ 4352'

Packer @ 4357'

X/N Nipple @ 4365'

EOT @ 4367'

4432'-4436'

4570'-4577'

10/08/13

10/09/13

5024'-5038' squeezed

5040'-5043' squeezed

5190'-5193'

5203'-5207'

5258'-5261'

5279'-5284'

5340'-5344'

5444'-5450'

5502'-5521'

5596'-5603'

5629'-5634'

5911'-5919'

5947'-5962'

5996'-5999'

6011'-6015'

6024'-6028'

6031'-6034'

6088'-6094'

6219'-6236' reperf

6246'-6252'

6267'-6273'

Top of fill @ 6345'

PBTD @ 6350'

TD @ 6400'

FRAC JOB

4/05/84 5024'-5043' **Frac D1 sand as follows:** 89,500# 20/40 sand in 655 bbls frac fluid. Treated @ avg press of 2100 psi w/avg rate of 31 BPM. ISIP 2160 psi. Flushed to perms.

10/09/90 5024'-5043' **Reperf D1 zone.**

10/13/90 **Acidize D1 w/ 100 gal 15% HCl + 60% N2.**

4/19/94 **Put on Injection.**

4/18/01 **Convert to producer.**

12/18/02 5024'-5043' **Squeezed perms**

12/18/02 5911'-6273' **Frac BS and CP sands as follows:** 197,938# 20/40 sand in 1005 bbls Viking I-25 fluid. Treated @ avg. pressure of 3330 psi w/avg. rate of 15.2 BPM. ISIP - 2200 psi. Calc. flush: 1562 gals. Actual flush: 1437 gals.

12/20/02 5444'-5634' **Frac A and LODC sands as follows:** 93,076# 20/40 sand in 512 bbls Viking I-25 fluid. Treated @ avg. pressure of 3950 psi w/avg. rate of 15.0 ISIP - 3700 psi. Calc. flush: 1451 gals. Actual flush: 42 gals.

12/21/02 5190'-5344' **Frac B and C sands as follows:** 60,044# 20/40 sand in 305 bbls Viking I-25 fluid. Treated @ avg. pressure of 3830 psi w/ avg. rate of 15.0 BPM. ISIP - 2750 psi. Calc. flush: 1365 gals. Actual flush: 1283 gals.

12/22/02 4432'-4577' **Frac GB sands as follows:** 26,820# 20/40 sand in 121 bbls Viking I-25 fluid. Treated @ avg. pressure of 2550 psi w/avg. rate of 24.5 BPM. ISIP - 3300 psi. Calc. flush: 4432 gals. Actual flush: 3570 gals.

5/18/04 **Stuck Pump.** Update rod detail.

6/24/04 **Stuck Pump.** Update rod detail.

6-19-08 **Parted rods.** Updated rod & tubing details.

1/8/09 **Parted rods.** Updated rod & tubing details.

10/08/13 **Convert to Injection Well**

10/09/13 **Conversion MIT Finalized** - update tbg detail

PERFORATION RECORD

3/31/84	6219'-6236'	1 JSPF	17 holes
4/04/84	5040'-5043'	1 JSPF	04 holes Squeeze 12/02
4/04/84	5024'-5038'	1 JSPF	14 holes Squeeze 12/02
10/09/90	5040'-5043'	3 JSPF	12 holes
10/09/90	5024'-5038'	3 JSPF	42 holes
12/18/02	6267'-6273'	4 JSPF	24 holes
12/18/02	6246'-6252'	4 JSPF	24 holes
12/18/02	6219'-6236'	5 JSPF	85 holes reperf
12/18/02	6088'-6094'	4 JSPF	24 holes
12/18/02	6031'-6034'	4 JSPF	28 holes
12/18/02	6024'-6028'	4 JSPF	28 holes
12/18/02	6011'-6015'	4 JSPF	16 holes
12/18/02	5996'-5999'	4 JSPF	12 holes
12/18/02	5947'-5962'	4 JSPF	92 holes
12/18/02	5911'-5919'	4 JSPF	92 holes
12/18/02	5629'-5634'	4 JSPF	20 holes
12/18/02	5596'-5603'	4 JSPF	28 holes
12/18/02	5502'-5521'	4 JSPF	76 holes
12/18/02	5444'-5450'	4 JSPF	24 holes
12/18/02	5340'-5344'	4 JSPF	16 holes
12/18/02	5279'-5284'	4 JSPF	32 holes
12/18/02	5258'-5261'	4 JSPF	32 holes
12/18/02	5203'-5207'	4 JSPF	16 holes
12/18/02	5190'-5193'	4 JSPF	12 holes
12/18/02	4570'-4577'	4 JSPF	28 holes
12/18/02	4432'-4436'	4 JSPF	16 holes

NEWFIELD

Monument Butte Fed. 8-34-8-16
2059' FNL & 701' FEL
SENE Section 34-T8S-R16E
Duchesne Co, Utah
API #43-013-30843; Lease #U-16535

Sundry Number: 44239 API Well Number: 43013308430000

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: U-16535
1. TYPE OF WELL Water Injection Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		7. UNIT or CA AGREEMENT NAME: GMBU (GRRV)
3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT, 84052		8. WELL NAME and NUMBER: MONUMENT FED 8-34
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2059 FNL 0701 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENE Section: 34 Township: 08.0S Range: 16.0E Meridian: S		9. API NUMBER: 43013308430000
PHONE NUMBER: 435 646-4825 Ext		9. FIELD and POOL or WILDCAT: MONUMENT BUTTE
COUNTY: DUCHESNE		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input checked="" type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input checked="" type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER:
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 10/23/2013			
<input type="checkbox"/> SPUD REPORT Date of Spud:			
<input type="checkbox"/> DRILLING REPORT Report Date:			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

The above reference well was put on injection at 11:15 AM on 10/23/2013.

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY
 October 29, 2013

NAME (PLEASE PRINT) Lucy Chavez-Naupoto	PHONE NUMBER 435 646-4874	TITLE Water Services Technician
SIGNATURE N/A	DATE 10/28/2013	

RECEIVED: Oct. 28, 2013

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	FORM 9 5. LEASE DESIGNATION AND SERIAL NUMBER: U-16535
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7. UNIT or CA AGREEMENT NAME: GMBU (GRRV)
1. TYPE OF WELL Water Injection Well	8. WELL NAME and NUMBER: MONUMENT FED 8-34
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY	9. API NUMBER: 43013308430000
3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT, 84052	PHONE NUMBER: 435 646-4825 Ext
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2059 FNL 0701 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENE Section: 34 Township: 08.0S Range: 16.0E Meridian: S	9. FIELD and POOL or WILDCAT: MONUMENT BUTTE COUNTY: DUCHESNE STATE: UTAH

11.

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 10/24/2014 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text" value="Polymer Squeeze"/>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Newfield proposes to do a polymer squeeze on the above mentioned well using a plug and packer system. See attached procedure.

**Accepted by the
Utah Division of
Oil, Gas and Mining**

Date: ~~November 12, 2014~~

By: *Derek Duff*

NAME (PLEASE PRINT) Mandie Crozier	PHONE NUMBER 435 646-4825	TITLE Regulatory Tech
SIGNATURE N/A		DATE 10/24/2014

Spud Date: 2/28/1984
 Put on Production: 3//1984
 Put on Injection: 3/25/1994
 Convert to Producer: 4/18/01
 GL: 5617' KB: 5627'

Monument Butte Fed. 8-34-8-16

Initial Production: 35 BOPD,
 139 MCFD, 0 BWPD

Injection Wellbore Diagram

SURFACE CASING


CSG SIZE: 8-5/8" / J-55 / 24#
 LENGTH: 6 jts. (279')
 DEPTH LANDED: 302'
 HOLE SIZE: 12-1/4"
 CEMENT DATA: 210 sxs Class "G" cmt.

PRODUCTION CASING

CSG SIZE: 5-1/2" / J-55 / 17#
 LENGTH: 161 jts. (6388')
 DEPTH LANDED: 6369'
 HOLE SIZE: 7-7/8"
 CEMENT DATA: 150 sxs HiFill & 3.25 sxs Gypseal
 CEMENT TOP AT: 3284' per CBL

TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
 NO. OF JOINTS: 134 jts (4337')
 SEATING NIPPLE: 2-7/8" (1.10')
 SN LANDED AT: 4351' KB
 ON/OFF TOOL AT: 4352.1'
 ARROW #1 PACKER CE AT: 4357.3'
 SWEDGE AT: 4360.9'
 TBG PUP 2-3/8 J-55 AT: 4361.4'
 X/N NIPPLE AT: 4365.5'
 TOTAL STRING LENGTH: EOT @ 4367.34'



FRAC JOB

4/05/84 5024'-5043' **Frac D1 sand as follows:** 89,500# 20/40 sand in 655 bbls frac fluid. Treated @ avg press of 2100 psi w/avg rate of 31 BPM. ISIP 2160 psi. Flushed to perfs.

10/09/90 5024'-5043' **Reperf D1 zone.**

10/13/90 **Acidize D1 w/ 100 gal 15% HCl + 60% N2.**

4/19/94 **Put on Injection.**

4/18/01 **Convert to producer.**

12/18/02 5024'-5043' **Squeezed perfs**

12/18/02 5911'-6273' **Frac BS and CP sands as follows:** 197,938# 20/40 sand in 1005 bbls Viking I-25 fluid. Treated @ avg. pressure of 3330 psi w/avg. rate of 15.2 BPM. ISIP - 2200 psi. Calc. flush: 1562 gals. Actual flush: 1437 gals.

12/20/02 5444'-5634' **Frac A and LODC sands as follows:** 93,076# 20/40 sand in 512 bbls Viking I-25 fluid. Treated @ avg. pressure of 3950 psi w/avg. rate of 15.0 ISIP - 3700 psi. Calc. flush: 1451 gals. Actual flush: 42 gals.

12/21/02 5190'-5344' **Frac B and C sands as follows:** 60,044# 20/40 sand in 305 bbls Viking I-25 fluid. Treated @ avg. pressure of 3830 psi w/ avg. rate of 15.0 BPM. ISIP - 2750 psi. Calc. flush: 1365 gals. Actual flush: 1283 gals.

12/22/02 4432'-4577' **Frac GB sands as follows:** 26,820# 20/40 sand in 121 bbls Viking I-25 fluid. Treated @ avg. pressure of 2550 psi w/avg. rate of 24.5 BPM. ISIP - 3300 psi. Calc. flush: 4432 gals. Actual flush: 3570 gals.

10/08/13 5024'-5038' squeezed

10/09/13 5040'-5043' squeezed

5190'-5193'

5203'-5207'

5258'-5261'

5279'-5284'

5340'-5344'

5444'-5450'

5502'-5521'

5596'-5603'

5629'-5634'

5911'-5919'

5947'-5962'

5996'-5999'

6011'-6015'

6024'-6028'

6031'-6034'

6088'-6094'

6219'-6236' reperf

6246'-6252'

6267'-6273'

Top of fill @ 6345'

PBTD @ 6350'

TD @ 6400'

PERFORATION RECORD

Date	Interval	Tool	Holes
3/31/84	6219'-6236'	1 JSPF	17 holes
4/04/84	5040'-5043'	1 JSPF	04 holes Squeeze 12/02
4/04/84	5024'-5038'	1 JSPF	14 holes Squeeze 12/02
10/09/90	5040'-5043'	3 JSPF	12 holes
10/09/90	5024'-5038'	3 JSPF	42 holes
12/18/02	6267'-6273'	4 JSPF	24 holes
12/18/02	6246'-6252'	4 JSPF	24 holes
12/18/02	6219'-6236'	5 JSPF	85 holes reperf
12/18/02	6088'-6094'	4 JSPF	24 holes
12/18/02	6031'-6034'	4 JSPF	28 holes
12/18/02	6024'-6028'	4 JSPF	28 holes
12/18/02	6011'-6015'	4 JSPF	16 holes
12/18/02	5996'-5999'	4 JSPF	12 holes
12/18/02	5947'-5962'	4 JSPF	92 holes
12/18/02	5911'-5919'	4 JSPF	92 holes
12/18/02	5629'-5634'	4 JSPF	20 holes
12/18/02	5596'-5603'	4 JSPF	28 holes
12/18/02	5502'-5521'	4 JSPF	76 holes
12/18/02	5444'-5450'	4 JSPF	24 holes
12/18/02	5340'-5344'	4 JSPF	16 holes
12/18/02	5279'-5284'	4 JSPF	32 holes
12/18/02	5258'-5261'	4 JSPF	32 holes
12/18/02	5203'-5207'	4 JSPF	16 holes
12/18/02	5190'-5193'	4 JSPF	12 holes
12/18/02	4570'-4577'	4 JSPF	28 holes
12/18/02	4432'-4436'	4 JSPF	16 holes



Monument Butte Fed. 8-34-8-16
 2059' FNL & 701' FEL
 SENE Section 34-T8S-R16E
 Duchesne Co, Utah
 API #43-013-30843; Lease #U-16535

Part 13 Cover Letter

REQUIREMENTS FOR STIMULATING THE INJECTION ZONE USING INJECTION WELLS

Well Name: 8-34-8-16
 API#: 4301330843
 UIC Permit#: UT22197-00000

Procedure Description:

Per Section 13 of the area wide permit, Newfield requests permission to perform a polymer treatment on the referenced well. The well is directly connected to one or more producers resulting in water cycling from injector to producer(s). The purpose of the proposed work is to inject polymer into the pre-existing fracture network to improve sweep efficiency, thereby increasing recoverable reserves in the pattern. The zone(s) to be treated were identified via RTS logs.

Proposed Injection Fluids:

This treatment will be pumped with fresh (Johnson) water as a base fluid. The gel polymer solution is created when dry polyacrylamide is mixed in water and cross-linked with a very low concentration of a safe and non-hazardous chromium acetate chemical. The entire gel solution, which is about 99.5% water, is blended on the surface with special equipment and can usually be created with fresh, KCL or produced brine water. The mixture is blended with special equipment (on-the-fly) and continuously injected into the reservoir in a liquid phase for the duration of the treatment. The lower the polymer concentration, the weaker the gel; so as polymer concentration is increased, the resulting gels become stronger. The strength and volume of gel pumped is based on reservoir/well specifics and experience.

Proposed Fluid Volumes*:

Volume, bbls	Polymer, PPM	Polymer, lbs	X-link Ratio	X-linker, lbs
1500	8000	4200	0.4	911

*Volumes subject to change "on-the-fly". Treatment will be preceded and followed by a water flush.

Proposed Injection Pressure:

The proposed max surface pressure for this treatment is 3000 psi. While pumping polymer there are significant friction pressure drops down tbg, across perms, and in the near-wellbore region. If the job was performed at or below the MAIP, surface pressure would be insufficient to overcome friction losses in the system. Consequently, the job cannot be pumped without exceeding surface MAIP.

Well Name:	8-34-8-16
API#:	4301330843
Top Perf:	4432
Btm Perf:	6273
PBTD:	6345
Polymer Target Top:	5911
Polymer Target Btm:	5919
Frac Grad:	0.75

- 1 Spot FB tank on location and FB minimum 24 hrs.
*Equip tank with H2S sensor.
- 2 MIRU-WOR and hold safety meeting.
- 3 Drop SV and test tubing to 3000 psi.
- 4 ND WH & NU BOPs.
- 5 Release injection packer.
- 6 TOO H & LD pkr and BHA.
- 7 MU RBP and service pkr.
- 8 TIH w/plug and pkr.
- 9 Set plug @ +/- 5979'.
- 10 Set pkr @ +/- 5949' and test to 3000 psi for 15 minutes.
- 11 Release pkr and POOH to +/- 5861'.
- 12 ND BOPs and set pkr w/15K compression.
- 13 NU WH.
- 14 RDMO-WOR.
- 15 MIRU EOGA equipment and hold safety meeting.
- 16 Test lines to 3000 psi.
- 17 Pump polymer job per EOGA recommendation.
* Attempt to stay below 1861 psi during treatment.
* If pressure climbs, max pressure to place job is 3000 psi.
* Call engineer before exceeding MAIP.
* Record casing pressure throughout treatment.
- 18 RDMO EOGA equipment.
- 19 Leave well shut-in per EOGA recommended time.
- 20 MIRU-WOR.
- 21 ND WH & NU BOPs.
- 22 Release service pkr.
- 23 TIH and release RBP.
- 24 TOO H w/pkr & RBP and LD same.
- 25 MU BHA on 2-7/8", 6.5# J-55 tbg as follows:
 - a. WL re-entry guide
 - b. 2-3/8" XN Nipple
 - c. 4' tbg sub
 - d. 5-1/2" x 2-7/8" Arrowset Pkr (dressed for 15.5# csg)
 - e. On/Off tool
 - f. 2-7/8" PSN
 - g. 2-7/8" tbg to surface

- 26 TIH w/BHA and tbg.
- 27 Pump 15 bbls pad and drop SV.
- 28 Pump SV to PSN and pressure test tbg to 3000 psi.
 - a. 100% test for 30 minutes.
- 29 Retrieve SV w/SL & overshot.
- 30 Spot pkr fluid (fresh wtr w/corrosion inhibitor) in annulus.
- 31 ND BOPs and set pkr w/15K tension @ +/- 4382'.
- 32 NU WH.
- 33 Top off annulus w/pkr fluid if necessary.
- 34 Pressure test casing to 1400 psi.
 - a. Must have 100% test for 30 minutes.
- 35 Commence injection after EPA authorization.

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: U-16535
1. TYPE OF WELL Water Injection Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		7. UNIT or CA AGREEMENT NAME: GMBU (GRRV)
3. ADDRESS OF OPERATOR: Rt 3 Box 3630, Myton, UT, 84052		8. WELL NAME and NUMBER: MONUMENT FED 8-34
PHONE NUMBER: 435 646-4825 Ext		9. API NUMBER: 43013308430000
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2059 FNL 0701 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENE Section: 34 Township: 08.0S Range: 16.0E Meridian: S		9. FIELD and POOL or WILDCAT: MONUMENT BUTTE
		COUNTY: DUCHESNE
		STATE: UTAH

11.


CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 1/8/2015	<input type="checkbox"/> ALTER CASING
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS
	<input type="checkbox"/> CHANGE WELL STATUS
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS
	<input type="checkbox"/> DEEPEN
	<input type="checkbox"/> FRACTURE TREAT
	<input type="checkbox"/> NEW CONSTRUCTION
	<input type="checkbox"/> OPERATOR CHANGE
	<input type="checkbox"/> PLUG AND ABANDON
	<input type="checkbox"/> PLUG BACK
	<input type="checkbox"/> PRODUCTION START OR RESUME
	<input type="checkbox"/> RECLAMATION OF WELL SITE
	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> TEMPORARY ABANDON
	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> WATER SHUTOFF
	<input type="checkbox"/> SI TA STATUS EXTENSION
	<input type="checkbox"/> WILDCAT WELL DETERMINATION
	<input checked="" type="checkbox"/> OTHER
	OTHER: Workover / Polymer

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

The above subject well had workover procedures performed (polymer squeeze), attached is a daily status report. On 01/06/2015 Richard Powell with the State of Utah was contacted concerning the MIT on the above listed well. On 01/08/2015 the csg was pressured up to 1219 psig and charted for 30 minutes with no pressure loss. The well was not injecting during the test. The tbq pressure was 0 psig during the test. There was not a State representative available to witness the test.

**Accepted by the
Utah Division of
Oil, Gas and Mining**

Date: January 20, 2015
By: 

NAME (PLEASE PRINT) Lucy Chavez-Naupoto	PHONE NUMBER 435 646-4874	TITLE Water Services Technician
SIGNATURE N/A	DATE 1/14/2015	

Mechanical Integrity Test Casing or Annulus Pressure Test

Newfield Production Company**Rt. 3 Box 3630
Myton, UT 84052
435-646-3721**

Witness: _____ **Date** 1/8/15 **Time** 9:30 am pm
Test Conducted by: IRAKI LASA
Others Present: _____

Well: MONUMENT FED. 8-34-8-16
SE/NE SEC 34, T8S, R16E
UTU-16585, UTU87588X
Well Location: DUCHESNE COUNTY, UTAH

Field: GREATER MONUMENT BUTTE**API No:** 4301330843

<u>Time</u>	<u>Casing Pressure</u>	
0 min	<u>14.2</u>	psig
5	<u>1,223.8</u>	psig
10	<u>1,222.4</u>	psig
15	<u>1,221.2</u>	psig
20	<u>1,219.6</u>	psig
25	<u>1,218.4</u>	psig
30 min	<u>1,219.4</u>	psig
35	_____	psig
40	_____	psig
45	_____	psig
50	_____	psig
55	_____	psig
60 min	_____	psig

Tubing pressure: 0 psig


Result: Pass **Fail**

Signature of Witness: _____

Signature of Person Conducting Test: IRAKI LASA

MF 8-34-8-16 (MIT After Workover Rig)

1/8/2015 9:25:57 AM



NEWFIELD

Schematic

Well Name: Mon 8-34-8-16


Surface Legal Location 34-8S-16E				API/UWI 43013308430000	Well RC 500151476	Lease	State/Province Utah	Field Name GMBU CTB4	County DUCHESNE
Spud Date 2/28/1984	Rig Release Date 3/9/1984	On Production Date 4/19/1984	Original KB Elevation (ft) 5,614	Ground Elevation (ft) 5,628	Total Depth All (TVD) (ftKB)		PBDT (All) (ftKB) Original Hole - 6,350.0		

Most Recent Job

Job Category Recompletion	Primary Job Type Other Stimulation	Secondary Job Type N/A	Job Start Date 12/2/2014	Job End Date 1/8/2015
------------------------------	---------------------------------------	---------------------------	-----------------------------	--------------------------

TD: 6,400.0

Vertical - Original Hole, 1/12/2015 8:55:20 AM



NEWFIELD**Newfield Wellbore Diagram Data
Mon 8-34-8-16**

Surface Legal Location 34-8S-16E		API/UWI 43013308430000		Lease	
County DUCESNE		State/Province Utah		Field Name GMBU CTB4	
Well Start Date 2/28/1984		Spud Date 2/28/1984		Final Rig Release Date 3/9/1984	
Original KB Elevation (ft) 5,614		Ground Elevation (ft) 5,628		On Production Date 4/19/1984	
Total Depth (ftKB) 6,400.0		Total Depth All (TVD) (ftKB)		PBSD (All) (ftKB) Original Hole - 6,350.0	

Casing Strings

Csg Des	Run Date	OD (in)	ID (in)	Wt/Len (lb/ft)	Grade	Set Depth (ftKB)
Surface	2/29/1984	8 5/8	8.097	24.00	J-55	293
Production	3/9/1984	5 1/2	4.892	17.00	J-55	6,388

Cement**String: Surface, 293ftKB 2/29/1984**

Cementing Company		Top Depth (ftKB) 14.0	Bottom Depth (ftKB) 302.0	Full Return?	Vol Cement Ret (bbl)
Fluid Description +2% CaCl + 1/4#/sk flocele		Fluid Type Lead	Amount (sacks) 210	Class G	Estimated Top (ftKB) 14.0

String: Production, 6,388ftKB 3/9/1984

Cementing Company		Top Depth (ftKB) 3,284.0	Bottom Depth (ftKB) 6,400.0	Full Return?	Vol Cement Ret (bbl)
Fluid Description		Fluid Type Lead	Amount (sacks) 150	Class Hifill	Estimated Top (ftKB) 3,284.0
Fluid Description		Fluid Type Tail	Amount (sacks) 325	Class Gypseal	Estimated Top (ftKB) 4,800.0

String: <String?> 12/14/2002

Cementing Company BJ Services Company		Top Depth (ftKB) 5,023.5	Bottom Depth (ftKB) 5,043.5	Full Return?	Vol Cement Ret (bbl)
Fluid Description W/ .75% FL-62 & .2% SMS		Fluid Type Squeeze	Amount (sacks) 100	Class G	Estimated Top (ftKB) 5,023.5

Tubing Strings

Tubing Description					Run Date		Set Depth (ftKB)	
Tubing					1/5/2015		4,366.2	
Item Des	Jts	OD (in)	ID (in)	Wt (lb/ft)	Grade	Len (ft)	Top (ftKB)	Btm (ftKB)
Stretch Correction	1	2 7/8				0.44	14.0	14.4
Tubing	134	2 7/8	2.441	6.50	J-55	4,335.96	14.4	4,350.4
Pump Seating Nipple	1	2 7/8	2.270			1.10	4,350.4	4,351.5
On-Off Tool	1	4.515	1.875			1.45	4,351.5	4,353.0
Arrowset 1-X Packer	1	4 5/8	2.441			7.35	4,353.0	4,360.3
Cross Over	1	3.635	1.991			0.40	4,360.3	4,360.7
Tubing Pup Joint	1	2 3/8	1.991			4.15	4,360.7	4,364.9
XN Profile Nipple	1	2 3/8	1.875			0.91	4,364.9	4,365.8
Wireline Guide	1	3 1/8	1.991			0.39	4,365.8	4,366.2

Rod Strings

Rod Description		Run Date			Set Depth (ftKB)		
Item Des	Jts	OD (in)	Wt (lb/ft)	Grade	Len (ft)	Top (ftKB)	Btm (ftKB)

Perforation Intervals

Stage#	Zone	Top (ftKB)	Btm (ftKB)	Shot Dens (shots/ft)	Phasing (*)	Nom Hole Dia (in)	Date
6	GB2, Original Hole	4,432	4,436	4			12/18/2002
6	GB6, Original Hole	4,570	4,577	4			12/18/2002
1	D1, Original Hole	5,024	5,038	1			4/4/1984
2	D1, Original Hole	5,024	5,038	3			10/9/1990
1	D1, Original Hole	5,040	5,043	1			4/4/1984
2	D1, Original Hole	5,040	5,043	3			10/9/1990
5	C, Original Hole	5,190	5,193	4			12/18/2002
5	C, Original Hole	5,203	5,207	4			12/18/2002
5	B1, Original Hole	5,258	5,261	4			12/18/2002
5	B1, Original Hole	5,279	5,284	4			12/18/2002
5	B2, Original Hole	5,340	5,344	4			12/18/2002
4	A.5, Original Hole	5,444	5,450	4			12/18/2002
4	A3, Original Hole	5,502	5,521	4			12/18/2002
4	LODC, Original Hole	5,596	5,603	4			12/18/2002
4	LODC, Original Hole	5,629	5,634	4			12/18/2002
3	CP.5, Original Hole	5,911	5,919	4			12/18/2002

NEWFIELD

Newfield Wellbore Diagram Data Mon 8-34-8-16

**Perforation Intervals**

Stage#	Zone	Top (ftKB)	Btm (ftKB)	Shot Dens (shots/ft)	Phasing (*)	Nom Hole Dia (in)	Date
3	CP1, Original Hole	5,947	5,962	4			12/18/2002
3	CP2, Original Hole	5,996	5,999	4			12/18/2002
3	CP3, Original Hole	6,011	6,015	4			12/18/2002
3	CP3, Original Hole	6,024	6,028	4			12/18/2002
3	CP3, Original Hole	6,031	6,034	4			12/18/2002
3	CP4, Original Hole	6,088	6,094	4			12/18/2002
	BS, Original Hole	6,219	6,236	1			3/31/1984
3	BS, Original Hole	6,219	6,236	4			12/18/2002
3	BS, Original Hole	6,246	6,252	4			12/18/2002
3	BS, Original Hole	6,267	6,273	4			12/18/2002

Stimulations & Treatments

Stage#	ISIP (psi)	Frac Gradient (psi/ft)	Max Rate (bbl/min)	Max PSI (psi)	Total Clean Vol (bbl)	Total Slurry Vol (bbl)	Vol Recov (bbl)
1	2,160		31.0	2,650			
2	2,700						
3	2,200	0.8	15.2	3,820			
4	3,700		15.2	4,610			
5	2,750	0.962	15.0	4,610			
6	3,300		24.8	2,980			
7							

Proppant

Stage#	Total Prop Vol Pumped (lb)	Total Add Amount
1		Proppant Sand 89500 lb
2		
3		Proppant Sand 197938 lb
4		Proppant Sand 99421 lb
5		Proppant Sand 60044 lb
6		Proppant Sand 26820 lb
7		

NEWFIELD**Job Detail Summary Report****Well Name: Mon 8-34-8-16****Jobs**

Primary Job Type Other Stimulation	Job Start Date 12/2/2014	Job End Date 1/8/2015
---------------------------------------	-----------------------------	--------------------------

Daily Operations

Report Start Date 12/2/2014	Report End Date 12/2/2014	24hr Activity Summary MIRU
Start Time 06:00	End Time 07:00	Comment Crew Travel & Safety MTG
Start Time 07:00	End Time 09:00	Comment Load out & move from ASH 14-11 To MON BUTTE FED 8-34, MIRU Same
Start Time 09:00	End Time 14:45	Comment Flow back well, Flowed back 140 BBLS Oil & 160 BBLS H2O
Start Time 14:45	End Time 17:00	Comment ND Wellhead, Strip on 5000# BOPS, RU Floor & TBG Works, REL 5 1/2" Arrowset-1 PKR, CWI
Start Time 17:00	End Time 18:00	Comment Crew Travel
Report Start Date 12/3/2014	Report End Date 12/3/2014	24hr Activity Summary TOOH W/ PROD PKR, TIH W/ Bit & Scraper
Start Time 06:00	End Time 07:00	Comment Crew Travel & Safety MTG
Start Time 07:00	End Time 09:30	Comment Flush TBG W/ 40 BBLS H2O, TOOH W/ 134 JTS 2 7/8" TBG, LD 2 3/8" Reentry guide, XN Nipple, 4' 2 3/8" TBG SUB, X-over, 5 1/2" Arrowset-1 PKR, On/off tool & PSN, Stopped once & flushed TBG W/ 30 BBLS H2O
Start Time 09:30	End Time 12:45	Comment PU & TIH W/ 5 1/2" Bit & Scraper PSN & 134 JTS 2 7/8" TBG, CONT PU 61 JTS 2 7/8" TBG Tag fill @ 6320' LD 10 JTS EOT @ 5994
Start Time 12:45	End Time 13:30	Comment CIRC SV To PSN, Test TBG To 3000 PSI-OK, RU & RIH W/ Sandline RET SV, POOH & Rack out sandline 1:30 TOOH W/ 185 JTS 2 7/8" TBG, LD 5 1/2" Bit & Scraper
Start Time 13:30	End Time 15:30	Comment PU & TIH W/ 5 1/2" RBP, RH, 4' 2 3/8" TBG SUB, X-Over 5 1/2" PKR & 134 JTS 2 7/8" TBG, EOT @ 4356', CW
Start Time 15:30	End Time 16:30	Comment Crew Travel
Report Start Date 12/4/2014	Report End Date 12/4/2014	24hr Activity Summary Flush Tbg, Cont TIH Tbg
Start Time 06:00	End Time 07:00	Comment C/Trvl & Safety Mtg
Start Time 07:00	End Time 10:00	Comment Flush TBG W/ 30 BBLS H2O, CONT TIH W/ 52 JTS 2 7/8" TBG, Set RBP & 5990' & PKR @ 5968', Test tools to 3000 PSI For 30 MIN-Good test, REL PKR, PUH & Set @ 5872', Land TBG W/ Well head, RDMO @ 10:00
Report Start Date 12/13/2014	Report End Date 12/15/2014	24hr Activity Summary Polymer Treatment Treatment pumped continuously
Start Time 07:00	End Time 20:00	Comment Completed polymer injection and followed with a 203 barrel water flush. Injected a total of 1507 barrels of gelant that has consisted of 504 bbls @ 5000 ppm, 495 bbls @ 3500 ppm, 252 bbls @ 5000 ppm, and 256 bbls @ 8000 ppm polymer concentration. The WHP reached a max of 2525 psi and fell to 2300 psi by the end of the water flush. We performed a 30 minute fall off test and saw the pressure fall to 2200 psi.
Report Start Date 12/30/2014	Report End Date 12/30/2014	24hr Activity Summary LOAM, RU RIG & XO TBG EQUIP
Start Time 06:00	End Time 07:00	Comment Crew Travel & Safety Mtg

NEWFIELD**Job Detail Summary Report****Well Name: Mon 8-34-8-16**

Start Time	End Time	Comment
07:00	09:00	LOAM from 14-23-9-16 to 8-34-8-16
Start Time	End Time	Comment
09:00	13:00	RU rig & XO to tbg equip, Thaw well head to bleed down well & ND well head, Release PKR to let well flow up csg & pump 40 bbls down tbg. NU BOPs & TIH w/4 jts tbg to Retrieve Plug, Release plug & pump 30 bbls down tbg & take lunch break.
Start Time	End Time	Comment
13:00	17:30	TOOH LD tbg total of 51 jts, Cont TOOH w/tbg to derick w/67 stands, total of 134 jts, Talley on TOOH, TIH w/BHA as follows, 2-3/8" XN-Nipple, 4" pup jt w/XO, Stacked Oil tools PKR, On/Off tool, 2-7/8" PSN, 74 jts tbg, MU 10' sub & SWIOW. SDFN @5:30pm ready to Finish TIH w/tbg.
Start Time	End Time	Comment
17:30	18:30	Crew Travel
Report Start Date	Report End Date	24hr Activity Summary
1/5/2015	1/5/2015	Cont TIH w/ Tbg, wait on water, Drop SV
Start Time	End Time	Comment
06:00	07:00	Crew Travel & Safety Mtg
Start Time	End Time	Comment
07:00	12:00	Thaw well head & bleed down to tank, pump 10 bbls down csg to thaw tbg, tbg unplugged, pump 30 bbls hot down tbg, Cont TIH w/tbg total of 134 jts tbg, wait on water from 10-12
Start Time	End Time	Comment
12:00	14:30	Pump 10 bbls down tbg, Drop SV & pump down w/20 bbls. Wont Pressure up past 1800psi, PU & RIH w/sand line & tag SV @4000', push down to PSN @4346', POOH w/sand line & try to pressure up again, wont go past 2300psi, pump 20 bbls down csg to try & flush the SV clean. Pump another 10bbls down tbg willl pressure up to 3000 but wont hold pressure. PU & RIH w/sand line & Retrieve SV, POOH w/sand line & flush tbg w/30 bbls & drop New SV, pump down w/10 bbls & pressured up to 3000psi, wait for 30 min test.
Start Time	End Time	Comment
14:30	17:30	Gained 300 psi bleed down to 2800 & watch pressure, Gained 200 psi & held @3000psi good test, bleed down tbg. PU & RIH w/sand line to fish SV @ PSN, POOH w/sandline & RD floor & ND BOPs, NU Injection tree & SWION. SDFN @5:30pm Ready to pump PKR fluid & test csg.
Start Time	End Time	Comment
17:30	18:30	Crew Travel
Report Start Date	Report End Date	24hr Activity Summary
1/8/2015	1/8/2015	Conduct MIT
Start Time	End Time	Comment
09:30	10:00	On 01/06/2015 Richard Powell with the State of Utah was contacted concerning the MIT on the above listed well. On 01/08/2015 the csg was pressured up to 1219 psig and charted for 30 minutes with no pressure loss. The well was not injecting during the test. The tbg pressure was 0 psig during the test. There was not a State representative available to witness the test.



**CROSS-LINKED POLYMER GEL
WATER REDISTRIBUTION TREATMENT
JOB LOG AND SUMMARY PREPARED FOR**



**MONUMENT BUTTE FIELD
WELL NO. 8-34-8-16
DUCHESNE COUNTY, UTAH**

December 16, 2014



BULK POLYMER GEL TREATMENT


Morning Progress Report

Company Name: Newfield Exploration
Field Name: Monument Butte
Well Name: 8-34-8-16

Location: Duchesne Co., UT
Date: 12/16/2014
Est. Cum. Cost: \$30,000

The following is the most recent information available for the bulk polymer gel treatment that is in progress at the above captioned well.

Stage No.	Begin Date	Begin Time	End Date	End Time	Polymer		Cross-linker		Gel Bbls.	WHP (psi)		BHP (psi)		Rate (BPM)		Comments
					Ppm	Lbs.	Ratio	Lbs.		Begin	End	Begin	End	Begin	End	
1	12/13/2014	7:00 AM	12/13/2014	11:00 AM	0	0		0	0	1200	2100	3292	4192	0.50	0.50	100 barrels water
2	12/13/2014	11:00 AM	12/14/2014	3:48 AM	5000	881	40	192	504	2100	2400	4192	4492	0.50	0.50	
3	12/14/2014	3:48 AM	12/14/2014	8:18 PM	3500	606	40	132	495	2400	2400	4492	4492	0.50	0.50	
4	12/14/2014	8:18 PM	12/15/2014	4:42 AM	5000	441	40	96	252	2400	2425	4492	4517	0.50	0.50	
5	12/15/2014	4:42 AM	12/15/2014	1:14 PM	8000	716	40	156	256	2425	2525	4517	4617	0.50	0.50	
6	12/15/2014	1:14 PM	12/15/2014	8:00 PM	0	0		0	0	2525	2300	4617	4392	0.50	0.50	203 barrels water
Totals						2644		575	1507							






Project Engineer - Jay Portwood
P.O. Box 2230 Keller, TX 76244-2230
817-431-6936 (off) 817-431-6937 (fax)
817-312-1093 (cell)

PROJECT INFORMATION

Company Name:	Newfield Exploration	MD to Top Perforation (ft.):	4432	EOT (ft.):	4367
Field Name:	Monument Butte	MD to Btm Perforation (ft.):	6273	Packer (ft.):	4357
Well Name:	8-34-8-16	MD to Mid-Perf (ft.):	5353	Tbg Size:	2.875"
Injector or Producer:	Injector	BHP Tool Depth (ft.):	NA	Tbg. Cap. (bbbls./ft.):	0.00538
County/State:	Duchesne/Utah	Type Mix Water Used:	Produced	Tbg. Vol. (bbbls.):	23.49
Polymer Unit No.:	1	Mix Water Specific Gravity:	1.09	Csg Size:	5.5", 15.5#
Polymer Unit Operators:	Paul Larson (day) 785-346-6281 / Vance Garner (night) 785-346-8070	Mix Water Pressure Gradient (psi per ft.):	0.472	Csg. Cap. (bbbls./ft.):	0.0238
Generator Used (Yes/No):	Yes	Expect Positive WHP @ BHP of:	INVALUE!	Csg Vol. bbbls. (Pkr. to Plug):	45.3628
Customer Contact:	Garrett Worrell 303-382-4492 (off) 435-401-1319 (cell)	Calculated Static BHP (psig):	2400 est	Total Well Vol. (bbbls.):	68.96

Date	Time	Elapsed Time Between Readings (Mins.)	Injection Rate		Total Cum. Injection (bbls.)	Stage Cum. Injection (bbls.)	Tubing Pressure (psig)	PSIG per Bbl Injected	PSIG per Hour Injected	Bottomhole Conditions Pressure		Halt Plot Cum. psi-time	Injectivity Ratio (Psi ÷ Rate)	Δp	Injectivity Index BPD/(Calc. BHP-Static BHP) (BPD per psig)	Pressure Gradient (psig per ft.)	Polymer Concentration (ppm)	Cross-linker Ratio (x:1)	Total Cum. Polymer (lbs.)	Stage Cum. Polymer (lbs.)	Total Cum. X-linker (Lbs.)	Stage Cum. X-linker (Lbs.)	Casing Pressure (psig)	Comments
			BPD	BPM						Actual Reading (psig)	Calculated to Top Perforation (psig)													
13-Dec-14	7:00 AM	0	0	0	0	0	560	0.00	0.00	NA	2652	0	0	0	0.00	0	0	0	0	0	0	0	1100	Static Pressure
13-Dec-14	7:40 AM	0:40	720	0.50	0	0	1200	0.000	0.00	NA	3292	0	0	0	0.81	0	0	0	0	0	0	0	1100	Begin water pre-flush
13-Dec-14	8:00 AM	0:20	727	0.51	10	10	1675	47.030	1425.00	NA	3767	33500	2.30	675	0.53	0.70	0	0	0	0	0	0	1100	
13-Dec-14	9:00 AM	1:00	722	0.50	40	40	2000	10.797	325.00	NA	4092	135000	2.77	1,000	0.43	0.76	0	0	0	0	0	0	300	
13-Dec-14	10:00 AM	1:00	722	0.50	70	70	2100	3.322	100.00	NA	4192	279500	2.91	1,100	0.40	0.78	0	0	0	0	0	0	300	
13-Dec-14	11:00 AM	1:00	713	0.50	100	100	2100	0.000	0.00	NA	4192	405500	2.95	1,100	0.40	0.78	0	0	0	0	0	0	300	
13-Dec-14	11:00 AM	0:00	720	0.50	100	0	2100	0.000	0.00	NA	4192	405500	2.92	1,100	0.40	0.78	5000	40	0	0	0	0	300	Begin 5,000 ppm polymer gel solution
13-Dec-14	12:00 PM	1:00	725	0.50	130	30	2125	0.828	25.00	NA	4217	533000	2.93	1,125	0.40	0.79	5000	40	53	53	11	11	300	
13-Dec-14	1:00 PM	1:00	718	0.50	160	60	2200	2.508	75.00	NA	4292	665000	3.07	1,200	0.38	0.80	5000	40	105	105	23	23	300	
13-Dec-14	2:00 PM	1:00	725	0.50	190	90	2275	2.483	75.00	NA	4367	801500	3.14	1,275	0.37	0.82	5000	40	158	158	34	34	300	
13-Dec-14	3:00 PM	1:00	715	0.50	220	120	2350	2.517	75.00	NA	4442	942500	3.29	1,350	0.35	0.83	5000	40	210	210	46	46	300	
13-Dec-14	4:00 PM	1:00	726	0.50	250	150	2390	1.322	40.00	NA	4482	1085900	3.29	1,390	0.35	0.84	5000	40	263	263	57	57	300	
13-Dec-14	5:00 PM	1:00	716	0.50	280	180	2390	0.000	0.00	NA	4482	1229300	3.34	1,390	0.34	0.84	5000	40	315	315	68	68	300	
13-Dec-14	6:00 PM	1:00	718	0.50	310	210	2390	0.000	0.00	NA	4482	1372700	3.33	1,390	0.34	0.84	5000	40	367	367	80	80	300	
13-Dec-14	7:00 PM	1:00	725	0.50	340	240	2390	0.000	0.00	NA	4482	1516100	3.30	1,390	0.35	0.84	5000	40	420	420	91	91	300	
13-Dec-14	8:00 PM	1:00	718	0.50	370	270	2390	0.000	0.00	NA	4482	1659500	3.33	1,390	0.34	0.84	5000	40	472	472	103	103	300	
13-Dec-14	9:00 PM	1:00	725	0.50	400	300	2390	0.000	0.00	NA	4482	1802900	3.30	1,390	0.35	0.84	5000	40	525	525	114	114	300	
13-Dec-14	10:00 PM	1:00	713	0.50	430	330	2390	0.000	0.00	NA	4482	1946300	3.35	1,390	0.34	0.84	5000	40	577	577	125	125	300	
13-Dec-14	11:00 PM	1:00	725	0.50	460	360	2390	0.000	0.00	NA	4482	2089700	3.30	1,390	0.35	0.84	5000	40	630	630	137	137	300	
14-Dec-14	12:00 AM	1:00	715	0.50	490	390	2390	0.000	0.00	NA	4482	2233100	3.34	1,390	0.34	0.84	5000	40	682	682	148	148	300	
14-Dec-14	1:00 AM	1:00	722	0.50	520	420	2390	0.000	0.00	NA	4482	2376500	3.31	1,390	0.35	0.84	5000	40	735	735	160	160	300	
14-Dec-14	2:00 AM	1:00	718	0.50	550	450	2390	0.000	0.00	NA	4482	2519900	3.33	1,390	0.34	0.84	5000	40	787	787	171	171	300	
14-Dec-14	3:00 AM	1:00	726	0.50	580	480	2390	0.000	0.00	NA	4482	2663300	3.29	1,390	0.35	0.84	5000	40	840	840	183	183	300	
14-Dec-14	3:48 AM	0:48	710	0.49	604	504	2400	0.423	12.50	NA	4492	2778500	3.38	1,400	0.34	0.84	5000	40	881	881	192	192	300	End Stage #1 @ 5000 ppm
14-Dec-14	4:48 AM	0:00	720	0.50	604	0	2400	0.000	0.00	NA	4492	2778500	3.33	1,400	0.34	0.84	3500	40	881	0	192	0	300	Begin Stage #2 @ 3500 ppm
14-Dec-14	4:00 AM	0:12	732	0.51	610	6	2400	0.000	0.00	NA	4492	2807300	3.28	1,400	0.35	0.84	3500	40	889	6	193	1	300	
14-Dec-14	5:00 AM	1:00	725	0.50	640	36	2400	0.000	0.00	NA	4492	2951300	3.31	1,400	0.35	0.84	3500	40	926	45	201	9	300	
14-Dec-14	6:00 AM	1:00	718	0.50	670	66	2400	0.000	0.00	NA	4492	3096300	3.34	1,400	0.34	0.84	3500	40	967	81	209	17	300	
14-Dec-14	7:00 AM	1:00	725	0.50	700	96	2400	0.000	0.00	NA	4492	3239300	3.31	1,400	0.35	0.84	3500	40	999	118	217	25	300	
14-Dec-14	8:00 AM	1:00	713	0.50	730	126	2400	0.000	0.00	NA	4492	3383300	3.37	1,400	0.34	0.84	3500	40	1035	154	225	33	300	
14-Dec-14	9:00 AM	1:00	722	0.50	760	156	2400	0.000	0.00	NA	4492	3527300	3.32	1,400	0.35	0.84	3500	40	1072	191	233	41	300	
14-Dec-14	10:00 AM	1:00	718	0.50	790	186	2400	0.000	0.00	NA	4492	3671300	3.34	1,400	0.34	0.84	3500	40	1109	228	241	49	300	
14-Dec-14	11:00 AM	1:00	725	0.50	820	216	2400	0.000	0.00	NA	4492	3815300	3.31	1,400	0.35	0.84	3500	40	1146	265	249	57	300	
14-Dec-14	12:00 PM	1:00	722	0.50	850	246	2400	0.000	0.00	NA	4492	3959300	3.32	1,400	0.35	0.84	3500	40	1183	302	257	65	300	
14-Dec-14	1:00 PM	1:00	706	0.49	880	276	2400	0.000	0.00	NA	4492	4103300	3.40	1,400	0.34	0.84	3500	40	1219	338	265	73	300	
14-Dec-14	2:00 PM	1:00	730	0.51	910	306	2400	0.000	0.00	NA	4492	4247300	3.29	1,400	0.35	0.84	3500	40	1256	375	273	81	300	
14-Dec-14	3:00 PM	1:00	718	0.50	940	336	2400	0.000	0.00	NA	4492	4391300	3.34	1,400	0.34	0.84	3500	40	1292	411	281	89	300	
14-Dec-14	4:00 PM	1:00	727	0.50	970	366	2400	0.000	0.00	NA	4492	4535300	3.30	1,400	0.35	0.84	3500	40	1330	449	289	97	300	
14-Dec-14	5:00 PM	1:00	716	0.50	1000	396	2400	0.000	0.00	NA	4492	4679300	3.35	1,400	0.34	0.84	3500	40	1366	485	297	105	300	
14-Dec-14	6:00 PM	1:00	716	0.50	1030	426	2400	0.000	0.00	NA	4492	4823300	3.35	1,400	0.34	0.84	3500	40	1403	522	305	113	300	
14-Dec-14	7:00 PM	1:00	725	0.50	1060	456	2400	0.000	0.00	NA	4492	4967300	3.31	1,400	0.35	0.84	3500	40	1440	559	313	121	300	
14-Dec-14	8:00 PM	1:00	715	0.50	1090	486	2400	0.000	0.00	NA	4492	5111300	3.36	1,400	0.34	0.84	3500	40	1476	595	321	129	300	
14-Dec-14	8:18 PM	0:18	712	0.49	1099	495	2400	0.000	0.00	NA	4492	5154500	3.37	1,400	0.34	0.84	3500	40	1487	606	323	131	300	End Stage #2 @ 3500 ppm
14-Dec-14	8:18 PM	0:00	720	0.50	1099	0	2400	0.000	0.00	NA	4492	5154500	3.33	1,400	0.34	0.84	5000	40	1487	0	323	0	300	Begin Stage #3 @ 5000 ppm
14-Dec-14	9:00 PM	0:42	714	0.50	1120	21	2400	0.000	0.00	NA	4492	5255300	3.37	1,400	0.34	0.84	5000	40	1523	36	331	8	300	
14-Dec-14	10:00 PM	1:00	727	0.51	1150	51	2400	0.000	0.00	NA	4492	5399300	3.30	1,400	0.35	0.84	5000	40	1576	89	343	20	300	
14-Dec-14	11:00 PM	1:00	725	0.50	1180	81	2400	0.000	0.00	NA	4492	5543300	3.31	1,400	0.35	0.84	5000	40	1629	142	354	31	300	
15-Dec-14	12:00 AM	1:00	715	0.50	1210	111	2400	0.000	0.00	NA	4492	5687300	3.36	1,400	0.34	0.84	5000	40	1681	194	365	42	300	
15-Dec-14	1:00 AM	1:00	727	0.51	1240	141	2425	0.825	25.00	NA	4517	5832800	3.33	1,425	0.34	0.84	5000	40	1734	247	377	54	300	
15-Dec-14	2:00 AM	1:00	715	0.50	1270	171	2425	0.000	0.00	NA	4517	5978300	3.39	1,425	0.34	0.84	5000	40	1786	299	388	65	300	
15-Dec-14	3:00 AM	1:00	722	0.50	1300	201	2425	0.000	0.00	NA	45													



Project Engineer - Jay Portwood
P.O. Box 2230 Keller, TX 76244-2230
817-431-6336 (off) 817-431-6337 (fax)
817-312-1033 (cell)

Company Name:		Newfield Exploration		MD to Top Perforation (ft.):		4432		EOT (ft.):		4367	
Field Name:		Monument Butte		MD to Btm Perforation (ft.):		6273		Packer (ft.):		4357	
Well Name:		8-34-8-16		MD to Mid-Perf (ft.):		5353		Tbg Size:		2.875"	
Injector or Producer:		Injector		BHP Tool Depth (ft.):		NA		Tbg. Cap. (bbls./ft.):		0.00538	
County/State:		Duchesne/Utah		Type Mix Water Used:		Produced		Tbg. Vol. (bbls.):		23.49	
Polymer Unit No.:		1		Mix Water Specific Gravity:		1.09		Csg Size:		5.5", 15.5#	
Polymer Unit Operators:		Paul Larson (day) 785-346-6281 / Vance Garner (night) 785-346-8070		Mix Water Pressure Gradient (psi per ft.):		0.472		Csg. Cap. (bbls./ft.):		0.0238	
Generator Used (Yes/No):		Yes		Expect Positive WHP @ BHP of:		#VALUE!		Csg Vol. bbls. (Pkr. to Plug):		45.3628	
Customer Contact:		Garrett Worrell 303-382-4492 (off)		435 401-1319 (cell)		2400 est		Total Well Vol. (bbls.):		68.86	

Date	Time	Elapsed Time Between Readings (Mins.)	Injection Rate		Total Cum. Injection (Bbls.)	Stage Cum. Injection Bbls.	Tubing Pressure (psig)	PSIG per Bbl	PSIG per Hour	Bottomhole Conditions Pressure		Hall Plot Cum. psi-time	Injectivity Ratio (Psi + Rate)	Δp	Injectivity Index BPD/(Calc. BHP-Static BHP) (BPD per psig)	Pressure Gradient (psig per ft.)	Polymer Concentration (ppm)	Cross-linker Ratio (x:1)	Total Cum. Polymer (lbs.)	Stage Cum. Polymer (lbs.)	Total Cum. X-linker (lbs.)	Stage Cum. X-linker (lbs.)	Casing Pressure (psig)	Comments
			BPD	BPM						Actual Reading (psig)	Calculated to Top Perforation (psig)													
15-Dec-14	6:00 PM	1:00	725	0.50	1750	143	2400	0.000	0.00	NA	4492	8328850	3.31	1,400	0.35	0.84	0		2644	0	575	0	600	
15-Dec-14	7:00 PM	1:00	708	0.49	1780	173	2400	0.000	0.00	NA	4492	8472850	3.39	1,400	0.34	0.84	0		2644	0	575	0	600	
15-Dec-14	8:00 PM	1:00	722	0.50	1810	203	2300	-3.322	100.00	NA	4392	8610850	3.18	1,300	0.36	0.82	0		2644	0	575	0	600	End water post-flush
15-Dec-14	8:00 PM	0:00	0	0.00	1810	203	2300			NA	4392	8610850		1,300			0		2644	0	575	0	575	ISIP
15-Dec-14	8:05 PM	0:05	0	0.00	1810	203	2275			NA	4367	8610850		1,275			0		2644	0	575	0	575	5 MINUTE SIP
15-Dec-14	8:10 PM	0:05	0	0.00	1810	203	2250			NA	4342	8610850		1,250			0		2644	0	575	0	550	10 MINUTE SIP
15-Dec-14	8:15 PM	0:05	0	0.00	1810	203	2225			NA	4317	8610850		1,225			0		2644	0	575	0	550	15 MINUTE SIP
15-Dec-14	8:20 PM	0:05	0	0.00	1810	203	2225			NA	4317	8610850		1,225			0		2644	0	575	0	550	20 MINUTE SIP
15-Dec-14	8:25 PM	0:05	0	0.00	1810	203	2200			NA	4292	8610850		1,200			0		2644	0	575	0	550	25 MINUTE SIP
15-Dec-14	8:30 PM	0:05	0	0.00	1810	203	2200			NA	4292	8610850		1,200			0		2644	0	575	0	550	30 MINUTE SIP

